

POPULAR SCIENCE

MONTHLY

AUGUST

5¢

See Page 42

EDGAR
FRANKLIN
MILWAUKEE
59



NEW INVENTIONS
MECHANICS
THE HOME WORKSHOP
MONEY MAKING IDEAS
450 PICTURES

Copyrighted material

32 M. P. H. STANDING STILL

BUT IT PROVES THAT MODERN CARS HAVE 3 GRADES OF PERFORMANCE

You don't really buy gasoline...you buy performance and mileage. That's why you'll be doing yourself a real favor to read the basic facts about gasoline and performance. Here's what you can expect from each grade of gasoline:—



Poor performance with "low grade" gasoline

There is no anti-knock fluid (containing tetraethyl lead) in "low grade" gasoline. Power is lost because your car dealer *must* retard the spark to prevent "knock" or "ping."



Good performance with "regular" gasoline

Most regular gasoline has in it anti-knock fluid (containing tetraethyl lead). The spark can be considerably advanced for more power without "knock" or "ping."



Best performance with gasoline containing "ETHYL"

Gasoline "with ETHYL" is highest in all-round quality. It has enough anti-knock fluid (containing tetraethyl lead) so that the spark can be *fully* advanced for maximum power and economy without "knock" or "ping."

THIS DYNAMOMETER TEST at the Ethyl Motor Clinic clearly shows the three grades of performance. Illustrated above is the rear wheel of a popular make of car on the dynamometer rollers. Three grades of gasoline are used and the differences in power and speed indicated on sensitive instruments. This test leaves no doubt that every car has three grades of performance.

ETHYL GASOLINE CORPORATION, manufacturer of anti-knock fluids used by oil companies to improve gasoline

FIRST

AT YOUR THEATRE

WITH THE NEWS of SCIENCE and INDUSTRY

SEE-HEAR POPULAR SCIENCE-ON-THE-SCREEN

IN CINE COLOR

PRODUCED BY
FAIRBANKS and CARLISLE
WITH THE COOPERATION OF
THE EDITORS OF
POPULAR SCIENCE MONTHLY

**TO SEE LATEST
RELEASE SEND
THIS COUPON TODAY**

Popular Science Monthly
353 Fourth Avenue • New York, N. Y.
(Paste on penny post card and mail today)

Please make double-sure that *latest* release of Popular
Science-On-The-Screen appears at my local theatre.

NAME

ADDRESS

NAME OF THEATRE

RAYMOND J. BROWN
EDITOR

ARTHUR WAKELING, Home Workshop Editor
ALDEN P. ARMAGNAC, Associate Editor

GEORGE H. WALTZ, Jr., Associate Editor
SYDNEY OXBERRY, Art Editor

CONTENTS for AUGUST 1938

World's Deepest Oil Well.....John E. Lodge 21

New prospecting and production methods increase Uncle Sam's fuel supply

Big Business in Miniature.....Kenneth M. Swezey 24

Youthful craftsmen organize and run dividend-paying corporations

Sword Swallower X-Rayed.....A Picture Story 29

Scientific studies give "inside dope" on feats of sideshow performers

Plane Flies 63,875 Miles in a Shed.....30

Drawing and photographs show how engineers tested a giant transport indoors

Test-Tube Forest Fires.....35

How U.S. Forest Service experimenters try out new ways to save timberlands

Learn To Sail on Your Dining Table.....E. W. Murtfeldt 36

With a model boat and an electric fan you can master the fundamentals of yachting

Twenty-One-Mile Parachute Leap.....Walter E. Burton 42

Veteran stunt man plans daring and spectacular plunge from the stratosphere


Skimmed Coal.....Drawing by B. G. Seielstad 48

Ingenious sink-and-float process removes slate from fuel and speeds production

FEATURES AND DEPARTMENTS

OUR READERS SAY—	4
NEW IDEAS FOR HOME OWNERS	12
THE MAN WITH THE NET	39
POPULAR SCIENCE QUESTION BEE	50
UN-NATURAL HISTORY	51
GUS WILSON'S MODEL GARAGE	54
THE HOME WORKSHOP	55
ADVENTURES WITH YOUR MICROSCOPE	74
HOME-LABORATORY CHEMISTRY	76
RADIO DEPARTMENT	78
AMATEUR PHOTOGRAPHY	84

COVER DESIGN BY EDGAR F. WITTMACK



Mysteries of sailing are made clear by a model boat and an electric fan. Read the article on table-top yachting on page 36

AUTOMOBILES

Headlight Tilts on Hills	27
Horse and Car in Hurdle Race	33
Busses Cleaned in 40 Seconds	34
Color Mixer Tests Car Hues	40
Windows for Your Trailer	58

AVIATION

Plane Lands on Auto	26
Odd Blimps Snare Bombers	27
Wind-Tunnel Projector	32
Test Plane Fire Hazard	40
Wind Models Aid Student Flyers	46
Archer Christens Airliner	47

LAWN AND GARDEN

Rocking Seat for Weeding	41
Porous Hose Saturates Soil	41
Fungus Spray Dyes Grass	41
Lawns Laid Like Linoleum	41

Published monthly at 353 Fourth Avenue, New York, N. Y., by Popular Science Publishing Co., Inc. A. L. Cole, President and Treasurer; Godfrey Hammond, Executive Vice President; R. C. Wilson, Vice President; John Nichols, Vice President; C. D. Freeman, Vice President; F. W. Briggs, Secretary. Entered as second-class matter Dec. 28, 1918, at the Post Office at New York under the act of March 3, 1879; additional entry as second-class matter at Dayton, Ohio. Entered as second-class matter at the Post Office Department, Canada. Printed in U. S. A. Copyright, 1938, by Popular Science Publishing Co., Inc. Single copy, 15 cents. Yearly subscriptions to United States, its possessions, and Canada, \$1.50; foreign

countries, excepting Canada, \$2. Subscribers must notify us of change of address four weeks in advance of the next publication date. Be sure to give both old and new address. The contents of this magazine must not be reprinted without permission. The editors are not responsible for unsolicited contributions, and cannot guarantee the return of such material or insure against its loss. Contributions not accompanied by sufficient postage will not be returned. In presenting numerous stories of new products of applied science, Popular Science Monthly does not underwrite the business methods of the individuals or concerns producing them. The use of Popular Science Monthly articles for stock-selling schemes is never authorized.

Nozzle Serves as Sprinkler.....	41
Rubber Hose Trains Vines.....	65
Arched Garden Gateway.....	66

MODELS

Our Ship-Model Kits.....	11
Contest-Winning Plane Model....	55
Sails for the Alabama	68
Punch Cuts Car Windows.....	88
Freeing Tight Journals.....	88
Paint for Your Models.....	88
Railway Loading Platforms.....	89
Reversing Switch for Train.....	89

NEW DEVICES FOR THE HOME

Holder for Coffee Maker.....	52
Broiler Swings from Oven.....	52
Toothbrush Guard Saves Powder	52
Tube Cap Dispenses Toothpaste..	52
Waffles Drop from New Mold.....	52
Adjustable Egg Beater.....	52
Water Heater for Tap.....	53
Mixer Expands To Fit Bowl.....	53
Refrigerator-Bottle Faucet.....	53
Built-In Electric Dishwasher.....	53
Handy Compressed Washcloths..	53
Folding Garment Rack.....	53

NEW PROCESSES AND INVENTIONS

Spring Heels for Shoes.....	26
Cigarette Match Holder.....	26
Table-Top Flower Garden.....	26
Aluminum Bow for Archers.....	32
Egg Candler Spots Chicks.....	32
Pencil Turns into Compass.....	32
Toy-Train Speed Control.....	33
Novel Eraser Holder.....	33
Skidproof Blocks for Children.....	33
Batteries Run Portable Drill.....	34
Permanent Magnets Hold Work..	39
Opener Also Weighs Letters.....	39
Treadmill Walks the Dog.....	40

Device Finds Cinders in Eye.....	40
Bridge-Table Golf Game.....	40
Vise Jaws Grip Fragile Parts.....	44
Sidewalk Signals Halt Trolleys.....	44
Whistle Made of Chewing Gum....	44
Shock Absorber for Bike Saddle....	47
Holder Guards Blasting Caps.....	47
Gas "Fireproofs" Fuel Tanks.....	47

PHOTOGRAPHY

Camera on Police Gun.....	28
Rapid-Fire Action for Camera.....	45
Teeth Operate Shutter.....	45
Camera Gun for Sportsmen.....	45
Transformer for Floodlights.....	45
Bubbleproof Developing Tank.....	45
Printing Poor Negatives.....	82
Tilt-Top Tripod Head.....	84
Adhesive Tape Lifts Glass.....	84
Dampener Washes Prints.....	84
Improvising a Sunshade.....	86
Unloading Miniature Film.....	86
Plates Stiffen Light Tripod.....	86
Enlarging Paper Held Flat.....	86
Speeding Up Your Film.....	86
Fishline Brace for Tripod.....	87

UNUSUAL FACTS AND IDEAS

Bait Seller Fills Odd Order.....	27
Fiddle Plays 300 Tones.....	27
Dikes to Halt Erosion.....	28
"Electric Ear" Tests Horns.....	28
Patient Dials for Needs.....	28
Moving Bonfire Burns Weeds.....	32
Detector Traces Phone Wires.....	33
Scientific Worm Farm.....	34
Audible Chart Teaches Music.....	34
Make Daily Pollen Census.....	39
Rolling Lab X-Rays Workers.....	44
Melons Yield Sound Effects.....	44
Ball Game for Blind Players.....	46
Analyzing a Bridge's Air.....	46

Dummy Gets Wooden Legs.....	46
Odd Stunt with Liquid Air.....	47

WOODWORKING

Bookcase Fits Under Window.....	59
Our New Fisherman's Boat.....	60
A Floating Aquaplane.....	64
Fisherman's-Boat Blueprints.....	95

IDEAS FOR THE HANDY MAN

Decorating Canoe Paddles.....	58
Horseshoe Coat Hooks.....	58
Glass Cover for Glue Can.....	58
Court Returns Tennis Balls.....	58
Handy Envelope Moistener.....	59
Burning Off Old Paint.....	59
Wind-Driven Electric Plant.....	62
Gate Built of Rough Boards.....	64
Large Magnet Holds Tools.....	65
Metallic Wall Pictures.....	65
Cleaning Mower Guards.....	65
Seltzer Puts Out Fire.....	66
Homemade Badminton Set.....	67
Use for Small Thermometer.....	67
Nonsnagging Boat Anchor.....	67
Decorative Woven Baskets.....	70
Repairs Made by Brazing.....	71
Grinder Trues Chuck Jaws.....	71
Simple Indexing Method.....	72
Roller for Drawing Board.....	72
Multiple Lathe-Tool Holder.....	72
Heavy-Duty Anvil Mounting.....	72
Longer Life for Saw Blades.....	72
Homeworkshop Guild News.....	83
Eyedropper Used as Oiler.....	86
Cleaning Clogged Sanders.....	87
Using Soldering Coppers.....	88
Tightening Saw Handles.....	88
Loosening a Balky Screw.....	88
Homemade Flexible Shaft.....	90
Vacuum Cups Easily Made.....	90
Lacing Small Machine Belts.....	94
Planing Twisted-Grain Wood.....	96
Paste Improves Molding Sand.....	97

Our Readers Say



Good Old Sodium Stearate! Now Who'd Have Thought of That?

J.P., of Kansas City, Mo., advises potassium dichromate and sulphuric acid in a hot solution (caution) for cleaning chemical glassware. This is the most common cleaning solution of the analytical laboratory, and also the most effective, but sometimes glassware may be stained by salts, such as manganous salts, which cannot be cleaned with this solution. For these, a reducing agent such as stannous chloride will work wonders. While the analytical chemists swear by the potassium dichromate-sulphuric acid solution (it removes the slight film of grease), the organic chemists swear at it. For them, nothing beats a good, hot solution of sodium stearate—to you, soap. The organic tars, resins, oils, greases, and so on, are much more easily removed by soap than by the more expensive solution.—J.A., Pocatello, Idaho.

SOAP DOES IT!



This Bit Bit Off More Than Was Expected

HERE is something that might interest your readers. I just stumbled onto it: How to bore a 1½-inch hole with a one-inch bit. I was installing a piece of one-inch tubing as a rod in my coat closet. In drilling the end blocks to support it, I carelessly used a seven-eighths-inch bit. So I made a plug, intending to fill up the hole and rebore it. Then I got the one-inch bit started, but it was a sixteenth inch off center in the plug. It wouldn't have mattered, except for the fact the plug slipped, turning with the bit and producing an eccentric. So the bit went around outside of the center, a sixteenth of an inch all around, making a hole one and an eighth inches in diameter.—B.F.O., Montevideo, Minn.

He Might Try Crossing It with a Stick of Candy

THIS devoted reader wants bigger and better asparagus! Why not? Pink grapefruit and red tangerines are popular, and so are peach-plum combinations, apricot grafts, and many others, all children of grafting. Take asparagus, and if you can return it to me with a half inch or less of stem, an all-tip flavor, at the same cost a bunch, with redoubled flavor because of increased tip area, I should consider it a fair exchange. By that I don't mean cutting the waste stem off. Grow them anew—same size, all tip! The glory of the new vegetable is all yours, but give me that asparagus!—M.G., Brooklyn, N. Y.

WHO'S GRAFTING?



He Keeps the Sand out of His Sandwiches

THAT light-duty, one-piece tent on page 79 of your July issue takes the cake—and also keeps the sand out of it on picnics. I hopped on the idea and built the tent as soon as I took the family to our seashore cottage. Although we don't have to use it as a dressing tent, we use it for about everything else you suggested. I'm back at work after a vacation, now, but I can assure you that the rest of the family is still making good use of it. Thanks to the tent, our sunburn was less severe, our picnics are less sand-and-wind blown, our naps on the beach more restful, our family parties less public, and, at the last report, none of us had yet been socked on the head with one of those rubber beach balls that land all around you like shrapnel when the would-be Dizzy Deans of the resort start warming up. Every time I use the tent, it suggests some other way in which the thing will prove useful. At this rate, I'll soon be living in the tent all the time, and saving rent—and that's not a bad idea, either. Good luck to you.—S.A.H., Norfolk, Va.

Got His Goat, but it Rammed the Point Home

THIS is about an article, "Bumper for Goats Prevents Injuries," on page 15 of your March issue. After trying vainly for an hour to separate the rams and the goats, I decided that the only logical place to attach the bumper will be to the *gluteus maximus* muscles of the farmer—or to the seat of his overalls. Try, yourself, to sift the goats and rams apart. My attempt got my goat. The possibilities in my alternative measure are at least bizarre. Overalls manufacturers might put out a line with rubber bumpers in the rear for those who raise goats, rams, or both, which have that inbred tendency to raise hell with their raisers.—A.N.C., San Francisco, Calif.

COME ON, GOAT!



Were the Fish Electrocuted, or Just Scared to Death?

BEING an electrical and radio engineer, my attention was attracted by a newspaper article that credited a lightning bolt with killing a lot of fish, which were subsequently washed up on the shore of a bay. The article went on to say that lightning striking the surface of the water electrocuted the fish. I would like to know what your readers think of my theory that lightning could not do this under ordinary circumstances, and that there must have been a waterspout which sucked the fish into its column where they were electrocuted when the lightning struck the column. These

spouts occur at rare intervals along our coast, sucking up everything reasonably light within their paths.—K.S.W., Sydney, Australia.

That Page of Camera Ideas "Clicked" with This Fan

LET me add my voice to the hearty chorus of cheers that undoubtedly is rising from thousands of your readers in response to the page of "New Aids for Camera Fans" in your July issue. It's such a good idea. I'm surprised I didn't think of it myself and write you a "squawk" for not doing it sooner. Don't tell me this is just a flash in the pan—surely you're planning to make it a regular feature. After all, if the home owners and the housewives and the radio bugs have pages of new gadgets for their useless activities, there's no excuse for you to neglect the king of hobbies, photography. And if you don't believe it's the king of hobbies, ask any camera fan! —A.M.E., St. Joseph, Mo.

US WISHBONE
CAMERA BUGS
HAVE GOT
RIGHTS!



Anyone Ever See This Strange Mineral?

RECENTLY I was doing some local prospecting in the country when I came upon a chalky-looking rock. I brought it home and found that it gave off water when heated in a closed tube. It is soft enough to scratch with your finger nail, and smells limy. On chiseling out a piece, I noticed the smell of natural gas. Then I hit the rock with a hammer and smelled it again. Every time I hit it, this gas was given off momentarily. Could any reader give me any information concerning this? Surely some of them must have encountered it somewhere.—P.J.P., London, Ontario.

It Takes a Brave Man To Stay on the Ground

THAT story of Andrew R. Boone's, about his experience in flying the "crash-proof" plane, made me want to get right into one of those sky flivvers and fly away. I had read a lot about so-called foolproof planes using one gadget or another that was supposed to make a veteran out of any fledgling, but always thought it was a lot of baloney. If it's like Boone says, a fellow would be a lot safer up in the air in one of those things, on a Sunday afternoon, than he would be (Continued on page 5)

YEAH? THE AIR WILL
BE WORSE THAN THE
ROADS



(Continued from page 4)

coaxing a jalopy along a main highway. Give me the air, where there's more room!—A.S.K., St. Paul, Minn.

Maybe You Can Unscramble This Egg Problem

M.M.'s PROBLEM about the man with 100 theater seats to fill is comparatively simple. If J.J.O., of Fanning Island, has difficulty with it, the answer is: Seventy children at ten cents admission each, nineteen women at two dollars admission, and eleven men at five dollars admission. Now, here's a problem that should give our Pacific Ocean exile a real headache. A farmer has three sons, A, B, and C. He gives A ten eggs, B thirty eggs and C fifty eggs.

TRY'N FILL A HUNDRED SEATS ON FANNING!



He sends them to town to sell their eggs at any price the three of them agree upon. If market conditions change, the boys may alter the price, but at no time are they to sell at different prices; that is, if one changes his price, the others must change theirs accordingly. Furthermore, they are told to sell all their eggs—each his own lot—but all three of them must take in the same sum of money. How did they do it?—S.B., New York City.

He Thinks the Pavement Would Get "Tired" Out

I WISH to disagree with I.K.G.'s suggestion for using old automobile tires to reinforce cement pavement. I believe that the hollow space left inside the tires would make pavement crack and crumble under the weight of heavy vehicles. And then your road would be a pretty mess, wouldn't it? Am I wrong?—C.M., Old Orchard, Me.

Those Yankees Might Fool This Reader Yet

ONE of your readers is much opposed to more dirigibles. It seems that he prefers an airplane for an ocean crossing. I wonder if he prefers a motor boat to an ocean liner. In a long-distance run, a plane is crammed with equipment and fuel, leaving the passengers only room enough for convertible seats that they are also compelled to sleep in. If, during the trip, motor trouble or other mechanical difficulties are encountered, a landing is almost always necessary, regardless of conditions. And you know how successful most forced landings are! In a helium-filled Zeppelin, forced landings are almost out of the question, because it may stay aloft as long as its gas cells are intact. The passengers are not compelled to sit in their seats, but are left at freedom to walk about in dining, smoking, reading, and amusement halls. The Germans have built dozens of Zeppelins with great success, having had

"WHY CAN'T YOU YANKS DO THE SAME?"



(Continued on page 6)

Old friends are best friends




IN 1908 . . . "When this snap was taken of me I was just getting ready to cast my first vote and had plenty to learn. The proof of that is I didn't even meet up with Union Leader tobacco 'til 5 years later. But by that time I had growed enough in sense to know a fine tobacco when I found it, and Union Leader's been my constant pal ever since."

TODAY . . . "I'm 50 now, and all of those years Union Leader's friendliness has eased the bumps. My son Ike, shown in this picture, had the good judgment to take up with Union Leader when he was only 17, which proves he's even smarter than his Old Man!"

Jacob Zonneville, Williamson, N.Y.



Union Leader



ALWAYS . . . Father and son, men have been getting deep-down smoking enjoyment out of Union Leader for over a third of a century. Mellowed with age in oaken casks, this ripe Kentucky Burley is rich in flavor and fragrance usually found in only the costlier blends. Try a tin of UNION LEADER today! It's packed with pleasure and economy!

Copyright, 1938, by P. Lorillard Co., Inc.

THE GREAT AMERICAN SMOKE

INVENTORS New FREE BOOK

48 PAGES JUST OFF THE PRESS
OVER 100 ILLUSTRATIONS



LATEST FACTS ON INVENTIONS, PATENTS, and MARKETS for INVENTIONS

The very latest information on all matters affecting your invention—all inventions. Don't act until you get this Free Book! It reveals important information on obtaining patents, establishing a market for inventions, getting financial aid, using patent to secure commercial success. 48 pages crammed full of illustrations, helpful and interesting statistics, patent office data, rulings, a detailed guide on how to patent and protect your idea.

This new book will be sent promptly—have the most up-to-date guide to the things you must know to simplify patent procedure and save time, the vital thing to you!

MAIL COUPON NOW

for Free Book and Record of Invention Blank—delay may be costly!

CLARENCE A. O'BRIEN
and HYMAN BERMAN

882 Adams Building, Washington, D.C.
Registered Patent Attorneys Before U. S. Patent Office

Please send me at once your Big Free 48-Page Book, "Patent Guide for the Inventor" and your specially prepared "Record of Invention" Form. This request does not obligate me.

Name.....

Address.....

(Please write or print plainly)

Our Readers Say

(Continued from page 5)

only one disaster since the World War. And if they are using them successfully, why can't you Yankees do the same?—R.K., Kitchener, Ontario.

Coal Is the Perfect Food —If You Happen To Be a Stove

BEING interested in biology, I'd like to correct a few of A.F.S.'s ideas about eating coal. He says that his theory is based on the proposition that the essential value of food is heat. A high-school biology textbook would have told him that some foods are for the purpose of producing energy, of which heat happens to be one form. Other foods, just as important, serve the purpose of building up and repairing body tissue. He goes on to say that Americans are wasting a lot of coal by burning it in their stoves, instead of in their bodies. He neglects the fact that while a stove or furnace does not have to worry about getting indigestion from coal, we do. Our digestive tracts find certain solids indigestible. That is the reason for cooking certain foods. A.F.S. also neglects the fact that while coal is oxidized in a furnace by the quick method known as burning, energy food in our bodies is oxidized by a much slower process. Lastly, A.F.S. states that pigs can eat a limited quantity of coal, unharmed. That doesn't prove that they derive energy from it. I've seen goats eat paper and birds eat gravel, so what?—H.W., New York City.

Benignant Peruser Indites Encomiastic Epistle

Nor long ago, I read an account of a meeting of scientists at which some one told the assembled highbrows that they would have to learn to describe their discoveries in understandable English, instead of in Mumbo-Jumbo jargon, if they expected to get anywhere. It made me realize how lucky I am to have P.S.M. to keep me posted on the latest developments in science, written so I know what it's all about. None of your two-dollar words for me!—R.A.P., Utica, N. Y.

AW, THAT'S TO HIDE THE BALONEY!



A One-Way Journey with No Stopovers

THE article in your July issue, pointing out that machines of war are tending more and more toward small size, holds water all right, according to my way of thinking. And the illustrations give a fine idea of how they'll be used. I wonder, however, about those winged bombs which "are aimed directly at their objective by lone pilots who then bail out with their parachutes." After all, to score a hit, the dare-devil aeronaut would have to stay with his mount almost to the very last moment. He jumps! Then what? He's sure to land in the hands of the enemy. He stands a good chance of setting down in the midst of the wreckage his winged bomb has created. There, he

(Continued on page 7)

SNUBBED BECAUSE OF "ADOLESCENT SKIN"?

Act now to help keep your blood free of pimple-making poisons

Don't go on being cursed by loathsome pimples. Don't make others feel ashamed of you or shun you. Find out what's the matter and correct it.

During the period of adolescence, in the years between 13 and 25, important glands are developing. This causes disturbances throughout your body. Waste poisons from the intestines often find their way into the blood . . . and may break out in ugly skin eruptions. You must help free your system of these intestinal poisons.

Thousands of young people have solved this problem—simply by eating Fleischmann's Yeast. Each cake of this fresh food contains millions of tiny, living plants that act to help you eliminate waste poisons from the body—before they can get into the blood. Your skin becomes clearer and fresher again. Many get remarkable results in 30 days or less. Don't lose time. Start eating Fleischmann's Yeast now . . . 3 cakes daily, one before each meal.

Insure and Speed Up PROSPERITY

For many months, personal competition will be tremendous. Employers—up against new problems, fighting for survival and profits—will be able to pick and choose. Naturally they will prefer the trained man—the man who has special ability. If you want to speed up your prosperity and insure your share in the business pick-up, you must prepare yourself. And your first step is to get the facts about a proven training program. Check your subject below, write your name and address in the margin, and mail this coupon today.

- | | |
|--|---|
| <input type="checkbox"/> Higher Accountancy | <input type="checkbox"/> Law: Degree of LL.B. |
| <input type="checkbox"/> Salesmanship | <input type="checkbox"/> Executive Management |
| <input type="checkbox"/> Traffic Management | <input type="checkbox"/> Commercial Law |
| <input type="checkbox"/> Industrial Management | <input type="checkbox"/> Business Corresp. |
| | <input type="checkbox"/> Business English |


LASALLE EXTENSION

Dept. 883-R

CHICAGO

Be Your Own Auto Trouble Shooter

NEW SIMPLE HANDBOOK MAKES IT EASY



A reduced drawing from AUTO KINKS showing how to repair hole in gas-line tank without soldering. Complete explanation in book.

Now you can cut down monthly repair bills and keep your car in A-1 condition by doing yourself many easy tasks completely explained in this brand new manual.

Anyone can follow the non-technical language in AUTO KINKS fully illustrated with drawings and simple diagrams, and find out just what to do no matter what goes wrong—how to make temporary or permanent repairs to the motor, carburetor, fuel line, ignition, lights, starter, radiator, chassis, running gear, body, fender, top, and even the garage.

AUTO KINKS is a complete service manual which will save you many times its cost. Besides cutting your repair bills, you will get a lot of fun out of doing these simple jobs yourself. 192 pages, full strong cloth binding, pictures on every page, only \$1.00 C.O.D. plus a few cents postage.

POPULAR SCIENCE MONTHLY—Dept. 88
353 Fourth Ave., New York, N. Y.

Send me AUTO KINKS. I agree to pay the postman \$1.00 plus a few cents postage when the book arrives. If I am not entirely satisfied with the book, I will return it to you within 5 days of receipt and you will refund my money in full.

Name.....

Address.....

City..... State.....

(Continued from page 6)

may burn alive. He'll surely be shot if he doesn't. He might better stay with his mount and ride it into its objective, where his own end would be, at least, mercifully swift. Are we to suppose that volunteers will enlist in the country's service with the foreknowledge that they are to "fight" this way?—T.N.O., Boonton, N. J.

Leg Guards for Milkmaids Have the Farmers Kicking

How're you going to keep the farm boys down on the farm if the hired girls start wearing "dairy leg guards" like the one you show in page 46 of your July issue? I'll bet that idea was thought up by some city slicker who doesn't give a hoot what becomes of agriculture. Let him put a pair of those wooden leggings on his stenographer for a few days, and see how he likes it.—R.E., Dodge City, Kans.

BY HECK!



He'll See His Fireworks And Have Them Too

THANKS for the tips in your latest issue on how to make good photographs of aerial fireworks. I intend to take a lot this year. Meanwhile, I have been using the instructions to aid me in taking night shots of lightning. The results have been spectacular. I never realized before how much the camera can see that our eyes cannot.—F.A.H., Philadelphia, Pa.

But Ants Are Bloodthirsty Little Creatures, Too

ALL this war stuff is giving me the jitters. Let's have a quiet, soothing article about life in an ant colony.—D.R., Richmond, Va.

Voice Teacher Hopes That Many Will Read Article on Speech

ALLOW me to express the pleasure I have had in reading your article on investigations into matters concerning the voice, "Odd Laboratory Tests Show How We Speak," and the hope that it will be widely read in this country. My attention was called to it by a professor of singing, and writer on the voice. I quite agree that ignorance of the vocal mechanism has been widespread, but there has been a good deal of knowledge in certain quarters all the same, though it was difficult for the possessors of it to obtain a hearing. I have often (I am seventy-five, and have been teaching singing all my life) put both my thumbs or a bundle of lint into the cavity of my hard palate to demonstrate to pupils the truth about resonance there. I was for twenty years actively engaged in the direction of an organ factory, building pipe organs so solving problems of wind, resonance, and so on, was part of my work.—J.M.L., London, England.

MI-MI-MI-M-M-M



OFFER TO YOUNG MEN Who Hanker to Smoke a Pipe



MEN: Complete smoking pleasure comes only from smoking fine tobacco, and starting under ideal conditions. Through this unusual offer we are introducing to you pipe smoking at its best.

Here's Our Offer

FIRST: Trial Packets of each of the three styles of world-famous Edgeworth, wrapped in heavy foil. Edgeworth, famous for more than 35 years, has always contained only the finest tobacco leaf on the market. We know that you cannot make good tobacco from inferior tobacco leaf any more than you can get the pleasure of choicest porterhouse steak for a rump

steak price. We gladly pay premium prices to give you a finer smoke. This costly leaf is then manufactured to the high Edgeworth standard—better tobacco, made to smoke cooler, means *no tongue bite* and permits you to enjoy fully its enhanced flavor, greater mildness and richer aroma.

SECOND: A handsome *Signature Pipe* (made by Linkman) that has been mechanically pre-smoked (already "Broken-In") with genuine Edgeworth. It's sweet and gentle from the start. Then to give you an added interest in this pipe, we engrave your *own personal signature* in gold color on the stem. No pipe so personal.

Edgeworth always carries a written guarantee of satisfaction, or money refunded. Edgeworth is on sale everywhere in convenient pocket tins at 15¢.

EDGEWORTH Smoking TOBACCO

TO GET YOUR EDGEWORTH SAMPLER KIT—JUST MAIL COUPON WITH \$1.00

LARUS & BRO. Co.,
Richmond, Va.

Enclosed please find \$1.00 for your Edgeworth Sampler Kit... Opposite is my signature to engrave on the stem of the pipe. (Please print clearly your name and address below.)

SIGNATURE

Place your normal signature clearly within exact space allotted

Name..... Address.....
City..... State..... P.S.

PLEASE SEND US YOUR DEALER'S NAME AND ADDRESS

Dealer's Name..... Address.....
City..... State.....

All Aboard!

for a Wonderful
VACATION TRIP

Auto-Glide
120 MILES
PER GALLON

Here you go!—on the most thrilling trip of your life! See other states, cities, mountains, lakes—travel 200 to 300 miles daily comfortably—only 50¢ to 75¢ a day for gas! Genuine Auto-Glide, made by a foremost engine builder, has the ruggedness, power and comfort for long trips. Extra strong welded frame. Powerful 1½ or 2 H.P. Cushman engine (2-speed transmission) climbs the steepest hills. In high, up to 35 miles an hour. Clutch makes it easy to stop at crossings, intersections, 2 or 3-wheel models. Karl-Pac model has big luggage carrier. Magneto or battery. Starter, brake, light, hand-accelerator, balloon air tires, etc.

Free Book! See your dealer or write for full details, book, Low Prices.

CUSHMAN MOTOR WORKS, Dept. C-8, Lincoln, Nebr.



Ideal for deliveries. Cuts costs 'way down.

**NO MORE
Spoiled
FILM!**

\$1.95

**NOW—PERFECT PICTURES
WITH ANY CAMERA!**

For movies or stills. Eliminates guesswork; insures perfect "shots," even in poor light. Automatically corrects for speeds, filters, subjects, etc. Case, 35¢. At all Dealers.



**Univex EXPOSURE
METER**



Secrets of Success

STORIES THAT WILL HELP YOU GET AHEAD



Learn a profitable Trade

DIESEL

COMPLETE TRAINING WITH ALL TYPES INTERNAL COMBUSTION ENGINES, ELECTRIC POWER GENERATION, Etc.

If you are sincerely ambitious to make good in the Diesel and related industries, you want to know the true facts. National Schools will send all details regarding training and employment opportunities. National's master course offers you real shop experience with time-tested training. Coach R.R. fare allowed from any point in U.S. to L.A. Earn room and board while learning.

FREE—NEW BOOK OF DIESEL FACTS

Mail coupon for interesting Book of Facts. Gives full details of Training, and opportunities for you.



NATIONAL SCHOOLS

Los Angeles

Request for FREE BOOK

NATIONAL SCHOOLS

Dept. PSA-8, 4000 So. Figueroa St., Los Angeles, Calif.

NAME _____ AGE _____

ADDRESS _____

CITY _____ STATE _____



Learn AVIATION

Come to LINCOLN TRAIN NOW AT THIS GOVERNMENT

APPROVED SCHOOL for a good position as Pilot or Airplane Mechanic. Air Transport Pilots earn up to \$8000 a year; Mechanics up to \$2400.

FOR A PILOT'S POSITION Government Approved Lincoln Training prepares you for any Pilot Rating up to and including Transport. (Commercial), 14 modern Training Planes.

FOR A MECHANIC'S POSITION Government Approved Lincoln Training prepares you for immediate employment as a Government Rated Airplane and Engine Mechanic.

YOU CAN GET INTO AVIATION Our Lincoln Graduates regularly taking positions. WRITE TODAY for complete information.



LINCOLN AIRPLANE & FLYING SCHOOL
608 Aircraft Building Lincoln, Nebraska

Be Your Own Music Teacher



Learn to Play at Home This Quick, Easy Way

A remarkable spare-time, home-study method now makes learning to play your favorite instrument easy as A.B.C. No tedious work—no teacher. Play "real notes." Averages only few cents a day. Send for FREE Booklet "How You Can Learn Music in Your Own Home" and Demonstration Lesson Today. Mention instrument. No obligation.

U. S. SCHOOL OF MUSIC, 88 Brunswick Bldg., New York, N. Y.

Be An ARTIST!

Learn to draw at home this simple way

in your SPARE TIME. Commercial Art, Cartooning and Designing all in ONE course. Trained Artists are capable of earning \$30, \$50, \$75 a week. No previous Art experience necessary. Mail coupon for FREE BOOK, "Art for Pleasure & Profit." Describes complete course famous since 1914, and TWO BIG ART OUTFITS given students. Tear out and mail coupon—No obligation.



COMMERCIAL ART
ILLUSTRATING · CARTOONING

Washington School of Art, Studio 138E
1115 Fifteenth St. N.W., Washington, D.C.

Name _____ Age _____

Address _____

City _____ State _____

PREPARATION MADE THE EXAMS EASY

AT THIRTEEN years of age, I went into the coal mines in Missouri, just a husky boy with a fourth-grade education. At twenty, I emerged from the mine for the last time, with no more book learning than I had when I entered seven years before. My seven years of hard labor had taught me only one fact; but it was one of value to me. I must acquire knowledge and education if I hoped to escape the undesirable life of the poorly paid day laborer. With such thoughts in mind, I started to the East with my seven years' savings, totaling about \$100. At St. Louis, Mo., I trucked mail for six months, then followed telephone-line work for a year or less, but I was not contented. I wanted something better. I had tried for other things but, always, lack of education held me back. I was handicapped badly. The only school that I had attended was one of the type known to the pioneers of the '90s as the "little red schoolhouse." It had one teacher and eighty-odd pupils, ranging in age from six to forty.

For months I remained in a quandary. I wanted to do something about my education, but didn't know how to go about it. I must get some special training, a trade, a profession, or at least some knowledge, somehow. But how to get it perplexed me.

In just this frame of mind, my chance came to me out of a clear sky at a ball game. I was glancing through my newspaper between innings when my eyes fell on an advertisement. "Prepare Yourself for Civil Service Position by Correspondence Course." I tore out the ad and placed it in my bill fold. I knew then and there that I had something. I was certain of a means to an end.

I immediately took steps to begin studying for the next railway mail clerks' examination, which was scheduled to be held in St. Louis the following September.

I enrolled in the _____ School, studied hard, and the school gave me every possible coaching and training. I had returned approximately fifteen lessons by the time the date for appearing before the civil-service examiners arrived. During the examination, I was never worried after the first subject had been disposed of. My average of 94.60 won for me an early appointment as sub-clerk, and in due time came my regular appointment. I continued on through the higher railway-mail grades without difficulty.

Many of the boys with high-school diplomas, and others with college degrees, either failed to make the passing grade, or their appointments never reached their names, low on the eligible register. The men who made the higher

Diesel

For several years, Diesel engines have been replacing steam and gasoline engines in power plants, motor trucks and buses, locomotives, ships, tractors, dredges, pumps, etc. And now the first Diesel-powered passenger car is on the market. Our home-study course offers you a real opportunity to prepare for a worth-while position in this new field. Write TODAY for full information. No obligation. American School, Dept. DC46, Drexel at 58th, Chicago

CARTOON YOUR WAY TO SUCCESS!

DON'T COPY - LEARN TO ORIGINATE!
RAYE BURNS will teach you HOW to CREATE ORIGINAL CARTOONS at home that you can SELL!
Course has 26 lessons and 600 illustrations.
Send name and address for free details. Only \$3.85

RAYE BURNS SCHOOL, Dept. S, Box 2194, CLEVELAND, OHIO

AUTO-MECHANICS & WELDERS

Auto Mechanics and Welders are in big demand. Complete courses in arc and oxyacetylene welding, metal finishing, body and fender bumping, spray painting, collision work. Low rates. Pay after graduation plan. Write.
MICHIGAN TRADE SCHOOL
3761 Woodward Ave., Detroit, Mich. Write for FREE CIRCULAR!

BE A PASSENGER Traffic Inspector

Let Us Help You To a Well-Paid Job!
MEN—19 to 50—trained as Railway and Bus Passenger Traffic Inspectors earn good pay to start and advance quickly with experience. Simple, home-study course qualifies you and upon completion, we place you at up to \$185 per month, plus expenses, to start, or refund tuition. Free Booklet outlines 18-yr. record.
STANDARD BUSINESS TRAINING INSTITUTE
Div. 305 Buffalo, N. Y.

EARN MONEY MAKE COLOR-GLAZED CONCRETE PRODUCTS

New low cost method. No molds, power or costly tools. You build your own equipment from plans we furnish. No experience needed to make color-glazed concrete pottery, wall tiles, statuary casting, giftware—in home or shop.
MEN—Send 10c TODAY for booklet, and details of this money making business.
NATIONAL POTTERIES COMPANY
Room 7, 13 W. 26th St., Minneapolis, Minn.

Become an expert photographer

Send for big free booklet that tells how you can become an expert in Commercial, News, Portrait, Advertising or Motion Picture Photography. Big money-making opportunities. Personal Attendance and Home Study training. 28th year.

NEW YORK INSTITUTE OF PHOTOGRAPHY
10 West 33 St. (Dept. B) New York City

EARN MONEY Stringing TENNIS RACKETS

An opportunity to earn as much as \$3.50 for a few minutes of your spare time. String your own racket and save money. Tennis rackets need restringing frequently. Every stringing means profit for you. No experience needed—we teach you how. TOMGUT Equipment makes it easy. Costs practically nothing to start. Easy work. Begin NOW!

FREE Write today and we will send you Free plan and Special offer on strings and stringing equipment.

THOMPSON MANUFACTURING COMPANY
4529 Packers Avenue, Chicago, U. S. A.
TOMGUT "Court-Tested" Tennis & Badminton Strings

☐ Send FREE plan and Special offer.
☐ Send new booklet "400 YEARS OF TENNIS."
Enclosed is 10c to cover mailing costs.

Name _____

Address _____

City _____ State _____

MAIL THIS COUPON

Secrets of Success

averages, and who subsequently received the early appointments, had prepared themselves by correspondence courses especially suited to their needs.

My various assignments took me pretty well over the world. A period of a few years I spent in charge of mails with the Army in France, during the World War, and later with the Army of Occupation, in Germany. The railway post offices I have served in would be too numerous to mention here, but they covered much territory and a vast distribution of United States and European mails.

I have forgotten the coal mines and other laborious lines of work, and just now, at fifty-three, I am preparing for something still higher than railway mail service. I have a special course paid for in the ———— Schools, and shall start to work on that right away.

For all this I am thankful, and always will be, to the correspondence school that prepared me so thoroughly for my first civil-service examination. It was the very thing that I needed to get out of a rut and get started up hill. All I had to do was answer that ad and study hard for about three months. I was certain of success from the start.
—J. J. D., Kansas City, Mo.

BARBER FOR YEARS, WON COLLEGE JOB

TEN YEARS ago, I worked in a barber shop. I spent ten hours a day, and, on Saturday, fourteen and fifteen hours, cutting hair and shaving people for my living. For years I had stood behind a barber chair, calling "Next," and hoping the customer sitting in the waiting line would see fit to get in my chair. We were paid a commission on what we took in. On Sundays, I went out to preach in the little Baptist churches scattered through the mountains near where I lived.

Today, I am director of publicity of the ———— College. My work averages eight hours a day, and, although it does not mean I work any the less, I am practically my own boss.

As a barber, I earned only about twenty dollars a week, if I was fortunate and the weather was good. It doesn't matter, so far as my story is concerned, just what my present salary is. It is sufficient to say that there is no comparison between it and the old salary of barber-shop days.

I now move socially in the best of circles. I rub elbows with college-trained men and women with no thought of embarrassment, feeling perfectly at home in practically any discussion. And while it may sound like a patent-medicine advertisement, it is true that I owe my present standing and position entirely to self-improvement through home-study courses.

When I first became interested in home-study courses ten years ago, I answered an advertisement and took

Accountancy Home-Study

made interesting and practical thru problem method

YOU know as well as we do that Accountancy fits many men for positions that pay three and five and ten thousand dollars a year—gives many other men unusual opportunity to start a profitable growing business of their own.

The only question is—just how practical is it for you to train yourself adequately in Accountancy through home study?

And the answer lies in the LaSalle Problem Method.

For this modern plan of training not only makes Accountancy study at home thoroughly practical but makes it interesting as well.

And here's how:

You Learn by Doing

Suppose it were your privilege every day to sit in conference with the auditor of your company or the head of a successful accounting firm. Suppose every day he were to lay before you in systematic order the various problems he is compelled to solve, and were to explain to you the principles by which he solves them. Suppose that one by one you were to work those problems out—returning to him every day for counsel and assistance—

Granted that privilege, surely your advancement would be faster by far than that of the man who is compelled to pick up his knowledge by study of theory alone.

Under the LaSalle Problem Method you pursue, to all intents and purposes, that identical plan. You advance by solving problems.

Only—instead of having at your command the counsel of a single individual—one accountant—you have back of you the organized experience of a great business training institution, the authoritative findings of scores of able accounting specialists, the actual procedure of the most successful accountants.

Thus—instead of fumbling and blundering—you are coached in the solving of the very problems you must face in the higher accounting positions or in an accounting practice of your own. Step by step, you work them out for yourself—until, at the end of your training, you have the kind of ability and experience for which business is willing and glad to pay real money—just as it was glad to pay these men.*

Five Men Who Tested and Proved It for You

For instance, there was the plumber who started Accountancy training with us in 1916. After a short period of study, he took a position as bookkeeper for a year, and then became accountant for a leading automobile manufacturer—

with two bookkeepers under him. Later he became auditor of one of the foremost banks in his state with his salary 325 percent larger than when he started training.

He wrote, "My training is the best investment I've ever made, showing a cash value running into five figures."

And the young clerk, earning \$75 a month and then getting many times that as general auditor for an outstanding, nation-wide organization. Within six months after he began our training, he was earning \$125 a month and within four years, he was earning \$250.

Do you wonder that he writes, "While LaSalle ads once seemed like fairy tales to me, now I know from personal experience that they are true?"

Or let us tell you about two men—one a stenographer and the other a retail clerk—neither of whom knew more than the simplest elements of bookkeeping. One is now the comptroller and the other the assistant comptroller of a large company.

"LaSalle training in Higher Accountancy," write both, "was the important factor in our rapid climb."

And if you are thinking about the C. P. A. degree and a public accounting business of your own, read about the pharmacist who was earning \$30 a week eleven years ago when a LaSalle registrar secured his enrollment for Accountancy training. Eight months later he left the drug store to take a bookkeeping job at \$20 a week—less money but larger opportunity. Three years later he passed the C. P. A. examination and a year later yet he was earning \$5,000 a year. Now he has his own highly successful public accounting firm for which he says, "My LaSalle training has been largely responsible."

One-Tenth of All C. P. A.'s Are LaSalle Trained

If you want still more proof, remember that 1,600 C. P. A.'s—approximately one-tenth of all those in the United States who have ever passed the difficult examination for this coveted certificate—are LaSalle trained.

Or remember that in our files—accessible on request—are thousands of letters from our Accountancy graduates reporting material increases—some double, triple—and even more—over their original earnings.

And knowing these facts, ask yourself if there can be any further question about the practicability of this training for you—ask rather if the real question is not about the size of your own ambition and the quality of your determination.

For Accountancy is no magic wand for the lazy or the fearful or the quitter—it offers success only to the alert adult who has the courage to face the facts and the will to carry on till the job is done.

If you are that individual, the coupon below, filled out and mailed, will bring you free the information that can open up to you the future of which you have dreamed—ability and income and success.

Is it not worth getting that information?



Send for This Book

*Names and addresses given on request.

LASALLE EXTENSION

LASALLE EXTENSION, Dept. 883-HR, Chicago, Illinois

Please send me, free of all cost or obligation, your 64-page, illustrated book, "Accountancy, the Profession That Pays," telling about the profession of accountancy and your training for success in that field.

Name.....

Address.....City.....

Position.....



TRAIN FOR ELECTRICITY 12 WEEKS HERE IN THE COYNE SHOPS MANY OPPORTUNITIES IN THIS GIGANTIC FIELD



Mail coupon today for details of famous Coyne "Learn by Doing" method of practical shop training for your start for success in this big-pay field. Age or lack of money need not hold you back.

12 WEEKS' TRAINING
Coyne Training is practical, thorough, easy to grasp... you learn quickly by doing actual jobs on real electrical machinery right here in my Chicago Training Shops—NOT from books or printed lessons. You don't need previous experience or a lot of book learning. Expert instructors guide you every step of the way.

EARN WHILE LEARNING— JOB HELP AFTER GRADUATION

Big things ahead in Electricity means opportunities for steady jobs, good pay, and a real future in this fascinating "live" industry. Thousands of opportunities. Rush the coupon TODAY for Big Free Book containing many photos of the great Coyne Shops in Chicago, facts about Coyne Training, Free Employment Service, many earn while learning, additional instruction in Diesel Engines, Electric Refrigeration and Air-Conditioning at No Extra Cost. MAIL COUPON TODAY.

COYNE ELECTRICAL SCHOOL
R. C. LEWIS, President
500 S. Paulina St., Dept. C8-73, Chicago, Ill.

H. C. LEWIS, President, Coyne Electrical School
500 S. Paulina St., Dept. C8-73, Chicago, Ill.

Send me, without cost or obligation, your Big Free Book and details of your "Plans" to help me.

NAME _____

ADDRESS _____

CITY _____

STATE _____



High School at Home

Many Finish in 2 Years

Go as rapidly as your time and abilities permit. Equivalent to resident school work—preparation for entrance to college. Standard U. S. texts supplied. Diploma awarded. Credit for H. S. subjects already completed. Single subjects if desired. Bulletin on request.

20 Other Courses

Specialized training is absolutely essential to success today. Over 100 noted Educators, Engineers and Business Men helped prepare a special instruction material used by many resident schools and colleges. U. S. Navy and Province of Manitoba Can. Train at home for best paying home as listed below. No interference with present earnings while preparing for better job.
American School, Chicago

Mail Coupon for Information—No Obligation

American School, Dept. H-C 46, Drexel at 58th, Chicago
Tell me how to train for success in the checked
High School Course in 2 Years

- | | |
|--|---|
| <input type="checkbox"/> Air Conditioning | <input type="checkbox"/> Electrical Refrigeration |
| <input type="checkbox"/> Architecture and Building | <input type="checkbox"/> Highway Engineering |
| <input type="checkbox"/> Automotive Engineering | <input type="checkbox"/> Liberal Arts College |
| <input type="checkbox"/> Aviation | <input type="checkbox"/> Mechanical Engineering |
| <input type="checkbox"/> Business Management | <input type="checkbox"/> Private Secretary |
| <input type="checkbox"/> Civil Engineering | <input type="checkbox"/> Professional Accounting |
| <input type="checkbox"/> Complete Law | <input type="checkbox"/> Incl. C. P. A. Coaching |
| <input type="checkbox"/> Diesel Engineering | <input type="checkbox"/> Radio and Television |
| <input type="checkbox"/> Drafting and Design | <input type="checkbox"/> Salesmanship |
| <input type="checkbox"/> Electrical Engineering | <input type="checkbox"/> Steam Engineering |

Name _____

Address _____

INVENTORS PATENT YOUR IDEAS SEND FOR FREE BOOK



HOW TO OBTAIN A PATENT.

Written by a Former Member of the Examining Corps (1922-24) of the U. S. Patent Office. If you want to profit by your idea you should take steps to apply for a U. S. Patent at once. Your first step is to get this Free Book. This interesting illustrated book contains valuable information you should have. It tells you fully how to obtain a patent on your idea in the quickest way. With this Free Book you will also receive a "Record of Invention" form on which you can easily record your idea. Personal and Confidential Service: Your case will be personally handled only by a Registered Patent Attorney who is also a Former Member of the Examining Corps of the U. S. Patent Office. All communications will be strictly confidential.

MAIL COUPON TODAY for FREE PATENT BOOK, and RECORD OF INVENTION Form.

CARL MILLER
REGISTERED PATENT ATTORNEY
FORMER MEMBER EXAMINING CORPS U. S. PATENT OFFICE

Woolworth Bldg., 35th Floor, Dept. 88-C, New York
MILLER BUILDING, DEPT. 88-C, WASHINGTON, D. C.

Please send me your Free Book, "How to Obtain a Patent," and "Record of Invention Form."

NAME _____

ADDRESS _____

Secrets of Success

the course in newspaper writing offered by the _____ School. After completing the course, I became correspondent for several newspapers. In 1930, I left the barber shop and accepted the position of general secretary of the Y.M.C.A., at _____. Seeing my need of more education, I took a high-school correspondence course from the _____ School, and graduated in 1932.

With a daughter at _____ College, I was unable to attend college myself. In order to become a better preacher, I enrolled in 1932 for the four-year course of the _____ School, continuing with my Y.M.C.A. and newspaper work.

I completed the course and graduated in 1936. In October of that year, I became staff correspondent for the _____ "News," then resigned to accept a like position with the _____ "Times," three months later. When offered my present position early this year, I accepted.

In conclusion, let me say that I would never have learned enough about newspaper work to become acceptable to outstanding newspapers if it had not been for the correspondence courses I took. And my diploma, coupled with my newspaper training, was largely responsible for my securing the position I now hold.—C. L. R. Cleveland, Tenn.

More \$5 Prize Winners

Two prize-winning letters in POPULAR SCIENCE MONTHLY'S Secrets of Success contest—"What Home Study Has Meant to Me"—are printed above. Read these stories carefully, because your own career may be just as interesting and inspiring to other readers. If you think so, put it down on paper and send it in. We will pay \$5 for every letter we publish.

CONTEST RULES

Only letters from bona fide home-study school students will be considered and these must contain the name of the school and the name of the company, or companies, for which you have worked since graduation. (Names, however, will be deleted from the letters when published.) We also want to know the kind of course you took and the type of position you have held. Your own identity will be kept anonymous, if desired.

We are interested in facts, not literary ability, but please write clearly, completely, and keep your letters within 750 words. We are not looking for "get-rich-quick" stories or freak adventures, and authors must be prepared to substantiate the truth of their statements. Manuscripts submitted and printed become the property of this magazine, and we are not responsible for the return of rejected letters unless sufficient postage is provided for this purpose. Address your contribution to Success Story, 353 Fourth Avenue, New York, N. Y.

ELECTRICAL ENGINEERING

One Year Condensed Course Prepares
For Technical Work in Electrical Field

Thorough training in principles, with practical applications in laboratory and shop. High placement record. 7,000 graduates.

Modern buildings, dormitory, dining hall. Campus. 46th year begins September 28.

Catalog on request.



BLISS ELECTRICAL SCHOOL
108 Takoma Avenue Washington, D. C.

ENGINEERING DEGREE IN TWO YEARS

B. S. Degree courses in engineering: Electrical, Civil, Chemical, Mechanical, Radio and Television, or Aeronautical. 1 yr. Mech. Drafting. Intense, practical, thorough program. Prep. courses without extra charge. Earn board if desired. Low tuition. Enter March, June, Sept., Dec. Catalog.

243 E. Washington Blvd., Fort Wayne, Ind.

INDIANA TECHNICAL COLLEGE

HOME STUDY

Home Study Courses leading to Degrees in Arts and Sciences; Philosophy; Education; Writing; Psychology; Chemistry; Theology; Law; Agriculture; Business; Accounting; Sales; Advertising; Public Speaking; Electrical, Civil, Diesel, Mechanical, Architectural, Aeronautical, Drafting, Radio, Air Conditioning, Refrigeration, Automotive, Highway, Mining, Steam, Petroleum, Industrial and Chemical Engineering.

McKinley-Roosevelt Graduate College
4202 Clarendon Ave., Chicago, Illinois, U.S.A.



THERE'S MONEY IN YOUR CAMERA!

Others make good incomes selling pictures to publications. FREE CATALOG describes home study course (which may be paid for in easy installments) and tells how YOU can do it too! Universal Photographers, Dept. 38, 10 West 33 Street, N.Y.C.

DO YOU WANT a new business profession of your own, with all the trade you can

attend to? Then become a foot correctionist, and in a few weeks earn big income in service fees—not medical nor chiropody—easy terms for home training, no further capital needed, no goods to buy, no agency. Established 1894. Address Stephenson Laboratory, 62 Back Bay, Boston, Mass.

PLASTEX

The Plastex Industry needs manufacturers on small scale and for big production of Lamp and Clock Stands, Art Goods & Novelties in Plastex and Marble imitation. Experience unnecessary. 1/2¢ material makes regular 10¢ store sellers. Rubber moulds furnished for speed production. Small investment brings big returns. Ambitious men have chance for real prosperity. Our free booklet will interest and benefit you. Plastex Industries, Dept. 2, 1088 Washington Avenue, New York, N. Y.

Photography



PLEASURE or PROFIT


Prepare for profitable business or fascinating hobby, at home under guidance of qualified instructors. No previous experience necessary, common school education sufficient. Many earn while learning. Our practical studio methods also qualify for well-paying positions upon graduation. Send coupon below at once for free booklet "Opportunities in Modern Photography", particular and requirements.

AMERICAN SCHOOL OF PHOTOGRAPHY
3601 Michigan Avenue Dept. 136C Chicago, Ill.
Send booklet "Opportunities in Modern Photography", full particulars and requirements.

Name _____ Age _____

Address _____

City _____ State _____



SHIP MODELS Make Perfect Gifts

A BEAUTIFUL ship model makes a perfect gift—it never wears out or becomes obsolete. If you would like to give one to a relative or close friend next Christmas, now is the time to start, particularly if you undertake one of the more elaborate models, such as the *Great Republic* shown above.

Our construction kits have been prepared to save you time and money. All the raw materials are of such sizes and shapes as to make it easiest for you to transform them into their final form, and a certain amount of preliminary shaping has been done on most of the hulls or hull lifts.

We also have model railway, whittling, and furniture kits. The complete list follows:

STANDARD SHIP MODEL KITS

- A. Whaling ship *Wanderer*, 20½-in. hull, 27½ in. over all..... \$7.40*
- D. Spanish galleon, 24-in. hull, 30 in. over all..... 6.95*
- E. Battleship U.S.S. *Texas*, 3-ft..... 7.45*
- G. Elizabethan galleon *Revenge*, 25-in. hull, 28 in. over all..... 7.25*
- L. Farragut's flagship *Hartford*, steam-and-sail sloop-of-war, 33½-in. hull, 41 in. over all..... 8.45*
- Q. Privateer *Swallow*, 12½-in. hull, 20 in. over all..... 4.95†
- V. Clipper *Sovereign of the Seas*, 20½-in. hull, 26 in. over all..... 4.95†
- Y. Trading schooner, 17½-in. hull, 22½ in. over all..... 4.90†
- 2S. U. S. Navy destroyer *Preston*, 31½-in. hull..... 5.95*
- 3S. *Constitution* ("Old Ironsides"), 21-in. hull, 31 in. over all..... 6.50*
- 4S. Clipper ship *Great Republic*, 31½-in. hull, 42 in. over all..... 8.40*

(Continued on page 18)



"Constitution" model built from Kit 3S



"SELDOM SEE AN I. C. S. GRADUATE OUT OF A JOB"

"IN ALL THE YEARS I have known of the International Correspondence Schools, I have seldom seen one of your graduates jobless."

A business executive made this statement in a recent letter commenting on the I. C. S. graduates and students in his employ and expressing regrets that it was necessary to reduce his personnel.

"However," he added, "all I. C. S. graduates and students will be retained,

for I fully realize their value in my business."

The reason so many I. C. S. men have jobs is because they are *trained men*! A recent investigation into the working conditions of 1000 I. C. S. students revealed only ten unemployed. You, too, can be an I. C. S. man.

Mark the coupon and mail it today! It has been the most important act in the lives of thousands of men.

INTERNATIONAL CORRESPONDENCE SCHOOLS

BOX 7639-J, SCRANTON, PENNA.

★ Without cost or obligation, please send me a copy of your booklet, "Who Wins and Why," ★ and full particulars about the subject before which I have marked X:

- | | | | |
|--|--|--|--|
| TECHNICAL AND INDUSTRIAL COURSES | | | |
| <input type="checkbox"/> Architect | <input type="checkbox"/> Welding, Electric and Gas | <input type="checkbox"/> Mechanical Draftsman | <input type="checkbox"/> Management of |
| <input type="checkbox"/> Architectural Draftsman | <input type="checkbox"/> Reading Shop Blueprints | <input type="checkbox"/> Diesel Engines | <input type="checkbox"/> Inventions |
| <input type="checkbox"/> Building Estimating | <input type="checkbox"/> Sheet Metal Worker | <input type="checkbox"/> Aviation Engines | <input type="checkbox"/> R. R. Locomotives |
| <input type="checkbox"/> Contractor and Builder | <input type="checkbox"/> Machinist <input type="checkbox"/> Toolmaker | <input type="checkbox"/> Auto Technician | <input type="checkbox"/> R. R. Section Foreman |
| <input type="checkbox"/> Structural Engineer | <input type="checkbox"/> Patternmaker <input type="checkbox"/> Boilermaker | <input type="checkbox"/> Auto Elec. Tech. | <input type="checkbox"/> Air Brakes <input type="checkbox"/> Signalmen |
| <input type="checkbox"/> Structural Draftsman | <input type="checkbox"/> Heat Treatment of Metals | <input type="checkbox"/> Plumbing | <input type="checkbox"/> Chemistry <input type="checkbox"/> Pharmacy |
| <input type="checkbox"/> Electrical Engineer | <input type="checkbox"/> Bridge Engineer | <input type="checkbox"/> Steam Fitting | <input type="checkbox"/> Coal Mining |
| <input type="checkbox"/> Electric Lighting | <input type="checkbox"/> Bridge and Building Foreman | <input type="checkbox"/> Heating <input type="checkbox"/> Ventilation | <input type="checkbox"/> Cotton Manufacturing |
| <input type="checkbox"/> Telegraph Engineer | <input type="checkbox"/> Highway Engineer | <input type="checkbox"/> Air Conditioning and Cooling | <input type="checkbox"/> Woolen Manufacturing |
| <input type="checkbox"/> Telephone Work <input type="checkbox"/> Radio | <input type="checkbox"/> Civil Engineer | <input type="checkbox"/> Steam Engineer | <input type="checkbox"/> Poultry Farming |
| <input type="checkbox"/> Commercial Refrigeration | <input type="checkbox"/> Surveying and Mapping | <input type="checkbox"/> Steam Electric Engineer | <input type="checkbox"/> Agriculture |
| | <input type="checkbox"/> Mechanical Engineering | <input type="checkbox"/> Marine Engineer | <input type="checkbox"/> Navigation |
| BUSINESS TRAINING COURSES | | | |
| <input type="checkbox"/> Business Management | <input type="checkbox"/> Bookkeeping | <input type="checkbox"/> First Year College Subjects | <input type="checkbox"/> High School Subjects |
| <input type="checkbox"/> Industrial Management | <input type="checkbox"/> Secretarial Work | <input type="checkbox"/> Business Correspondence | <input type="checkbox"/> College Preparatory |
| <input type="checkbox"/> Traffic Management | <input type="checkbox"/> Spanish <input type="checkbox"/> French | <input type="checkbox"/> Stenography and Typing | <input type="checkbox"/> Illustrating |
| <input type="checkbox"/> Accountancy | <input type="checkbox"/> Salesmanship | <input type="checkbox"/> Civil Service <input type="checkbox"/> Mail Carrier | <input type="checkbox"/> Cartooning |
| <input type="checkbox"/> Cost Accountant | <input type="checkbox"/> Service Station Salesmanship | <input type="checkbox"/> Railway Mail Clerk | <input type="checkbox"/> Lettering Show Cards |
| <input type="checkbox"/> C. P. Accountant | <input type="checkbox"/> Advertising | <input type="checkbox"/> Grade School Subjects | <input type="checkbox"/> Signs |
| DOMESTIC SCIENCE COURSES | | | |
| <input type="checkbox"/> Professional Dressmaking and Designing | <input type="checkbox"/> Tea Room and Cafeteria Management, Catering | | |
| <input type="checkbox"/> Home Dressmaking | <input type="checkbox"/> Advanced Dressmaking | <input type="checkbox"/> Foods and Cookery | |

Name..... Age..... Address.....

City..... State..... Present Position.....

If you reside in Canada, send this coupon to the International Correspondence Schools Canadian, Limited, Montreal, Canada

If you like POPULAR SCIENCE MONTHLY why not pass the word along to your friends. When an article in this magazine strikes you as being unusually good, tell your friends to get a copy at the newsstand, and read it.



TRI-STATE COLLEGE ENGINEERING DEGREE IN 2 YEARS

Courses in Civil, Electrical, Mechanical (108 weeks), Chemical, Aeronautical (108 weeks), Radio Engineering. Essentials of engineering included and non-essentials eliminated. B. S. Degree granted upon completion of course. For ambitious, earnest students. Those who lack high school may make up required work. Graduates compete successfully with those of 4-year schools.

Technical instruction at lowest cost and in least time consistent with thorough training. Courses also in Business Administration and Accounting. Also short diploma courses, (36 weeks) in Surveying and Drafting. Students from all parts of the world. Tri-State graduates make good. Tuition, living expenses low. 53th year. Enter June, September, January, March. Write for catalog. 588 College Ave., Angola, Ind.



FOUNDED
IN 1884

BE A RADIO EXPERT

Learn at Home—Make Good Money

Many men I trained at home in spare time make \$30, \$50, \$75 a week. Many make \$5, \$10, \$15 a week extra in spare time while learning. Illustrated 84-page book points out Radio's opportunities, also how you can learn to be a Radio Expert through my practical 50-50 method of training. Television training is included. Money Back Agreement given. Mail coupon today. Get book FREE.

J. E. SMITH, President, Dept. SHP3,
National Radio Institute, Washington, D. C.

Send me, without obligation, your 84-page book "Rich Rewards in Radio" FREE. (Please write plainly.)

Age _____

Name _____

Address _____

City _____

State _____

Learn Profitable Profession in 90 days at Home

Swedish Massage is the most profitable profession for men and women in the home. You can make \$10 to \$25 per week but many prefer to open their own office. Large incomes from doctors, hospitals, and private parties come to those who qualify through our training. Receiving a big step in rewards for your work. Write for details and booklet. They're FREE.

The College of Swedish Massage
1601 Warren Blvd., Dept. C78, Chicago
Superior to National College of Massage



Listen Pal, DON'T BE AN OSTRICH



"Don't keep your head 'buried in the sand'...when it comes to the kind of work you're going to do the rest of your life. You're playing ostrich...whether you realize it or not...if you fail to look at what's happening in Air Conditioning. Believe me, I know...because I'm in Air Conditioning and have an interesting, good-pay job, with an unlimited future ahead of me."

Words like these come from the mouths of Thermo Institute graduates who have stepped into Air Conditioning—the field which financial authorities call the next industrial giant. It's so big even now...and growing so fast...that the supply of men with proper training is lagging far behind. Get into this great new field...get the training you need, through Thermo Institute courses. The same superior, practical training is given at any one of the three Thermo schools you choose to attend...or you can start your training at home immediately, no matter where you live. For complete information send the coupon below.

THERMO

AIR CONDITIONING INSTITUTE

Completely Equipped Laboratories and Schools at
LOS ANGELES—194 South Alvarado Street
CHICAGO—125-B West Hubbard Street
NEW YORK—1755-B Broadway

Please send information on Thermo Institute training, and free copy of booklet "The Air You Breathe."

NAME _____ AGE _____

STREET _____

CITY _____ STATE _____ 19__




Easily cut to shape, the moistureproof sheathing is shown being nailed securely to studs of a new house

New Ideas for HOME OWNERS


DDOUBLE-COATED on both sides with a moistureproof bituminous compound, a new insulating sheathing is now available to home builders. According to the manufacturers, it has unusual strength and will not foul saws or other tools used in cutting it to shape. Available in sections four feet wide and from eight to twelve feet long, the panels, shown being installed in the photograph at the left, are marked for nailing so that they can be applied quickly and easily.

Hangers Prevent Bathtubs from Settling

QUICKLY leveling any type of built-in bathtub, an adjustable hanger simplifies installations and is said to insure against any future settling that might crack the surrounding tile or plaster. Two lag screws fasten each hanger to the wall studding. The edge of the tub rests on an adjustable arm on each hanger, which can be raised or lowered by convenient nuts to bring the tub to a level position.



How the edges of a bathtub rest on the hangers. Inset shows the adjusting nuts



Nickel-plating a kitchen fixture with the electric brush

Electric Brush Plates Metals

JEWELRY, tableware, and plumbing fixtures can be quickly and inexpensively replated with a new electric kit just marketed. The user simply cleans the article, applies a paste containing the desired metal with an electric brush, and polishes it to a luster. The device is designed for alternating house current. Besides restoring finishes, the unit can be used to plate metal surfaces not previously so treated.

ATHLETE'S FOOT?

Itching, burning—often torturing, if neglected—Athlete's Foot is a stubborn, communicable disease, caused by a fungus growth. Do not neglect it! Apply Ring-X to affected areas. Ring-X reaches the real seat of the trouble!

**-THEN YOU NEED
RING-X**



**RING-X IS A DEPENDABLE
EFFECTIVE TREATMENT**

Guaranteed! Purchase price refunded if not completely satisfactory after five day test. Order by mail. Send no money—simply pay postman ONE DOLLAR when Ring-X is delivered to you.

Not a liniment. Not a "cure-all." Ring-X is compounded only for the scientific treatment of Athlete's Foot.

RING-X COMPANY

Dept. P 2435 Plymouth Ave.
Columbus, Ohio

Work on ELECTRIC MOTORS

Get into the profitable business of rewinding and repairing electric motors. This home-study course will help those who wish to increase their knowledge of the subject, and will be of value to others responsible for maintenance of domestic, office and factory equipment. Free booklet.



International
Correspondence Schools
Box 7641-J, Scranton, Penna.

PATENTS PERSONAL SERVICE

My Personal service assures strictest confidence on all your patent problems. Send me a model or drawing, or sketch and description of your invention, and \$5.00. I will make a search and report promptly as to its patentability and send you a copy of my 78-page booklet. Or, if you prefer to read my booklet first, write today for FREE copy. Registered Patent Attorney.

L. F. Randolph, 340-D Victor Bldg., Washington, D. C.

New Ideas now Salable Before Patenting

Practical, useful inventions may now be safely marketed without patenting expense. Write for proof that we have been successfully selling both patented and unpatented inventions, since 1914.

Chartered Institute of American Inventors
Dept. 3, Barrister Building Washington, D. C.

Inventions Promoted

Patented or Unpatented. In business over 30 years. Send drawing and description or model, or write for information. Complete facilities. References.

ADAM FISHER COMPANY

183-D Enright, St. Louis, Mo.


When Writing Advertisers

Please Mention POPULAR SCIENCE

Be a DENTIST LEARN AT HOME

To make Crowns, Plates, Bridgework, etc., for Dentists. Easy practical way to learn mechanical dentistry at home in spare time. FULL EQUIPMENT OF TOOLS AND MATERIALS INCLUDED WITH COURSE. Low tuition. Easy terms. Write for FREE BOOK about this money making profession that is not affected by machine age.

McCarrie School of Mechanical Dentistry
207 N. Broad St. Dept. 650 Philadelphia, Pa.



Light Lubricating Oil Now Comes in Tubes

HIGH-QUALITY lubricating oil of the type used for many years on bank safes and vaults is now available for general household use in a handy collapsible tube. Provided with an oil-can spout, the tube is squeezed lightly to eject the desired amount of oil, which is said to possess special rust-preventing properties and to flow easily at temperatures far below zero. Since oil is squeezed out, the tube does not have to be up-ended and oiling can therefore be done in an upward direction to reach difficult spots that defy ordinary oil cans.

Questions FROM HOME OWNERS

Q.—WHAT is the best method of finishing a concrete floor in a play room? It will have to withstand marring by steel skate rollers as well as scuffing by rubber-soled shoes.—E.J.B., Pewee Valley, Ky.

A.—WE SUGGEST that you use a special type of paint made with a so-called rubber-cement, waterproof base for finishing the concrete floor. Such a finish will be attractive yet will stand a considerable amount of very hard wear.

Patching Chipped Enamel

Q.—PATCHES of enamel have chipped off the surface of our refrigerator and washing machine. Is there any way to refinish and repair the enamel without scraping the entire surfaces down to the metal?—L.A.G., Blackwell, Okla.

A.—CHIPPED enamel can be repaired with the use of a special porcelain cement available to home owners. The chipped surface is cleaned and warmed, and the cement, which resembles sealing wax, is applied with a warm knife.


Leak in Hot-Water Tank

G.F.H., BINGHAMTON, N.Y. A small leak in a hot-water tank can be plugged easily by inserting a tapered stopper of white pine or walnut into the hole. The taper should be a gradual one, terminating in a point as sharp as a needle. Soak the plug in water, and then drive it in with a hammer. Cut off the projecting end within a half inch of the outside of the tank.

FREE

68 Pages of FACTS ABOUT PATENTS

AND SELLING INVENTIONS



Many pictures and examples of inventions make these excellent guide books for inventors.

OTHER MEN HAVE READ AND PROFITED BY THESE FREE BOOKS

IF you have an invention—or an idea for one—you should have these free books. They tell you real facts like these: How the patent laws protect you. Why you need the protection of a U. S. Patent. What a competent registered patent attorney can do for you. They tell what kind of sketch or model is needed and how to make proper disclosure of your idea to help establish your claims. They tell how some successful inventors have secured financial assistance. They show 115 different mechanical principles.

HOW WE SERVE YOU

For more than a third of a century—we have represented thousands of inventors. We answer questions. We study each device to bring out its best patentable possibilities. Often, also, we advise inventors against going ahead with inventions which could not possibly be protected. By carefully developed methods, we try to keep expenses at a minimum and we can arrange a deferred payment plan when needed. With the books, we will also send you a copy of our "Evidence of Invention" form on which you can sketch and describe your invention and establish a date of disclosure. Such a date of disclosure may later prove important to you. You can deal with us in strictest secrecy. Learn the facts. Simply sign and mail the coupon below. Take that first step today.

**VICTOR J.
EVANS & Co.**

REGISTERED PATENT ATTORNEYS

MAIN OFFICE: 10-J, Victor Building, Washington, D. C.
Other Offices: 514-C, Empire Bldg., Pittsburgh; 405-C, Garfield Bldg., Los Angeles

Send me FREE copies of your books "Patent Protection" and "When and How to Sell an Invention" (Note: Same books supplied by either of branch offices listed above.)

Name _____
Street and No. _____
City or Town _____ State _____

Classified Section

CLASSIFIED ADVERTISING is inserted in these columns at the special rates of: 20c a word per insertion for 12 consecutive issues, 25c a word for 6 consecutive issues, 30c a word for 3 consecutive issues, 35c a word for one issue. Minimum ad accepted is 10 words. Each insertion is payable in advance. Copy and remittance for the September issue (on sale August First) must reach this office not later than July Third.

POPULAR SCIENCE MONTHLY, 353 FOURTH AVE., NEW YORK CITY

ADVERTISING

MAIL-ORDER ad reaching 1,500,000 families throughout United States \$15.40 inch. Newspaper, magazine, ratebook free. Chicago Advertising Agency, 20-PS West Jackson, Chicago.

ADVERTISE: 24 words in 250 newspapers \$10. Lists free. Advertising Bureau, 4515-P Cottage Grove, Chicago.

ADVERTISE 25 words 25 magazines 3 months \$1.50. Inch \$6.00. List, special offers free. Bucknam, 177A State, Boston.

INCH display advertisement 30 magazines year \$24. Wood's Popular Services, Atlantic City, (N. J.)

24 WORDS 65 newspapers, magazines \$3.00. Goodall, 742 Market, San Francisco.

AGENTS WANTED

BIG Money applying initials on automobiles. Easiest thing today. Free Samples. Also, sideline salesmen for name plates and tire cover transfers. "Rafco," 1305 Washington, Boston, Mass.

PROFIT with new products. Make, sell, repeat. Analysis Research. Guaranteed formulas. Biggest catalog free. Special prices, leads. Gibson Laboratory, Chemists, FB-1142 Sunnyside, Chicago.

SPECIALTY sensation! 100% profit for agents on new patented home product. Chance to become district manager. Send 25 cents for sample, returnable. Write Appliance Products Co., Dept. 51, Madison, Wis.

I'll give you groceries at wholesale besides splendid opportunity to make up to \$45.00 in a week. Brand new Ford Sedan given as bonus. Details free. Albert Mills, 6231 Monmouth, Cincinnati, Ohio.

BIG profit—Sell latest auto specialty. Up to 300% profit. Wildfire rep. Details free or send \$1.00 for full sample. Nu-Way Products Co., 302 1/2-B South Front St., Mankato, Minn.

AGENTS—Opportunity make money; book containing 107 successful business plans home-office, send for free introductory booklet. Elite Co., 214-A Grand St., N. Y.

IMPORTING! Wholesale supply directory of foreign manufacturers and exporters. Over five million items. 10c postpaid. Blain Service, D-PS, Buffalo, Minn.

SCIENTIFIC gas economizer increases mileage 25-40%. Trial package \$1.00, enough to treat 120 gallons. Norsemen Chemicals, Crete, Nebr.

EXCLUSIVE representatives appointed. Faucet water softener. Revolutionary. Luxursoft, Sausalito, Calif.

FREE sample—amazing cleaner; sells homes, taverns, everywhere. Big profit—fast repeater. Besco, 5009-X, Irving Park, Chicago.

BIG money applying initials on automobiles. Write for particulars and free samples. American Letter Company, Dept. 47, Danielson, N. J.

ABSOLUTELY new food product (Haggietes). Wholesome. Replaces meat. Particulars free. R. Preston, Box 511 Ottawa Canada.

MEXICAN novelties. 100%-300% profit! Free particulars. Samples 10c stamps. Marquez-IA, Apartado 1176 Mexico City.

BUSINESS proposition resilvering mirrors, autographs, reflectors, making chipped glass signs. Write, Sprinkle, Plater, 910 Marion, Ind.

ATLAS window sign letters. Large sizes, penny each. Beautiful free samples. Atlas, 7941-J, Halsted, Chicago.

500% PROFIT! Gold and colored sign letters for windows, offices, trucks, signs Monograms Easily applied. Neonite, Akron, Ohio.

300% PROFIT selling gold leaf letters for store windows; free samples. Metallic Co., 437 North Clark, Chicago.

MAKE products yourself. Formula Catalog Free! Kemizo, 180-H Parkridge II.

AFTERNOONS Free! \$300 month—home! No canv. Expect surprise! Folios-B, Station D, Los Angeles.

\$50 WEEKLY calling on stores. No selling, just deliver—collect. Drexel Sales, Box 97, Drexel Hill, Pa.

SENSATIONAL new sellers, free catalogue, samples. Paty Co., Somerville, Mass.

AIR CONDITIONING

AIR-CONDITIONING Outfits; easily built! Home, work-shop, stores, offices! Enjoy "mountain air," year-around health and comfort. Complete instructions. Seven different blueprints. Send \$1.00. Money-back guarantee. Servatex Company, 850-PSM Madison Building, Milwaukee, Wis.

AMER. POLICE JIU JITSU

KNOCK-EM-COLD! Learn police Jiu Jitsu! 36 secret knockout blows without fists, many one-fingered headlock breaks, etc. New complete illustrated course by world-famous instructor, only 25c today. S. J. Jorgensen, 631 Maritime Bldg., Seattle, Wash.

ANTIQUES, RELICS INDIAN GOODS

100 GOOD ancient arrowheads \$3.00; Tomahawk head 50c. Flint knife 25c. Illustrated catalog 5c. H. Daniel, Hot Springs, Ark.

CASH for flintlock pistols. Locke, 3807 Ault Park Rd., Cincinnati, Ohio.

AUTHORS' SERVICE

IF you have a short story you want revised, typewritten and marketed, write. Hursh Service, Box 8-1013, Harrisburg, Pa.

WRITER wants rejected stories. Submit manuscript. Weldon Tinney, Winnsboro, Texas.

AUTOMOBILES

MIDGET autos! Plans, parts, building kits. New catalog-plan book, 10c. Latest lists used motors, midgets parts (direct owner prices), 20c. Circulars free. Shippe Midgets, Box 513-K, Zanesville, Ohio.

AUTO SUPPLIES & EQUIPMENT

CONVERT your car to burn Diesel oil. Save up to 70% fuel costs. Cheap installation. Wonderful performance. Proven factory method. Different and better. Costs nothing to investigate. Write for free circular No. 3. Harrington Company, 201-204 Manchester Bldg., Portland Ore.

AUTO Kinks—A service and repair manual for the auto owner who is not a mechanic. What to do no matter what goes wrong. Fully illustrated only \$1.00 postage. Eugene Watson, Dept. C88, 353-4th Ave., New York.

ECONOMY! Performance! Mileage! Semi-diesel conversions for gasoline motors. Manufacturers written guarantee. Learn basic facts from free literature. Houston & Logan Conversions, 2021 Grove St., Berkeley, Calif.

SEMI-DIESEL conversions for auto. Other gasoline engines save 65% \$5 up. Trial guarantee. Agents wanted. Diesigas, 355 Santa Clara, Oakland, Calif.

AUTO TRAILERS

BUILD the famous, low-cost Jim Dandy Cabin Trailer. Complete plans and instructions 50c. Plans to build the beautiful streamlined Jim Dandy Cabin Cruiser, \$1.00. Trailer Builders Manual and catalog of trailer parts, supplies and equipment—over 100 interesting, illustrated pages. 25c Order today. Satisfaction guaranteed. Trailer Supply Co., 411-B Jackson St., Wausau, Wis.

AVIATION

GET into aviation. Air transport pilots get up to \$6,000 per year, mechanics \$2,500. Learn at this Government approved school. Write for complete information. State age. Lincoln Flying School, No. 2101, Aircraft Building, Lincoln Nebr.

AVIATION apprentices. Good pay—big future. Write, immediately, enclosing stamp. Mechanix Universal Aviation Service, Strathmoor Station, Dept. H-2 Detroit, Mich.

PROPELLERS for airplanes, sleds. Also licensed blueprints. Catalog dime. Lorenzen Propeller Company, Niles, Mich.

PROPELLERS sled, airplane, catalogue free. Woodcraft Propellers, General Delivery, Dallas, Texas.

NEGATIVE gravity! Described in levitation treatise. 25c coin. Dennis, Osgood St., Pittsburgh, Pa.

GETTING ahead in aviation! Folder for stamp. Meyer, Box-8, Hempstead, N. Y.

BATTERIES, GENERATORS, ETC.

EDISON storage batteries for lighting and power. Non-acid. Odorless. Fifteen year life. Five year unconditional guarantee. Reasonably priced. Tremendous savings in battery and light plant combinations. Free illustrated literature. See-Jay Co., 87 Sterling Ave., Yonkers, N. Y.

EDISON lifetime storage batteries for light and power. Eliminate acid battery diseases. Long guarantee. All kinds rebuilt generating plants, motors, and miscellaneous articles at bargain prices. Free interesting literature. W. Hawley Smith Company, Croton Falls, N. Y.

BLUEPRINTS & PLANS

FIFTY cents brings you a book containing complete instructions, diagrams and specifications for building fireplaces at less than half cost. Fireside Company, Albany, Ore.

ELECTRICAL or mechanical development and blueprints of your ideas. Send \$1.00 copyrighted blueprints Caryvan table, P. O. Box 381, Grand Central Annex, New York.

COMPLETE solar heater plans \$2.00. Sunshine will heat water for your home. Emerson Solar Heater, Escondido, Calif.

BOATS, OUTBOARD MOTORS, ETC.

SHIP model construction sets, blueprints. Largest and finest selection of separate fittings. Leading manufacturer of model racing yacht fittings and sails. Send 20c (coin) for illustrated catalog. A. J. Fisher, 1002-S Etowah Ave., Royal Oak, Mich.

BUILD a boat by the Welch System. Save on the cost. Welch ready cut parts are inexpensive. Send 10c for complete catalog of boats, marine hardware and Welch white cap marine motors. Welch Boat Co., Station K-9 Milwaukee, Wis.

NEW book shows how to make any ship model. Short cuts, kinks, plans, 100 illustrations, only \$1.00 postpaid. Eugene Watson Dept. C-88, 353-4th Ave., New York.

FORD marine conversion parts and kit assemblies all models. Catalogue 25c (coin). Osco, 3105 Rosehill, Philadelphia Pa.

BUILD 12' outboard rowboat, 12' Kayak patterns, each \$1.00. Circular, dime. Henry Bakewell, 44 Billings St., Lowell, Mass.

KAYAKS, kits, blueprints. Illustrated catalogue 10c. Viking Kanoes Co., Merrick, N. Y.

BODY-BUILDING COURSES

EXERCISE equipment, courses. Special offers! Free booklet. Good Barbell Co., Dept. 6, 947 Elm, Reading, Pa.

BUILD IT YOURSELF

BUILD Power Scooters, Midget Cars. We supply tires, wheels, motors etc. Lowest Prices. Build-up-own Devices, 5240 Lake, Chicago.

BUSINESS OPPORTUNITIES

PLASTEX Industries offer industrious men an opportunity to start a business of their own manufacturing art goods, novelties and utility products in Plastex and marble imitation. 4c material makes regular 10c store sellers. Rubber moulds furnished for speed production. Small investment brings big returns. Nationwide demand in these low priced goods. Ambitious men have chance for real prosperity. Plastex Industries, Dept. S, 1085 Washington Ave., New York, N. Y.

REVOLUTIONARY new industry can make you independent. Grow vegetables, flowers, without soil, year round, small space. Supply chemicals, instructions, formula, bibliography—all \$1.00 postpaid. Chemiculture, 4701-PS Sheridan, Chicago.

HERE'S a real opportunity. If you want a business of your own that is substantial money maker right now and has unlimited future, and if you have \$500 cash to operate a business in an industry which Roger Babson predicts will, in ten years, be larger than automobile industry is today, write Department 21, Box 187, Lafayette, Indiana, for complete details.

COLOR-GLAZED concrete pottery, tiles, walls. Make 2,500 designs concrete lawn pottery without molds, power or costly tools. Cheap materials. Build own equipment from our plans. Money-making business for men. Booklet, colorplate, details 10c. National Potteries, 17 West 28th, Minneapolis, Minn.

MAKE your own perfumes. Get fully equipped perfume laboratory. Formula book and supplies to make over 50 different high quality perfumes. (Tremendous profits). No experience necessary to learn and earn. Send for free pamphlet. J. A. Winn Chemical and Laboratory Supplies, 124 W. 23rd St., New York.

ARTIFICIAL marble sanitary flooring. Instruction covering wood or cement flooring 1/2 inch thick, fireproof, all colors, low cost, ornamental casting, concrete, plaster, papier-mache, garden furniture, statuary, flexible molds, particulars free. C. Mahler, Elmont, N. Y.

FASCINATING business. Repair, adjust typewriters, adding machines. Learn easily at home from factory expert. Earn up to \$15.00 daily. Complete instructions covering all makes \$3.00 postpaid or sent C.O.D. Adding Machine Equipment Service, 3601 Michigan, Dept. 174C, Chicago.

WE start you in business, furnishing outfits and instructions, operating Specialty Candy Factory home. Men and women earn \$25 up to \$60 weekly, all or spare time. (Our 28th year.) Booklet free. W. Hilyer Ragsdale, Inc., Drawer 14, East Orange, N. J.

\$2.00 STARTS you in profitable Electroplating business at once. Will furnish outfit, simplified instruction book and supplies. Send for free pamphlet. J. B. Winn Chemicals & Laboratory Supplies, 124 W. 23rd St., New York.

MAKE artificial marble, glazed tiles, uncanny. Tabletops, plaques, floors, hones, novelties. Hard, fireproof, inexpensive, cement secrets. Brilliant tile and liquid rubber samples 3c. John J. Payn, 945 Grande Vista Ave., Los Angeles, Calif.

COLOR concrete surfaces with chemical solution. Beautiful pottery without moulds. Garden washings, wells, Stucco rock. Glazing concrete. Sample 10c. Hollywood Cement Craft, 8530 Wonderland, Hollywood, Calif.

PROFIT with new products. Make, sell, repeat. Analysis Research. Guaranteed formulas. Biggest catalog free. Special prices, leads. Gibson Laboratory, Chemists, FC-1142 Sunnyside, Chicago.

LEARN arc welding—A growing industry with great opportunities. Consult your local school, or if there is none available write The Lincoln School of Welding Dept. B, Box 5754, Cleveland Ohio.

ATTENTION photographers! Increase profits substantially by taking photocopies (commonly called photostats) with your regular camera. No film, no prism, details free. The Barbour Mfg. Co., Warren, Ohio.

MEXICAN leather pictures. 100% profit, easy sales. 50c (stamps) bring \$2.00 worth samples, details. Refunded if unsatisfied. Mexicanart-P, Apartado 1593 Mexico City.

SAVE money, electric shaver \$4.75; Chemi-Grow \$1.00; office supplies; money making books; stamp brings folders. Lightning Speedz, Streator, Ill.

FREE booklet describes 107 plans for making \$20-\$100 weekly, in home or office, business of your own. Elite Co., 214-A Grand St., New York.

"GOLD Band Mallet." 52 page magazine chockful money-making tips, opportunities, only 10c. Berts, Box 1436 Long Beach, Calif.

FLEXIBLE automobile fender guide. Spring staff, variety replaceable ornaments. Write: E. R. Jorgensen, Lewistown, Mont.

COUNTRY Drives or movies afternoons! Work mornings home. No canvassing! Folios, Station D, Los Angeles.

OPPORTUNITIES Aplenty! Money-makers that "click"! Unusual "idea" service! Particulars free! Cee-Tee Company, C-1079 Madison St., Brooklyn, N. Y.

"QUESTION"—Where can I get jewelry, gifts, necessities at discounts? Answer—Frank Milligan Co., Jefferson, Iowa. Send for free catalog.

LIKE to draw? Earn steady income tracing and duplicating cartoons for advertisers. Adservice, Argyle, Wis.

WHERE to buy at wholesale 500 000 articles. Free directory and other valuable information. Maywood 88 Publishers, 925 Broadway, N. Y.

CONDUCT your business from Chicago! Business, personal mail re-mailed to you daily. \$1 monthly. General, 108 North Dearborn.

"SUCCESS Beacon". Fifty pages moneymaking opportunities, ideas, articles! Dime, Jay, Publishers, 6054-R Kenwood, Chicago.

SELL by mail! Books, novelties! Bargains! Big profits. Particulars free. C. Eliseo, 438, North Wells, Chicago.

FREE! Big book explaining rubber mold-making, statuary casting, etc. Write Stewart, 2927 Wilcox, Chicago.

FOR an extremely profitable lifetime business, operate a Collection-Credit Agency. Free folder. Cole Associates, Syracuse, N. Y.

WHERE to buy at lowest wholesale prices. Information free. Yorena, Box M 312, Bayonne, N. J.

MAKE your own rubber molds Sample and details free. June, 101-A Beech, Holyoke, Mass.

COSMETIC and chemical formulae and analyses. Abon Co., Cleveland, Ohio.

ADDED income ideas. Mail Sales News magazine, copy 10c. Katz, 4254 No. Kimball, Chicago.

HANDY men—Earn money home operating community "Fix-It" Shop. Stafford, Makanda, Ill.

IF you have some spare room, a basement or garage, where you can do light work, we can offer you a profitable proposition for 1938 casting 5c and 10c Novelties, Ashtrays, Toy Autos, etc., for firm of many years standing. No experience necessary as we furnish full instructions with moulds. A rare opportunity to devote your spare or full time to profitable work. For details write: Metal Cast Products Co., Dept. E, 1898 Boston Road, New York City.

BUSINESS SERVICE

INFORMATION—Where to buy anything! Addresses of any manufacturers, wholesalers. 50c (coin). Universal Buyers Service, Lakewood, N. Y.

CHICAGO: mail address; branch office; \$1 monthly. Letters forwarded daily. Established 1919. General, 56 West Washington.

CAMERAS, PHOTO SUPPLIES

BASS: at the Camera Cross Roads of the world has just issued a new and sensational Bargaingram No. 235 listing outstanding values in cameras and accessories. Here are a few typical items: Bass's own De-Franne Sport, 16 or 8 shots on 120 roll film with F:3.8 lens, Prontor II shutter, velvet lined case, \$29.75; Dollina II, Range-finder coupled Radionar F:2.9 lens, Compur Rapid shutter, \$49.75; Super Press Bee 6 1/2 x 9 cm film pack and plate with F:2.9 lens, \$59.75, and dozens of other superb values. Order from above or get Bass' free Bargaingram. Write Dept. SP, Bass Camera Co., 179 W. Madison St., Chicago, Ill.

CAMERAS and supplies. Free illustrated photographic almanac listing everything photographic—still, movie cameras, films, lenses—at tremendous savings. Hundreds of bargains, new and used. All guaranteed. We take your old camera or equipment in trade. Write for free copy of new Photographic Almanac and money-saving bargain book—just out! Limited edition Hurry! Central Camera Co., (Photographic Headquarters since 1899), 230 South Wabash, Dept. 8-S, Chicago.

INCOME from your camera instead of expense. Low cost home course teaches you to make photographs for magazines, newspapers, advertisers. Tremendous demand. Earn good money wherever you live. Free book. Universal Photographers, Dept. S, 10 W 33rd St., New York.

MAKE money in photography. Learn quickly at home. Spare or full time. Easy plan. Previous experience unnecessary. Common school education sufficient. Interesting booklet and requirements free. American School of Photography, 3601 Michigan Ave., Dept. 1742, Chicago.

MAKE money selling snapshots—Dime brings hundred page book, complete instructions, markets, real information. Photomarkets, 402-R Evans Bldg., Washington, D. C.

COLOR in your black and white prints. New easy method for toning dozens of photographs in green, blue, sepia, red and brown. \$1.50 brings kit of toners with full instructions, postage prepaid. Torp, 1500 Stone Rd., Dept. 3, Rochester, N. Y.

20% TO 40% discount on films, paper, still or movie cameras. Write: Paramount Co., 327-PS, East 92nd St., New York.

DUPONT superior panchromatic (guaranteed) 35mm 25 foot roll. \$1.30. Optical Laboratories, Larchmont N. Y.

FREE! book, "How to Sell Snapshots." Fomo Company, Canton, Ohio.

CAMERA bargains galore. Get my 1938 Hobbygrams. Hobby Man, Jefferson, Iowa.

MANY makes of candid cameras delivered at cut prices. Catalogue free. Camera Store, Sac City, Iowa.

SAVE up to 30% in film, paper, cameras, supplies. Economy Photo, Greensburg, Pa.

CAPITAL

HOW to obtain capital fully explained particulars free. Star Service, Wapakoneta, Ohio. Established 1934.

CARTOONING, SIGN PAINTING, SHOWCARD WRITING

DRAW instantly without training with the Mur-O-Graph. Guaranteed. One dollar postpaid in U. S. Literature free. Mur-O-Graph, Irving, Texas.

LIKE to draw? Earn steady income tracing and duplicating cartoons for advertisers. Adservice, Argyle, Wis.

LETTERING made easy "A to Z" Two volumes \$2.00. Samples for stamp. Stein Studios, 949 Broadway, New York.

CHALK TALK STUNTS

LAUGH producing program. \$1.00. Illustrated catalog 10c. Cartoonist Balda, Oshkosh, Wis.

CHEMICALS & APPARATUS

HYDRION, the new pH test paper, as simple to use as litmus, but shows these five color changes; red, very strongly acid, orange, strongly acid; yellow, weakly acid; green, weakly alkaline; and blue, strongly alkaline. Merely place small drop on paper, and note color change. With this test you can better control your experimental processes, analyses, raw materials, and finished products. Vial (100 strips) 30c, carton of 4 vials \$1.00. Every experimenter should use "Hydrion" for rapid, inexpensive and wide range pH control. Send stamps to R.P.C. Co., 116 Liberty St., New York City.

HOME Chemist. Amazing new manual shows how to set up and operate inexpensive home laboratory. Many thrilling, practical, useful experiments. Diagrams and illustrations throughout. Only \$1.00 postpaid. Eugene Watson, Dept. C-88, 353-4th Ave., New York.

HANDBOOK for chemical experimenters. Hundreds of experiments, illustrated, 50c. Experiment booklet 15c. Chemical catalogue 10c. Reading Scientific Co., Reading, Pa.

FILE your small samples. glass vials in partitioned and indexed cases. Each sample easily visible. Instantly available. Invaluable to chemists, biologists and mechanics. Your collection soon becomes irreplaceable. Send postal card for descriptive leaflet or 15c for an assortment of 4 special vials. R.P.C. Co., 116 Liberty St., New York City.

FREE chemistry catalog. Supplies at 5c! Equip complete laboratory. Send 3c for postage. Kemkit Scientific Corporation, 397B Bridge Street, Brooklyn, N. Y.

ANALYSIS. Research. Newest guaranteed formulas. Biggest catalog free. Special prices, leads. Gibson Laboratory, Chemists, FD-1142 Sunnyside, Chicago.

WIN 1938 award on honor roll of amateur chemists. Full particulars and catalog, 10c coin. Clinton Chemical Co., Swedesboro, N. J.

CHEMICALS in 5c quantities. Catalog 5c. Fleischer's Laboratories, Everett, Mass.

DETECTIVES

DETECTIVES earn big money. Make secret investigations. Experience unnecessary. Detective particulars free. Write, George Wagoner, 2640-F Broadway, N. Y.

DOGS, BIRDS, PETS

OLD English sheepdogs. Unusual! Unique! Devoted! AKC Typical Custer Kennels, New Rumley, Ohio.

EDUCATIONAL & INSTRUCTION

WORK for "Uncle Sam." Start \$1260-\$2100 year. Steady increase. Dependable. Men-women. Try next announced examinations. Common education sufficient. List jobs, particulars telling how to qualify for them, and sample tests—free. Write today Franklin Institute, Dept. W49, Rochester, N. Y.

500,000 used technical and business books. Sold, rented, exchanged. All subjects. Satisfaction guaranteed. Cash paid for used books. Complete details and illustrated bargain catalog free. Send name. Nelson Co., 3333 Manhattan Bldg., Chicago.

USED correspondence courses and Educational Books sold or rented. Inexpensive. Money-back guarantee. Write for Free Catalog listing 4000 Bargains. (Courses bought). Lee Mountain, Pisgah, Ala.

RADIO engineering, broadcasting, aviation and police radio, servicing, marine and Morse telegraphy taught thoroughly. All expenses low. Catalog free. Dodge's Institute, Popular St., Valparaiso, Ind.

GROWING plants without soil. Instructions on equipment, mixing and use of chemicals \$1.00. Dawson and Dorn, 4615 West Washington Blvd., Los Angeles.

BUSINESS improving. Thousands positions opening everywhere. Instructive information free. Write. Employment Counsellors, Box 1283E, Milwaukee, Wis.

LEARN the answers and make big money inside legal information. 25c. Dept. D, 234 Hurst Bldg., Buffalo, N. Y.

LEARN tool, die, machinist work, screw-machines Booklet "Q" free. Allied School, 615-W Lake, Chicago.

BECOME a columnist. Pamphlet free. 10 years experience. Ben Arid, Station D, Los Angeles.

"SHORTHAND Simplified" \$1.00. Lesson 10c. Teaching opportunities. Simmons, 8-Rocky Hill, Conn.

ELECTRICAL SUPPLIES & EQUIP.

ELECTRO-Scribe. Electric Pencil writes engravings all metals. \$1.00 postpaid. Details free. Beyer Mfg. Co., 4515-Z Cottage Grove, Chicago.

MAKE money Rewind auto generators, washing machine motors. Make A.C. Welder. Each book \$1.00. 10c brings particulars, catalog winding materials. Ernest Knight, La-Salle, Ill.

ENGINES, MOTORS, ETC.

BE a Diesel Expert. A B C's of Diesel Engines shows how. All about pressure, volume, speed, heat, fuels, starters economies. How to take advantage of opportunities in this new field. Profusely illustrated only \$3.00 postpaid. Eugene Watson, Dept. C88, 353-4th Ave., New York.

REFRIGERATION motor rewinding data. 80 motors listed, \$1.50. Motor Data, Box 7631, Kansas City, Mo.

FARM LANDS

ADIRONDACKS. Sportsmen Paradise. Free folders. Charles Tyre, Corinth, N. Y.

FENCING

FENCING equipment. Folds, swords, masks, etc. Low prices. Free catalog. Industrial Products, Dept. PS 18, 48 West 48th Street, N. Y.

FIELDGLASSES, TELESCOPES & MICROSCOPES

WONDERS Through the Microscope. Fascinating new book tells all about microscopy. How to use equipment, secure and preserve specimens. Take photomicrographs, etc. Cloth bound, fully illustrated \$1.00 postpaid. Eugene Watson Dept. C88, 353 Fourth Ave., New York.

MICROSCOPES. Slide making supplies, reagents, and stains. Send for free circular M38. Biological Supply Company, 1176 Mt. Hope Avenue, Rochester, N. Y.

TELESCOPES. Microscopes, Binoculars: 1938 bargain catalog free. Brownscope Company, 5 West 27th Street, New York.

USED microscopes, binoculars, astronomical telescopes—Bought, sold, repaired. Send 10c for list. Rasmussen, P.O. Box 294, Amsterdam, N. Y.

FREE instructions. Make powerful astronomical telescope in one evening. Extremely low cost. Atemaco, Box 213R, Flushing, N. Y.

MICROSCOPES, mineralogy, chemistry, telescopes, binoculars. Catalog free. Tracey Laboratories, Evanston, Ill.

BUILD reflecting telescope 6" kit. \$3.50. Instructions 10c, catalog free. Optical Labs., Larchmont, N. Y.

TELESCOPES, binoculars, microscopes 1938 Bargaingrams free. Hobby Man, Jefferson, Iowa.

BUILD an astronomical telescope. Catalogue free. John Pierce, Springfield, Vt.

FOR THE HOME

ENGRAVED metal name plates. Rust proof. No polishing required. Last forever. Free Circular. Edward Lock, Box 1476, Washington, D. C.

FOR INVENTORS

PATENT your idea. Write immediately for two free books, "Patent Protection" and "When and How to Sell an Invention." Fully explain many interesting points to inventors and illustrate important mechanical principles. With books we also send "Evidence of Invention" form. Prompt service, reasonable fees, thirty-nine years' experience. Avoid risk of delay. Address: Victor J. Evans & Co., Registered Patent Attorneys, 59-J, Victor Building, Washington, D. C.

UNPATENTED ideas can be sold. I tell you how and help you make the sale. Particulars, with list of manufacturers and wanted inventions, sent free on request. Write Wilson Holmes, 916 Barrister Bldg., Washington, D. C.

INVENTORS: Secure immediately effective patent protection through simple, direct filing, but pay single Government fee only. Complete details, free. American Patents Corp., Dept. 30E, Washington, D. C.

BUYERS located meritorious patented, unpatented inventions. Descriptive booklet, disclosure form free. If you will sell, write us immediately. Invention Reporter, S-11236 South Fairfield Chicago.

HAVE you a sound practical invention for sale, patented or unpatented? If so, write Chartered Institute of American Inventors, Dept. 3-A, Washington, D. C.

INVENTIONS promoted. Patented, or unpatented. Write Adam Fisher Company, 183 Enright St. Louis, Mo.

CASH for unpatented ideas. Stamp appreciated. Mr. Ball, 9441-B Pleasant, Chicago.

IF you have a practical invention for sale, write National Service Bureau, Dept. K-1, St. Louis, Mo.

FORMULAS, PLANS, ETC.

FORMULAS: 15 proven moneymaking formulas \$1.00. (Not stock-formula catalogue stuff), real unusual offers. List free. Marvel Laboratories, 6629 No. Maplewood, Chicago.

ANALYSIS. Research. Newest guaranteed formulas. Biggest catalog free. Special prices, leads. Gibson Laboratory, Chemists, FA-1142 Sunnyside, Chicago.

THAXLY formulas for perfect products. Accurate analysis assured. Resultful research. Catalog free. P. Thaxly Co., Washington, D. C.

GUARANTEED formulas. Lowest prices. Catalogue free. Kemico, 500-H Park Ridge, Ill.

SHAVING and vanishing creams inexpensive and easily made. Formula 10c. P. O. Box 381, Grand Central Annex, New York.

SELL, mail order biggest profit item today. Details dime. Leland, 4701 Sheridan, Chicago.

FORMULAS—Latest Money Makers. Literature Free. E-Belfort, 4042 N. Keeler, Chicago.

100 DOLLAR formulas 5c each. Literature free. Pacific Laboratories, San Pablo, Calif.

GAMES, ENTERTAINMENT

PASTIME for the whole family. 1000 problems. Interesting and educational. 25 cents. No stamps. Watchman's Puzzle, 105 Brookview Ave., Troy, N. Y.

HELP WANTED

M. M. earned \$267, three weeks, raising mushrooms in cellar! Exceptional, but your cellar, shed perhaps suitable. We buy crops. Book free. United, 3848 Lincoln Ave., Dept. 237, Chicago.

FOREST jobs available \$125-\$175 month. Cabin, hunt, trap, patrol. Qualify immediately. Write Rayson Service, C-61, Denver, Colo.

HIGHGRADE SALESMEN

SALESMEN sell suits on our easy credit plan. Free suits and pants given as bonus besides large cash profits, premiums and gifts. Sell only (5) suits to get a free suit. No limit to number of Free garments you may earn. Wholesale prices \$17.95 and up. Sample line Free. No experience needed to make easy sales. All garments individually cut and tailored to measure. Satisfaction or money back guarantee. Three Star Clothes, Inc., 330 South Franklin St., Dept. CW1, Chicago, Ill.

\$50 WEEKLY possible from start placing nationally advertised counter Card goods with stores. Chance to double earnings in few weeks. Most unusual selling opportunity in wholesale field. Permanent connection. World's Products Co., Dept. 8883, Spencer, Ind.

BIG cash daily: Cash bonuses regularly. Sell sanforized shirts, ties, hose, underwear direct to wearer. Guaranteed full year. Sensational style and quality features. Sales outfit free. Write today. Dept. PE-8 Roseliff-Quaker, 1239 Broadway, New York.

MAKE more money with Red Comet Automatic Fire Extinguishers. Low Price. Proved seven years. Splendid sales outfit free. Some good territory open. Exclusive. Write quick. 744 Red Comet Building, Littleton, Colo.

MAGIC electric brush. Retail \$1.50. Your profit 75c. Uses static electricity. No wires, batteries or expense. Carry in your pocket. Unbreakable. Send for sample and particulars. Donald Brush Company, Household Division, Camden, N. J.

MAKE up to \$50.00 weekly part time selling top quality advertising book matches at low prices. Experience unnecessary. Full time profits unlimited. Free sales kit and zipper case. Match Corporation of America, Dept. N-8, 6041 West Grand, Chicago.

IF you are ambitious you can make good money with a Rawleigh Route. We help you get started. No capital or experience needed. Steady work for right man. Sales way up this year. Write Rawleigh's, Box H-2-PSC, Freeport, Ill.

NEW invention. No competition. Sell service stations and car owners. Write today for territory. Box 863, Des Moines, Iowa.

HOBBIES, COLLECTIONS

FREE. Combination pencil-lighter with purchases of cellophane envelopes for stamps, covers, coins. Samples 10c. Wetzel, Box 235P, North Bergen, N. J.

HOME CRAFTSMEN

"THINGS to make for the camp and game room and how to make them." Working drawings, perspective sketches, and suggestions for making 27 useful articles. 50 cents. Manual Arts Press, Second Floor Duroc, Peoria, Ill.

DESIGN your own furniture. Our complete course shows you how. Only \$8.50. Invaluable to home craftsmen. Write for descriptive folder. Klok Institute, 430 Lyon, Grand Rapids, Mich.

MEXICAN designs for making pictures from wood. 20 patterns complete instructions 25c. 10 full-sized lawn ornament patterns 10c. Mexican Arts, Crafts, Box 332, Eagle Pass, Texas.

"THINGS to make for the lawn and garden and how to make them." Working drawings, perspective sketches, and suggestions for making 27 useful articles. 50 cents. Manual Arts Press, Second Floor Duroc, Peoria, Ill.

26 FULL-SIZED lawn ornament patterns of animals, birds, etc. 25c. 20 full-sized silhouette patterns 25c. 20 full-sized novelty patterns of book ends, door stops, etc. 25c. Modern Woodcraft, Saginaw, Mich.

JIG and band saw blades, venetian blind supplies. Literature upon request. Four assorted plain end jig saw blades 10 cents prepaid. Homecraft Supply, Box 101, Aurora, Ill.

EVERYTHING needed to whittle 6 ornamental Scotties. Complete kit and instructions only \$1.00 prepaid. Eugene Watson, Dept. C88, 353-4th Ave., New York.

KNOCKDOWN furniture, lumber, veneers. Illustrated catalog 10c. Giles Kendall Co., Dept. 101, Decatur, Ala.

INVENTIONS WANTED

SMALL inventions wanted by manufacturers. I'll help you sell your invention. Write for free circular. S. Hull, 7829-M Euclid Avenue, Cleveland, Ohio.

INVENTIONS—Patented, Unpatented. Bought outright, royalty Write. Arellano-Power Co., 1 LaSalle, Chicago.

MACHINERY, TOOLS & SUPPLIES

SHURGRIP, a new powerful internal pipe wrench, removes broken pipe and nipples without damaging threads, pamphlet. Gooding, Machine Works, 6822 26th North East, Seattle, Wash.

SOUTH Bend 9" lathe milling attachment, universal movement, \$9; threading dial indicator, \$3; circular free. Unique Manufacturing Co., 4807 No. 31st Ave., Omaha, Nebr.

USED power tools, workshop equipment—direct owner prices. Buy or sell thru our service. Latest lists, 20c. Toollisting, Box 581-K, Zanesville, Ohio.

LAWNMOWER parts—all makes of mowers. Write for free catalogue. Calhot, Miami, Fla.

MAGIC TRICKS, PUZZLES, JOKER NOVELTIES

FREE! Magic Catalog 500 tricks. Amaze. Mystify friends. Write today! Lyle Douglas, Station A-1, Dallas, Texas.

FREE! Magic Catalog 500 tricks. Fraternity! Monthly magazine, sample 10c. International Magicians, Mt. Morris, Ill.

MAGICAL Coin and large magic catalog 25c coin. Gem, D-26, Wollaston, Mass.

MAGIC catalogue, latest tricks, 10c. Lane Co., Little Bldg., Boston, Mass.

LARGE Professional magic catalog. 25c. Holden, P-220 W. 42nd St., N. Y.

MANUFACTURING

ANALYSIS. Research. Newest guaranteed formulas. Biggest catalog free. Special prices, leads. Gibson Laboratory, Chemists, FE-1142 Sunnyside, Chicago.

"COLLECTION of moneymaking formulas and processes" by Dr. Cummings, obtainable only from us. Circular free. B. Grinstead, 505 Fifth Ave., New York.

MISCELLANEOUS

DEVELOP pictures yourself. Camera, films, developing chemicals, printing materials, complete photographic outfit \$1.00. Spanier, 100 Forsyth, New York.

STANDARD Electric Lamp Insect Killer, \$2.00 up. Literature free. Sauer Bros., 14822 Foothill Blvd., San Leandro, Calif.

SEND your old discarded fountain pen with 50 cents for beautiful, perfect writing, guaranteed fountain pen. Pen Exchange, Flagler, Colo.

FREE literature how to locate buried treasure and minerals. Fisher Laboratories, Palo Alto, Calif.

IF you have something to trade send ten cents to Dept. P-8, Swapper's Guide, Delphos, Ohio.

TWELVE in one shop page 39c. Money back guarantee. Stamps accepted. Jensen, 336 Linden St., Brooklyn, N. Y.

MODELS & MODEL SUPPLIES

CATALOGUE of over 40 engines—castings—supplies, 25c. Refunded. Howards, P-2417 North Ashland, Chicago.

NEW book shows how to make any ship model. Short cuts, kinks, plans, 100 illustrations, only \$1.00 prepaid. Eugene Watson, Dept. C88, 353-4th Ave., New York.

RAILWAY models. Catalog hand-book 25c. Walther, 250 E. Erie, Milwaukee.

HO Railroads. List 6c. Lange's, E. Jackson, R.818, Chicago.

MONEY MAKING OPPORTUNITIES

MAN in each town to Plate Auto Parts, Reflectors, Bicycles. Fixtures, Mirrors, by late method. Simple plan of manufacturing at home starts you in good paying business. Free particulars and proofs. Gunmetal Co., Ave. G., Decatur, Ill.

LIKE to write? Earn extra money preparing newspaper clippings for publishers. Simple, fascinating, profitable. Stamp brings details. Div. 31, National Press, Hohm Bldg., 6th and Western, Los Angeles, Calif.

SUCCEED. With your products. Make—Sell Them. Formulas, Processes. Accurate Analyses. Catalog Free. P. Thaxly Company, Washington, D. C.

EARN money collecting reptiles, toads, frogs. We buy all varieties. Splendid opportunity. Information free. Biological Research Laboratories, Dept. 15A, Springfield, Missouri.

DRAW-O-MATIC Portable drawing boards make fast, accurate drawing simple. Money-making proposition. Rollin Products Co., 216 N. Clinton, Chicago, Ill.

LAWNMOWERS kept ever sharp with Super-Flex. Huge profits. Millions waiting. Sample and information \$1. Loyalty, 3 Church & Main Bldg., Orlando, Fla.

"RAISE Earthworms for Profit" Information Free. Stamp Appreciated. Bureau Zoological Research, 106 P Broadway, Peoria, Ill.

INVENTION Finance Magazine, 80-N Wall Street, New York. Year subscription 60c. entered upon promise to pay on receipt of first copy.

ALL-profit mail order business. Brings dollars daily! Aids millions jobless. Co-Operative Service, 77 Swan, Room 213, Buffalo, N. Y.

MONEY by mail galore. Nearly all profit. We tell you how. Stamp appreciated. Homecraft Arts, Lakeside, Calif.

\$35.00 WEEKLY from 3 hours' home-work. 204 other moneymaking plans. Particulars free. Stamford, 836-S Riverdale Drive, N. Y.

EARN money addressing envelopes, circulars, typing. Information 10c. None free. Ace-PSMD, 323 Empire, Birmingham, Ala.

FOR an extremely profitable lifetime business, operate a Collection-Credit Agency. Free folder. Cole Associates, Syracuse, N. Y.

"RESULT Getter," monthly magazine of money making opportunities, copy 10c. G. Fenner, 1618 Lucia, Louisville, Ky.

90% PROFIT mailorder opportunities. Literature free. Harvey Teeple, Decatur, Ind.

AFTERNOONS Free! \$300 mo.—home! No canv. Expect surprise! Folio, Sta.-D, Los Angeles.

PRACTICAL money making plans; literature free. Silvester, LB217, Old Bridge, N. J.

SELL by mail. Suggestions free. Steinger, 706 West North, Pittsburgh, Pa.

67 PROVEN moneymaking plans. 25c. Frank Turack, 121 Staer Bldg., Export, Pa.

MOTION PICTURES & SOUND EQUIPMENT

AMBERTINT 16mm camera film, 100 ft. for \$1.95, including machine processing. Daylight loading. Weston six. Order now. Hollywoodland Studios, South Gate, Calif.

NEW 200 watt 8mm projectors \$19.50 prepaid. Automatic 16mm cameras \$22.50 prepaid. Free 16mm, 8mm lists. Home Movies, Box 2163, Easton, Pa.

CAMERA 8mm bulk film, 100 ft. for \$1.00 postpaid; for Univex, Keystone and Filmo, Processed with powders. Circulars free. Fromaders, Davenport, Iowa.

16mm VELOTEX. Perfect outdoor film. 50 foot rolls \$1.29, 100 feet \$1.95, including processing. Sample free. Velotex Laboratories, Box 600B, Gary, Ind.

MOVIE cameras and projectors. Monthly payment plan. Booklet free! Don Elder, C-739 Boylston, Boston, Mass.

LEARN motion picture theatre management, advertising, projection. Free catalog. Give age. Theatre Institute, 375 Washington, Elmira, N. Y.

8-16MM. titles, 2c word—backgrounds, trick effects Detailed literature. Cine Shop, 1812 Piedmont, Charleston, W. Va.

With your own 16mm stainless steel outfit \$7.95. 100 ft. film \$1.25. Formulas free. Boyd Laboratory, Ashton, Ill.

MOTORCYCLES, BICYCLES & SUPPLIES

RECONDITIONED Motorcycles. New-used parts for all makes. Authorized Harley-Davidson Dealer. Whitman Motorcycle & Supply Co., 405-9 Southwest Blvd., Kansas City, Mo.

SEND 15c for Illustrated Used Motorcycle Catalog. Bargains. Largest stock, genuine Indian Parts and Motorcycles. Indian Motorcycle Sales, Kansas City, Mo.

MOTORCYCLE bargains, lowest prices, bargain sheets for stamp. Motorcycle accessories. Rochester Harley Davidson Corp., 129 W. Main St., Rochester, N. Y.

MUSIC, MUSICAL INSTRUMENTS

SONG poems wanted immediately. Marvelous opportunity. Inquire Fred Strasser, 1412 Great Northern Bldg., Chicago.

LEARN swing piano! Postal brings free folder. Christensen, 765 Kimball Hall, Chicago.

VIOLIN-making supplies, patterns, instructions Free catalog. Fraser, 2028 Stark, Saginaw, Mich.

MUSIC composed to songpoems. Orchestration arranged. Frank Wildt, Lancaster, Pa.

ORCHESTRATIONS, popular back-numbers 10-\$1. Sheetmusic 20-\$1. Silverman, 3303 Lawrence, Chicago.

PATENT ATTORNEYS

INVENTORS: send immediately for your copies of our new free books, "Patent Protection" and "Suggestions on Selling an Invention." Sixty-eight pages of interesting facts. They tell how Patent Laws protect you; kind of sketch or model needed; simple steps to take without cost; how successful inventors have secured financial assistance; show interesting inventions; illustrate important mechanical movements. With book we also send free Evidence of Invention form to help establish date of disclosure. Prompt service, reasonable fees, special deferred pay-

ment plan. Strictest secrecy. Thirty-nine years' experience. Highest references. Write us today. The facts in our books are worth money to the man with a good invention. Address: Victor J. Evans & Co., Registered Patent Attorneys, 58-J Victor Building, Washington, D. C.

INVENTORS—Time counts. Don't risk delay in patenting your invention. Write for new 48-Page free booklet, "Patent Guide for the Inventor." No charge for preliminary information. Clarence O'Brien and Hyman Berman, Registered Patent Attorneys, 697-F Adams Bldg., Washington, D. C.

WHAT to do with your invention? Free books tell all. Patent facts clearly explained. 63 years experience at your immediate service on easy budget payment plan. Write today for free copies of our booklets and "Certification of Invention" form. C. A. Snow & Co., 285 Snow Bldg., Washington, D. C.

"INVENTOR'S Guidebook" containing 96 mechanical movements and advice about patenting, selling inventions, also "Record of Invention." Free. Frank B. Ledermann, Patent Attorney-Engineer, 154 Nassau Street, N. Y.

PATENTS—trade marks. Preliminary advice, book and disclosure form free. Personal service. Irving L. McCathran, 1050 International Bldg., Washington, D. C., Registered Patent Attorney.

WE successfully sell inventions, patented and unpatented. Write for proof and tell us what you have for sale. Chartered Institute of American Inventors, Dept. 8-B, Washington, D. C.

INSTRUCTIONS "How to Establish Your Rights" and form "Evidence of Conception" sent Free! Lancaster, Allwine & Rommel, 413 Bowen Building, Washington, D. C.

INVENTORS—send for free copy my 72-page book on patents. Reasonable terms. Prompt action. Confidential, personal service. L. F. Randolph, Dept. 340-A, Washington, D. C.

PATENTS. Booklet free. Highest references. Best results. Promptness assured. Watson E. Coleman, Patent Lawyer, 724 Ninth St., Washington, D. C.

RAMSAY Company, registered patent attorneys, free information. 273 Bank Street, Ottawa, Canada.

PERSONAL

AMHTSA. Something new. A great relief for asthma and catarrh troubles. Price \$1.00. J. E. Miller, Box 323, Ashland, Oregon.

HYPNOTISM. Complete 20 Method Course 25c. Western Institute Hypnotism, P-2984 North Ridgeway, Chicago.

NERVOUSNESS, nervous fear! Afflicted? Free, interesting information. Investigate! John Englund, Ontonagon, Mich.

MEN! Shave without razor! Send 25c for formula for self-shaving soap. Carl Greiner, 5112 N. Oakley Ave., Chicago, Ill.

LEARN ventriloquism, 3c stamp brings particulars. Smith, Room 698, 125 N. Jefferson, Peoria, Ill.

DIVORCES. Consent, few days; others, 30. American Attorney, Box 1736, El Paso, Texas.

CONSTIPATED? Send 10c. No drugs. Kraus, 2427 South Harding, Chicago.

PHOTO FINISHING

TAKE your pick! One master natural color enlargement, two beautiful enlargements, or 8 duplicate prints given Free with roll developed and 8 high-gloss prints for only 25c coin. Reprints 3c each. Overnight service. Amazing professional quality must delight you or money back! Sixteen years experience. Sunset Service, 280 Sunset Bldg., St. Paul, Minn.

BE modern! Get modern service, modern quality, modern prices. Our modern methods give quick service and bright guaranteed neverfade pictures. Roll developed 16 prints, 25c coin; 16 reprints, 25c. Enlargement coupon. Send next roll or reprint order to Modern Finishers, Box 3537, St. Paul, Minn.

THE Photo Mill. Immediate service! No delay! Roll developed, carefully printed and choice of two beautiful 5x7 double weight professional enlargements, one tinted enlargement, or eight reprints—for 25c coin. Reprints 2c each. The Photo Mill, Box 629-10, Minneapolis, Minn.

MAIL your rolls to film center of the world. Any 6 or 8 exposure roll developed and printed 25c coin. Deluxe enlargement coupon free! Photo Finishing Shop, Est. 23 yrs., 500 Genesee Valley Trust Bldg., Rochester, N. Y. "The Camera City."

PROMPT service—quality work. Two beautiful double weight Gloss Enlargements, eight guaranteed neverfade prints, each roll 25c. Excel Photo Service, Dubuque, Iowa.

TWO prints each with every roll developed, 25c. Very finest quality. Reprints 2c each. Brown Photo Company, 2209-32 Lowry, Minneapolis, Minn.

IDEAL photos, 25c per roll, finished with round corner prints. Coupon and snapshot folder free with initial order. Ideal Photos, Box 2255, Paterson, N. J.

35mm ROLLS fine-grain developed and enlarged to 2 1/4 x 3 1/4 on Argus Bromex paper, 36 exposures, \$1.00. 18 exposures, 55c. Reprints, 3c each. Economy Photo, Greensburg, Pa.

ROLLS developed—25c coin. Two 5x7 Double Weight professional enlargements, 8 gloss prints. Club Photo Service, Box 52, LaCrosse, Wis.

BEAUTIFUL oil colored enlargement in Deluxe frame, with each roll developed, 25c coin. Badger Studios, LaCrosse, Wisconsin.

ROLL film developed, 1 print each. 2 enlargements, 25c coin. High class work. Quick service. King's Photo, Box 447, Rockford, Ill.

LATEST in photo finishing. Miniature rolls developed, printed 3x4—5c each print. Radio Film, LaCrosse, Wis.

HIGHEST quality reprints 2c; rolls developed, 2 prints each negative 25c; Welch Photo; 2840 Zenobia, Denver, Colo.

LARJARGRAPH finishing: Five 5x7. Enlargements 25c; Miniature rolls, developed 10c; prints enlarged 2 1/4 x 2 1/4 c. Cordinal Photos, Summit, N. J.

BE convinced—Globe photos are unexcelled. 8 Duo-Tone prints, 2 5x7 enlargements. 25c coin. Globe Photo Shop, LaCrosse, Wis.

CONFIDENTIAL developing, two prints each negative 25c. Reprints 2c each. Royal Photos, 3902 North Sixth, Harrisburg, Pa.

ROLLS developed, 2 prints each and 2 free enlargement coupons, 25c; reprints 2c each; 100 or more, 1c. Summer's Studio, Unionville, Mo.

PROMPT service! Rolls developed, two Velox prints, each negative 25c. Hensch Studios, Harrisburg, Pa.

ROLL developed, 16 guaranteed prints 25c. Smart Photo, Winona, Minn.

ROLLS developed, 8 prints, 2 enlargements, 25c. Mayfair, Box 261-A, Toledo, Ohio.

FILMS developed, 16 prints, 2 enlargements 25c. Truefoto, Dept. 42, Des Moines, Iowa.

ROLL finished, 8 prints, 20c. Reprints, 1 1/4 c each. Goodwill Co., Jackson, Tenn.

PRINTING, MULTIGRAPHING, MIMEOGRAPHING, LABELS

1000 3x6 CIRCULARS \$1.00, 6x9 \$2.75; 100 8 1/2 x 11 bond letterheads 60c; 100 6 1/2 envelopes 60c. Everything prepaid. New Era, Buffalo, Minn.

125 LETTERHEADS 8 1/2 x 11 and 125 envelopes, \$1.00 postpaid. Benneville, 907 West Roosevelt, Philadelphia.

6x9 CIRCULARS, letterheads, envelopes, postcards, \$2.95 1000; 5000 \$9.45. Samples, cuts. Goodprint, Harrisonburg, Va.

HAMMERMILL letterheads, 300 8 1/2 x 11, any color paper and ink; \$1.48 postpaid. Free particulars. Woodruffs', 217D Lewis, Duluth, Minn.

50 LETTERHEADS, envelopes and cards or stickers, printed in two colors \$1.00. Bicocan, 2038 O'bear, St. Louis, Mo.

1000 ENVELOPES \$1.75. Prospector's Printing, 515-6th Ave., Brooklyn, N. Y.

HIGHEST grade printing, labels, office supplies. Lowest prices. Okay Print, Martins Ferry, Ohio. Samples.

350 NOTEHEADS 5 1/2 x 8 1/2, \$1.00, postpaid. Keelerprint, 4237 West Cermak, Chicago.

PRINTING OUTFITS & SUPPLIES

PRINT your own cards, stationery, circulars, advertising. Save money. Easy rules furnished. Print for others, big profits. Junior outfit \$9.00. Job presses \$11 up. Details free. Kelley Presses, B-8, Meriden, Conn.

6x9 PRESS \$5.00. Bargain literature free. Novelty Shop, Downsview, Ia.

PROFITABLE OCCUPATIONS

HUMAN efficiency. This surprising little book actually helping workers. \$1. Shertzer, 970 Weber, Pomona, Calif.

MINK raising is fun and highly profitable. Particulars. Empire Mink, Scarsdale, N. Y.

10c BRINGS copy National Mail Order News. Three months 25c, year \$1.00. Box 1773-PSM, Roanoke, Va.

RADIOS, SUPPLIES & INSTRUCTION

BAKELITE panels. Postpaid. Any thickness. \$.03 cubic inch. Hackbush, 1689 Linden, North Tonawanda, N. Y.

SAVE 50% on nationally advertised radios; 88 page catalog free. Model's, Dept. 51, Cortlandt St., New York.

6 BEGINNER'S plans and "Radio-builder"-year, 25c. 15 for 50c. Laboratories, 7700-T East 14th, Oakland, Calif.

SAVE money on radio sets, parts, tubes, etc. Send for new summer catalog. United Radio Co., S-Newark, New Jersey.

REPAIR burnt out radio tubes. Instructions \$1.00. Ducks Manufacturing Co., Freeport, Ill.

RARE COINS

BIG prices paid for certain wanted coins. 1909 cent \$10.00, some silver dollars \$4000, 1864-1865 Indian head cents \$100.00 each, dimes before 1895 \$600, liberty head nickels before 1914—\$500, encased postage stamps, some large pennies \$2000, half cents—\$275.00, paper money, gold dollars \$1500, foreign coins \$165, some worth \$6000 each. You may have coins for which we pay big premiums. Therefore send 15c today for 1938 big illustrated coin book for certain wanted coins. National Coin Corporation (2), Daytona Beach, Fla.

\$5.00 TO \$500.00 each paid for hundreds of Old or Odd Coins. Keep all until posted. Send 10 cents for Illustrated Coin Value Book, 4x6. Guaranteed Prices. 31 years in business. Coin Exchange, Box 31, Le Roy, N. Y.

UNITED STATES, large cent, 2c bronze, 3c nickel and Bargain list, 25c. Eleven dates large cents \$1. George P. Coffin Company, Augusta, Maine.

COMMEMORATIVE half dollars, Lincoln, Texas, Oregon, Stone Mountain, Cleveland, \$1.50 each. New illustrated catalogue 25c. Norman Shultz, Salt Lake City, Utah.

THREE foreign coins and price list 10c. Joseph Coffin, 1182 Broadway, New York.

WE purchase all Indianhead pennies. Purchasing catalogue 10c. Andrew Spanner, 100 Forsyth, New York.

COIN or stamp lists free. 213 South Seventh, St. Louis, Mo.

RUBBER STAMPS, OFFICE SUPPLIES

SAVE half! Typewriters, duplicators, addressographs, dictaphones, check-writers, terms 10c per day 10 day free trial. Write, Pruitt, 974 Pruitt Bldg., Chicago.

NATIONALLY advertised portable typewriters delivered at 20% discount from regular prices. Catalogue Free. Typewriter Exchange, Sac City, Iowa.

SCIENTIFIC INFORMATION

AMAZING 294-page book of fascinating scientific information: Pocket Guide to Science answers questions about the earth, stars, planets, the human body and mind, animals, electricity, radio, chemistry. Explains in simple language, the marvelous reasons for the miracles of the universe, of life, science, physics, evolution, geology, magnetism, motion. With this book handy you'll quickly gain a working knowledge of all these subjects and many more. Eleven complete sections—294 pages, cloth bound. Over half a million copies sold at higher prices—now send only 25c per copy, book will be mailed postpaid, while few remaining last. Eugene Watson, Dept. C88, 353-4th Ave., N. Y.

SONGWRITERS

SONGWRITERS—Send best poems today. Remarkable offer. Free rhyming dictionary and instruction book by famous Broadway composer. Songwriters Institute, 1234-J Broadway New York.

POEM writers, songwriters—Send for free Rhyming Dictionary. Songwriters' Guide. Submit best poems, melodies today for bonafide, superior offer. MMM Studios, Dept. 55E, Portland, Oregon.

MUSIC composed to words. Rhyming pamphlet free. Phonograph recording of song free. Send poem. Just released "Joyce." Copy 25c. Keenan, 259 Beach St., Bridgeport, Conn.

SONGWRITERS: Send your poem today for immediate consideration. Richard Brothers, 146 Woods Bldg., Chicago.

SONGWRITERS wanted, write for free book, 50-50 plan. Song Bureau, Dept. L, Salem, Ind.

SONGWRITERS wanted immediately. Glen Warren, 1560 Broadway, New York City.

SPORTING GOODS, GUNS, FISHING TACKLE, ARCHERY

HUDSON Bay blankets, Indian pack baskets, camp stoves, knives, compasses, outdoor equipment. Free catalogue. Howe Fur Co., Box PS, Coopers Mills, Maine.

EVERYTHING needed to whittle & ornamental Scotties. Complete kit and instructions only \$1.00 postpaid. Eugene Watson, Dept. C88, 353-4th Ave., New York.

SUBSCRIBE to the leading archery magazine. Covers all phases of archery. One dollar per year, 10 cents for sample copy. American Bowman-Review, Albany, Oregon.

HEADQUARTERS for bows and arrows, materials and supplies. Catalogue Free. Instruction Book 50c. Archery, 617 South State, Chicago.

MUZZLE loading rifles match accuracy; no others. Powders, caps, accessories, E. M. Farria, Portsmouth, Ohio.

FINE golf clubs. Regulation size \$25.00. Lincoln Surplus, 123-S Galena, Freeport, Ill.

STAMP COLLECTING

STAMP outfit free! Tannou Touva Landscape Triangle; new Tunafish Triangle from Costa Rica; amazing packet North Borneo (Jungle Scene), Georgia (Dead Country!), Sudan (Desert Scene), a set of the world's smallest stamps, and a Watermark Detector, all absolutely free to approval applicants sending 3c postage! Write today. Midwood Stamp Company, Dept. 8R, Midwood Station, Brooklyn, N. Y.

SUPER-WONDER packet offered containing 60 different stamps from Afghanistan, Transjordan, North Borneo, Manchukuo, Sudan, Guadeloupe, Iraq, Sarawak, French and British Colonies, including natives, beasts, ships, etc.: this entire packet for only 5c to approval applicants. Big illustrated lists free. Kent Stamp Co., Box 87 (11), G.P.O. Brooklyn, N. Y.

FREE stamp catalogue: George VI issue. Giant forty-page quarterly, listing Albums, Supplies, Coronations, Canadians, Colonials, United States and foreign. Illustrations galore! Empire Stamp Co., Dept. P.R., Toronto, Canada.

PRODIGIOUS gift! Fantastic Indochina, German State, Savage Somaliland, Perak, Selangor, Negri Sembilan, Bi-colored Banana Airmail, Siberia—Absolutely free with approvals! Postage 3c. Saxon Co., Dept. B, 408 Jay St., Brooklyn, N. Y.

DIAMOND airport commemorative issue complete; proletarian portraits and famous Dragon stamp with 117 additional, only 10c. Friendly Philatelists, Box 44288, Philadelphia, Pa.

FINE approvals, freshly filed books. Tell me the countries you prefer, and I will send just what you want. M. P. Skinner, 1316 Harding, Long Beach, Calif.

1897 GRANDE Comore, Liberian Bongo Antelope, Turks Caicos, Cayman Islands, genuine Baden, etc. Everything 3c with approvals. Viking, 1-P, Hanson Place, Brooklyn, N. Y.

4 1/2 TRIANGLES' Guatemala Bisect (diagonal half-stamp); beautiful Liberia three additional triangles, 27 other stamps, 5c. Abell Co., 1818-H St. Paul, Baltimore, Md.

DIAMOND shaped stamp, Liberia gunboat triangle two other triangles, silver jubilee, 27 others, 5c. Crowder Co. 127-H E. North, Baltimore, Md.

COSTA Rica diamond airmails, 25 different Canada, 20 different Mexico, 10c with approvals. Rayco, Box 5197, Metropolitan Station, Los Angeles.

EXCEPTIONAL packet. Triangles, commemoratives, constitution, scenes, airmails, 50 others, 3c. Approvals. Far Seas Co., Box 2154, Houston, Texas.

U.S. Packet or your choice from foreign approvals included. Postage please. Wm. Clatworthy, Upland, Calif.

LIBERIA snake triangle, giant Spanish triangle, 50 other stamps, 5c. Wright Co., 2527-d, Guilford, Baltimore, Md.

75 U.S. commemoratives, airmails, Virgin Islands, Alaska. Approval applicants, 5c. Gelburd Stamps, 1180 Gerard, Bronx, N. Y.

140 MANCHUKUO, Siam, Algeria, Brazil Dominican, Mongolia, Paraguay, Cuba, Spain, etc., 10c. Lufbery Middletown, Conn.

PHILIPPINES approvals. Send 10c for postage. References. Afran Stamp, Box 1181, Manila, Philippines.

9 SCARCE airmails from Guatemala, Syria, Lebanon, etc., 5c to approval applicants. Barker, Box 448-R, San Francisco.

25 UNITED States, including \$4 and \$5 stamps free to approval applicants. 3c postage. Brownie Stamp Shop, Dept. P, Flint, Mich.

TEN different nineteenth century United States stamps 1c to applicants for foreign approvals. Spanner, 100 Forsyth, New York.

FREE. Packet to approval applicants. Schramm, 1489 East 19th Street, Brooklyn, N. Y.

IOWA, Delaware, Constitution first days—10c each; Reitter-Imhoff, 111 W. Jackson, Chicago.

NEW book shows how to make any ship model. Short cuts, kinks, plans, 100 illustrations, only \$1.00 postpaid. Eugene Watson, Dept. C88, 353-4th Ave., New York.

100 ALL different Portugal 25c. L.C. Trading Company, Box 38, Bellefonte, N. Y.

POSITIVELY 119 different only 8c, approvals. Alton, 2068 Daly Ave., Bronx, N. Y.

FREE: 50 stamps, Manchukuo, etc. Postage 1c, album 3c. Bullard, 268D Northampton, Boston, Mass.

500 MIXED foreign 10c, approvals included. Hecht Co., 5, Belle Plaine, Iowa.

Fiji, Borneo, 23 other British colonial 3c. Approvals. Porter, Box 863, Springfield, Ohio.

FREE: Two coronation sets. Postage 3c. Roberts, 312U Shearer Bldg., Baycity, Mich.

25 DIFFERENT South American 10c. No approvals. Burkhardt Stamps, Sandwich, Ill.

FREE To approval applicants 101 different stamps, 3c postage. Quality Stamp Shop, Englewood, Colo.

ZEPPELIN Hindenburg scarce 5c, approvals. Frenchco, 241 Euclid, Room 501, Cleveland.

100 DIFFERENT Hungary 7c, approvals. Hazett Stamp Shop, 7015-Fourth, Bay City, Mich.

AT 1/10 catalog—U.S. & British Colonies. Meyerowitz, 1756R-70 St., Brooklyn, N. Y.

500,000 STAMPS! General line approvals. Where? Peterson's, Box 300, St. Paul, Minn.

HINDENBURG Zeppelin (catalogue 35c), 5c with approvals. Shultes, 13P, Berne, N. Y.

25 DIFFERENT Peru 3c to approval applicants. Maynard Sundman, D68, Bristol, Conn.

BARGAIN! 500 beautiful stamps, 25c. Vandal, Box 646, Stamford, Texas.

UNITED States postage, 50 different 20c. Goldsmith, Box 200, Chicago.

SCANDINAVIA, 45 different 10c with approvals. Wollaston Stamps, Wollaston, Mass.

WANTED—MISCELLANEOUS

CASH for used microscopes, binoculars, cameras, slide rules, drawing sets, surveying, mechanical, scientific and musical instruments. Highest prices paid day shipment received. Satisfaction guaranteed or shipment promptly returned. Elman's, 2300-PS VanBuren, Chicago.

NEW book shows how to make any ship model. Short cuts, kinks, plans, 100 illustrations, only \$1.00 postpaid. Eugene Watson, Dept. C88, 353-4th Ave., New York.

WELDING, SOLDERING

DC Arc-welder 25-200 amperes built from North-East (Dodge) automobile generators. Guaranteed plans \$1.00. (Money back if not satisfied). Welders Club of America, WB-3432 M-Mari, Chicago. Airmail or COD 12c extra. Special: Earn money, spare time selling plans, write for details. Agents desired.

FIX It Yourself—Save money by making your own household improvements. New Manual shows how to do hundreds of construction and repair jobs around the house. Fully illustrated cloth bound \$1.00 postpaid. Send your order to Eugene Watson Dept. C88, Popular Science Monthly, 353 Fourth Avenue, New York, N. Y.

75-200 AMPERE arc welder from Dodge generator. Complete plans and valuable catalog 35c. 100 other generator changes. LeJay Mfg., 323 LeJay Bldg., Minneapolis, Minn.


DC Arc-welder 25-600 amperes, build it yourself, use DC motors from battery driven electric trucks, conveyors, mules, etc. Guaranteed plans \$1.00. Welders Club of America, WB-3432 M-Mari, Chicago. Special: Agents desired.

REBUILT electric arc welders, all sizes, a c-d c. guaranteed. Lowest terms. Money-saving prices. Service Co., 3732 Cedar Ave., Cleveland, Ohio.

WIND ELECTRIC PLANTS

BUILD your own electric light plant. Large capacity. No rewinding necessary. Less than \$10.00. State Ignition, 52 Cullerton, Chicago.

GOT a good idea? Make it profitable. Popular Science Monthly Classified Section will advertise it to five hundred thousand men in the buying market. For sure results, send ad with remittance to Bill Corvett, Classified Advertising Manager, Popular Science Monthly, 353 Fourth Ave., New York, N. Y.



ISN'T SHE WORTH FIGHTING FOR?

Are you fair to HER when you let the days drift by without making a real effort to get ahead? Is it right to ask her to scrimp and save and deny herself when with just a little grit and effort you could provide her with the comforts and luxuries she would like to have?

Think this over—then act! Decide today that you are going to get the special training that is becoming more and more necessary in every line of business.

In your spare time that now goes to waste, the International Correspondence Schools will prepare you for advancement and more money.

Find out how—by marking and mailing the same salary-raising coupon that has meant so much to so many other men in just your circumstances.

It doesn't cost you a penny or obligate you in any way to do this. Do it now. Do it for HER.

INTERNATIONAL CORRESPONDENCE SCHOOLS

Box 7640-J, Scranton, Penna.

Without cost, please send me full particulars about the subject before which I have marked X.

TECHNICAL AND INDUSTRIAL COURSES

- | | |
|--|---|
| <input type="checkbox"/> Architect | <input type="checkbox"/> Steam Engineer |
| <input type="checkbox"/> Architectural Draftsman | <input type="checkbox"/> Marine Engineer |
| <input type="checkbox"/> Building Estimating | <input type="checkbox"/> Bridge Engineer |
| <input type="checkbox"/> Contractor and Builder | <input type="checkbox"/> Bridge Foreman |
| <input type="checkbox"/> Structural Draftsman | <input type="checkbox"/> Building Foreman |
| <input type="checkbox"/> Structural Engineer | <input type="checkbox"/> Diesel Engines |
| <input type="checkbox"/> Electrical Engineer | <input type="checkbox"/> Aviation Engineer |
| <input type="checkbox"/> Electric Lighting | <input type="checkbox"/> Auto Technician |
| <input type="checkbox"/> Telegraph Engineer | <input type="checkbox"/> Auto Elec. Tech. |
| <input type="checkbox"/> Telephone Work | <input type="checkbox"/> Plumbing |
| <input type="checkbox"/> Management of Inventories | <input type="checkbox"/> Heating |
| <input type="checkbox"/> Mechanical Engineer | <input type="checkbox"/> Ventilation |
| <input type="checkbox"/> Mechanical Draftsman | <input type="checkbox"/> Air Conditioning & Cooling |
| <input type="checkbox"/> Patternmaker | <input type="checkbox"/> Commercial Refrigeration |
| <input type="checkbox"/> Foundry Practice | <input type="checkbox"/> R. R. Locomotives |
| <input type="checkbox"/> Reading Shop Blueprints | <input type="checkbox"/> R. R. Section Foreman |
| <input type="checkbox"/> Heat Treatment of Metals | <input type="checkbox"/> R. R. Signalmen |
| <input type="checkbox"/> Sheet Metal Worker | <input type="checkbox"/> Air Brakes |
| <input type="checkbox"/> Welding, Electric and Gas | <input type="checkbox"/> Coal Mining |
| <input type="checkbox"/> Civil Engineer | <input type="checkbox"/> Chemistry |
| <input type="checkbox"/> Highway Engineer | <input type="checkbox"/> Fruit Growing |
| <input type="checkbox"/> Surveying and Mapping | <input type="checkbox"/> Navigation |
| <input type="checkbox"/> Sanitary Engineer | <input type="checkbox"/> Agriculture |
| | <input type="checkbox"/> Cotton Manufacturing |
| | <input type="checkbox"/> Woolen Manufacturing |
| | <input type="checkbox"/> Poultry Farming |

BUSINESS TRAINING COURSES

- | | |
|---|--|
| <input type="checkbox"/> Business Management | <input type="checkbox"/> Business Correspondence |
| <input type="checkbox"/> Industrial Management | <input type="checkbox"/> Lettering Show Cards |
| <input type="checkbox"/> Traffic Management | <input type="checkbox"/> Stenography and Typing |
| <input type="checkbox"/> Cost Accountant | <input type="checkbox"/> Civil Service |
| <input type="checkbox"/> C. P. Accountancy | <input type="checkbox"/> Mail Carrier |
| <input type="checkbox"/> Bookkeeping | <input type="checkbox"/> Railway Mail Clerk |
| <input type="checkbox"/> Secretarial Work | <input type="checkbox"/> Grade School Subjects |
| <input type="checkbox"/> Salesmanship | <input type="checkbox"/> High School Subjects |
| <input type="checkbox"/> Service Station Salesmanship | <input type="checkbox"/> College Preparatory |
| <input type="checkbox"/> Advertising | <input type="checkbox"/> First Year College Subjects |
| | <input type="checkbox"/> Illustrating |
| | <input type="checkbox"/> Cartooning |

DOMESTIC SCIENCE COURSES

- | | |
|---|---|
| <input type="checkbox"/> Professional Dressmaking | <input type="checkbox"/> Foods and Cookery |
| <input type="checkbox"/> and Designing | <input type="checkbox"/> Tea Room and |
| <input type="checkbox"/> Home Dressmaking | <input type="checkbox"/> Cafeteria Management |
| <input type="checkbox"/> Advanced Dressmaking | <input type="checkbox"/> Catering |

Name _____ Age _____

Address _____

City _____ State _____


Present Position _____

If you reside in Canada, send this coupon to the International Correspondence Schools Canadian, Limited, Montreal, Canada.

Kits for Making Gifts

(Continued from page 11)

- 5S. Coast Guard patrol boat of new 165-ft. class, 20% in. hull..... 4.95*
- 6S. Brig *Malek Adhel*, 1/4-in. scale, 20-in. hull, 33 in. over all, frame-and-plank construction.. 9.75†
- 8S. Fishing Schooner *Bluenose*, 17 1/2-in. hull, 22 in. over all..... 4.95†
- 9S. Whaleboat, 14 in. long; partly shaped hull and raw materials for making all equipment..... 2.75†
- 10S. Confederate raider *Alabama*; steam sloop, bark rigged; 3/32-in. scale; 21 1/2-in. hull, 28 in. over all 8.20*



Kit U—"Hispaniola" of "Treasure Island"

MODEL-OF-THE-MONTH KITS

- M. Aircraft carrier *Saratoga*, 18-in. 1.00
- N. Four U.S. destroyers, each 8 1/4-in.75
- R. U. S. cruiser *Tuscaloosa*, 11 1/4-in. 1.00
- U. *Hispaniola*, the ship in "Treasure Island," 7-in..... .50
- Z. H.M.S. *Bounty*, 11 1/2-in..... 1.50
- 2M. Ocean freighter, 14-in..... 1.50
- 3M. Yacht *Nourmahal*, 8 1/4-in..... 1.00
- 4M. Oil tanker, 14-in..... 1.50
- 5M. Liner *President Lincoln*, 14 1/4-in. 1.50


SIMPLIFIED SHIP MODEL KITS

- F. Liner S.S. *Manhattan*, 12-in..... 1.00
- H. Cruiser U.S.S. *Indianapolis*, 12-in. 1.50
- J. Clipper ship *Sea Witch*, 13-in... 1.50

MODEL RAILWAY KITS

- 1L. Model locomotive, Hudson type HO gauge. Kit contains all the necessary sheet brass, brass tubes, rods, wire, springs, fiber, screws, boiler head, ladder strip, six driving wheels, and ten pairs of wheels. Locomotive and tender are 14 in. long 9.95*

(Continued on page 19)



Raw materials for a brig are in Kit 6S

Says Everybody is Hypnotized

If there is any lack whatever in your life—if you suffer from poverty, fear, doubt, disappointment, disease, discord, inferiority complex, or failure—if your life is not a continuous record of abounding health, success, wealth and happiness—very likely it is because you're hypnotized! Such is the astounding declaration of Edwin J. Dingle, well-known explorer and geographer. He tells of a strange method of mind and body control that leads to immense powers never before experienced. He found the method in mysterious Tibet, often called the Land of Miracles.



He maintains that all of us are giants in strength, ability, and mind-power, capable of prolonging youth, defying sickness, developing great talents, and achieving dazzling success. From childhood, however, we are hypnotized, our powers put to sleep, by suggestions of associates, by what we read, and by various other experiences. To realize their really marvelous powers, men and women must escape from this hypnotism. The method found by Mr. Dingle in Tibet is said to be remarkably instrumental in freeing people of such hypnotizing ideas. Send today for the free 8,000 word treatise revealing the startling results of this strange system, by which men in the Far East can do things never equaled in the Western world. No obligation. Simply send your name and address.

The Institute of Mentalphysics, Dept. 465
213 So. Hobart Blvd., Los Angeles, Calif.

JOBS EVERYWHERE FOR THOSE TRAINED IN MERCHANDISING

● Retail stores in every neighborhood, town, city, provide 5 1/2 million jobs to qualified people. FREE BOOK tells how to prepare at home—in spare time—for pleasant \$25 to \$40 weekly merchandising jobs. Special training for those wishing to advance to buyer, manager—operate own business. Covers "Selling Up Customer," "Closing the Sale," "Buying for Resale," 42 other subjects. Simply ask for "Modern Merchandising Book." It is FREE. No obligation. Write NOW. American School, Dept. WC4, Drexel at 53rd, Chicago.

Learn to MOUNT BIRDS Tan SKINS, Make Up FURS

Be a Taxidermist. We teach you at Home. Mount Birds, Animals, Pets, common specimens. Save your hunting trophies! decorate home and den. Make money! KROME LEATHER, tan and make up furs for sparetime profit. FREE BOOK 48 pages—tells all about it. Hunters, get this wonderful book. Its how free! Send postal card today—The Minitel State your AGE. H. W. School of Taxidermy, Dept. C339, Omaha, Nebr.

PATENTS—TRADEMARKS

All inventions submitted held confidential and given personal attention by members of the firm. Form, "Evidence of Conception" and instructions, "How to Establish Your Rights"—FREE!

LANCASTER, ALLWINE & ROMMEL
PATENT LAW OFFICES
412 Bowen Building Washington, D. C.

DECORATIVE METAL WORK

A brand new manual for the amateur. Tells in easy to understand language how to make useful metal articles in your home workshop. You'll be surprised how easy and interesting metal work really is. Fully illustrated with diagrams and step-by-step instructions. Sturdy cloth binding, 253 pages. Send only \$2.00 and your copy will be sent postpaid. Popular Science Monthly—Dept. 88, 353-4th Ave., New York, N. Y.



START \$1260 to \$2100 Year

Get ready immediately. Over 44,000 appointments last Gov't year. Common education usually sufficient. Mail Coupon today sure. / Address _____

FRANKLIN INSTITUTE

Dept. T258, Rochester, N. Y.

Sirs: Rush to me without charge.

(1) 32 page book with list of many U. S. Government Big Pay Jobs.

(2) Tell me how to qualify for one of these jobs.

Name _____

Address _____

Kits for Making Gifts

(Continued from page 18)

- 2L. Supplementary power unit for the locomotive 1L. Consists of specially built electric motor (8-v.) and worm and gear..... 4.50
- 3L. Track kit. Contains running rail, third rail, cardboard ties, spikes, etc. for making 25 ft. of HO track..... 4.00*
- 4L. Deluxe track kit. Same as 3L. except that kit contains third-rail chairs, which eliminate much of the soldering..... 6.95*

MISCELLANEOUS

- No. 4. Solid mahogany book trough 22 1/2 in. long, 9 1/2 in. wide, and 2 1/4 in. high over all. Ready to assemble, with finishes..... 5.30*



Kit L—Farragut's flagship "Hartford"

- No. 5. Solid rock maple hanging wall rack with one drawer, 19 1/2 in. wide, 33 1/2 in. high. Ready to assemble and stain included..... 5.75*
- No. 7. Whittling kit with two shaped blocks for making sea captain 5 1/2 in. high..... 1.50
- No. 8. Whittling kit for six different Scotties. Each is 2 by 2 1/4 in., sawed to shape..... 1.00
- No. 10. Copycraft whittling kit for making one of several Hobo Hank novelties. Includes master model 5 1/2 in. high..... 1.50

Note: If you live west of the Mississippi River or in Canada, add 50 cents to all prices marked with an asterisk (*) and 25 cents to all prices marked with a dagger (†).

Popular Science Monthly, Dept. 38A
353 Fourth Avenue, New York, N. Y.

Please send me C. O. D. Kit

I will pay the postman the price shown above plus a few cents postage in full payment. (Canadian orders cannot be sent C. O. D.)

Name.....

Address.....

City..... State.....

(Print name very clearly)
If you prefer to send your remittance with this order you save the C.O.D. charge. Remit by money order check or registered mail. This offer is made only in the United States and Canada. Also see note above.

OWN A ROYAL



Believes Royal helped him get ahead
"The day I got my Royal I started typing my reports. Soon I had a larger territory. Now I have 5 men under me."

PORTABLE ON



Glad they picked a Royal
"All of us use our Royal Portable—Junior for his homework. I to work out assignments for a correspondence course I'm taking."

YOUR OWN TERMS



Idea typed on Royal bring raise
"Ideas count where I work. Since I got my Royal Portable, I've typed mine out. Already I've had one raise."

Only a Few Cents a Day

FREE HOME TRIAL

FOR EVERY MEMBER OF THE FAMILY!


A Royal Portable will help you write faster, think faster. A practical, modern necessity—it's an opportunity for a better brighter future! A chance to do more, be more!

Without risking a penny prove—right in your own home—that a Royal will help you—whatever your business or profession—help you to set down your ideas and reports legibly, impressively, too, that it will help the children with their homework...help every member of your family with their writing!

READ WHAT ROYAL

GIVES YOU! Standard, full-sized keyboard.

Easy, effortless action, Touch Control, Finger Comfort Keys, Genuine Dust Protection, Automatic Paper Lock, Touch-set Tabulator and many other office typewriter features. Tested, proved, guaranteed!



SEE how a Royal will do! Then own it on your own terms—cash or only a few cents a day! Mail coupon today for full details of Royal's offer—prices, terms, Free Home Trial—everything. No obligation.

FREE!

Royal's Instant Typing Chart, shows you how to type RIGHT. INCLUDED with every Royal Portable at no extra cost—a handsome, all-weather Carrying Case.

ROYAL TYPEWRITER COMPANY, Inc.,
Dept. B-33, 2 Park Ave., New York, N. Y.

Tell me how I can own—for only a few cents a day—a latest model Royal Portable—with FREE HOME TRIAL.
(DO YOU OWN A TYPEWRITER NOW? Then make it help pay! Write Make and Serial No. on coupon margin for full trade-in value.)

Name..... Street.....

City..... State.....

8 mm and 16 mm Films

Mickey Mouse Donald Duck
Oswald Rabbit

Numerous comedies, Westerns—and novelties—over 500 subjects to choose from—Catalogue free. Dept. M, Hollywood Film Enterprises Inc., 6060 Sunset Blvd., Hollywood, California.

DO YOU LIKE RADIO & TELEVISION

If you want to know employment opportunities and requirements in radio and related industries, get National's book of facts. Send for YOUR FREE COPY TODAY
Dept. PER-2 4200 S. Figueroa

NATIONAL
SCHOOLS
Los Angeles

HOW to Protect and capitalize on your INVENTION

Get these FREE BOOKS of "IDEA" Opportunities

Is your idea patentable? Has it commercial possibilities? Those are the things you want to know—and interesting information on these questions can be found in our books "How We Protect You" and "Suggestions on How to Commercialize Your Invention". We will send you these absolutely FREE—along with our Certificate of Invention form, if you mail the coupon below NOW!

Our Experience Guides You
You can feel perfectly sure in dealing with this reputable firm. C. A. Snow & Co. has been securing patents of every description for 63 years. Save time and expense now by getting advice based on our long patent experience.

C.A. SNOW & CO.
Registered Patent Attorneys Since 1875

DEPT. 288, SNOW BUILDING, WASHINGTON, D. C.

Gentlemen: Please send me absolutely free, and without obligation on my part, your original document, "Certificate of Invention," together with your two guides for inventors, "How We Protect You" and "Suggestions on How to Commercialize Your Invention."

Name.....

Street and No.....

City or Town..... State.....



I can train you for
DRAFTING
right in your home
by my practical method

Engineer Dobe can prepare you just as he has trained thousands of successful students, aged 16 to 18 to past 50. His practical "Work-Job" method requires no previous experience. High school education not needed. He offers you a real opportunity to get a complete training in drafting right in your home in a surprisingly few months. Engineer Dobe teaches his students until thoroughly trained and until holding a good paying job. Drafting offers big opportunities in many fields. Mail the coupon today for FREE illustrated book "Successful Draftsmanship" and full details of Engineer Dobe's remarkable offer that includes all necessary tools and equipment. Send coupon TODAY!

Complete
Outfit
Furnished

Send for FREE BOOK

ENGINEER DOBE
Div. C-330
Libertyville, Ill.

Send me your free book "Successful Draftsmanship." Please explain how you assist your graduates to good positions as draftsmen.

Name.....

Address.....

Town.....


State..... Age.....



WINGS OF THE FLEET

Here are nine of Uncle Sam's naval scout-bombing planes in an unusual and difficult formation. Operating from an aircraft carrier, planes of this type could locate a hostile armada far at sea and strike it a swift, paralyzing blow

NEW OIL SOURCES FORECAST BY World's Deepest Well



Improved drilling methods made possible this 15,004-foot well, the deepest hole man has ever made in the crust of the earth

PLUMBING the earth's crust to a depth of nearly three miles—15,004 feet, to be exact—the deepest of all man-made holes has just been drilled near Wasco, Calif.

Downward it leads, through regions never before explored by geologists, through sands laid down by prehistoric oceans, twice as far toward the center of the earth as man has ever penetrated in the lowest levels of the world's mines. At its bottom, bearing witness to its approach to some fiery, subterranean inferno, it reaches the ovenlike temperature of 270 degrees. Solely as an ob-

servation post for learning the secrets of the earth's interior, the shaft would fire the imagination of any scientist.

What most interests the petroleum engineers who bored this extraordinary hole, however, is their success in using it to tap the deepest-lying oil ever brought to the surface of the earth. Enough "black gold" to fill a dozen tank cars daily now flows from its mouth—marking a triumph for oil-seeking methods that were unknown


in the industry only a few years ago.

"KCL A-2," as the Continental Oil Company designates its record-breaking well, began as a wildcat or exploratory shaft—driven as much for the purpose of exploring the subterranean formations as in the hope of finding oil. When it finally passed the 15,000-foot goal of the drillers, not a drop of oil had been encountered! Once, that would have been the end of it; all the cost and labor would have been in vain, as far as striking oil was concerned.


But the men who drilled the "KCL A-2" had an ultra-modern aid at their

By JOHN E. LODGE

Echoes from Far Under the Ground Map Subterranean Formations



In an apparatus called a geosonograph, vibrations produced by an explosion and reflected by underground formations are picked up by buried detectors, like the one at the right, and used to chart possible oil pools



steel punctured the well casing and ripped through the surrounding sand. As if released from a bullet-riddled tank, oil gushed through the holes and up the pipe, vindicating the "sixth sense" of the electric probe.

The new oil detector does for vertical oil hunting what other scientific divining rods have already done for mapping the horizontal boundaries of an oil field. And the instruments used for picking out the surface sites of oil wells, in their turn, have come in for recent refinements.

Until now, for example, a widely used system of mapping oil-bearing formations beneath the earth has consisted of exploding buried charges of dynamite, and using seismographs to record the artificial-earthquake waves reflected from the depths (P.S.M., Mar. '37, p. 40). For the seismographs, a new scientific prospector, called a "geosonograph," substitutes highly sensitive electrical detectors, of a crystal type originally developed for locating enemy submarines in wartime. Earth tremors picked up by these detectors, which are buried in the ground, are successively converted into electrical waves, flickering light, and permanent records on motion-picture sound film. An analyzer employing an electric eye then interprets the complex patterns of the film records, yielding data from which a draftsman can plot the course of subterranean layers of rock and sand with as much assurance as if they were actually exposed to view. Thus complete charts are obtained of oil fields like the one in which the "KCL A-2" well is situated, before any well-drilling begins. According to the inventor of the geosonograph, it extends the range of present prospecting instruments to reveal faults, fissures, and other formations far beyond the depth of present wells.

Deeper and deeper shafts for oil, however, heighten the problem of getting it to the surface. For a while, nature may take care of the matter by providing pockets of natural gas under sufficient pressure to force the oil up through the thousands of feet of pipe. But as oil is constantly withdrawn, the gas pressure drops, and wells have had to be abandoned with millions of barrels of oil still in the ground.

To prevent this, experts have recently perfected a process of "pressure maintenance" described not long ago by E. O. Bennett, chief engineer of the company that drilled the "KCL A-2," before a meet-

disposal, a strange device nicknamed the "electric probe." Into the well, they lowered a bullet-shaped electrode, attached to a huge reel of wire. By gauging the amount of current that flowed between this electrode and a second one, buried in the ground at the surface, the proximity of oil at any particular level could be detected. Telltale indications were obtained when 13,100 feet of cable had been paid out, although samples of sand brought up from this level during the drilling of the well had not exhibited the slightest oily color, odor, or taste. Apparently the well had just missed an oil pool, blocked off from it by a formation impervious to oil.

At this point, another of the latest scientific aids to oil men, the "underground machine gun," was called into play. Down the well on the end of a cable went a torpedo-shaped cylinder of steel, studded with recessed knobs along its outer shell. Each knob formed the barrel of a pistol. As the device reached the 13,100-foot level, a thousand feet below the former world's deepest "producer," an operator at the surface closed an electric switch. Slugs of solid



Oil from the ocean floor. This well, located in the Gulf of Mexico, was drilled from a sunken barge. Subterranean explosions punctured oil-bearing sands to start the flow


ing held by the American Petroleum Institute. The idea is an outgrowth of the scheme of reviving oil wells that have ceased to flow by "repressuring"—that is, by pumping air or gas back into the underground formation to restore the pressure. In the newer "pressure maintenance" plan, however, oil wells are never allowed to reach a point where repressuring is required. The stimulating injections proceed simultaneously with the piping off of the oil.

Through an ingeniously designed set of separators, a modern pressure-maintenance system draws off the natural gas that comes to the surface with the oil. The vapor is treated for the recovery of gasoline and other by-products. Then powerful compressors pump the remaining "dry gas" back into the ground—either through a separate pipe in the same well, or through an "input well" reserved for the purpose—to aid in raising more oil and more gasoline-bearing gas. The final result, when all the oil and liquid by-products have been recovered from the underground pool, is a vast subterranean reservoir of natural gas which may then be profitably

tapped and used for fuel. Nearly half again as much oil may be recovered from a typical field where this method of conservation is practiced, it is claimed.

For deep wells, the "pressure-maintenance" system has another advantage. Brought from levels where terrific heat and pressure conflict to form strange borderland compounds, midway between liquids and gas, oil may change from one form to another on its way to the surface. Oil lines may even be clogged with solid paraffin as the rising oil expands and cools under reduced pressure. The new system provides a delicate means of pressure control that obviates these difficulties.

In applying the pressure-maintenance plan, engineers have succeeded in returning through a single



How natural gas is separated from oil and then pumped back into the ground. This maintains the pressure that is necessary for maximum production and prevents shifting of formations

well, daily, as much as 15,000,000 cubic feet of gas, or twice enough to fill the largest airship ever built. They have pumped gas into the ground at pressures up to a recent maximum of 4,600 pounds to the square inch, a pressure that not even the most heavily armored diving suit could withstand. Thus the strength of man-made machinery has been pitted against the titanic forces of the depths of the earth—and has won. The new achievement removes the last obstacle to reaching vast stores of liquid gold at record depths, miles beneath the ground we walk on.


Look backward less than a quarter of a century, and you will realize what an advance has been made when it is even mechanically possible to bore a hole nearly three miles deep. In 1915, drillers at Charleston, S. C., sank a well to what was then a world-record depth—2,000 feet. In 1926, a well at Brea, Calif., reached 8,000 feet. A race for the 10,000-foot level was won in 1931 by a well near Seaciff, Calif.

Now engineers began to speculate, for the first time, as to the possibility of reaching 15,000 feet. They got out their pencils and found that enough sections of pipe to reach this level, screwed end to end to twist the drill, would weigh 200 tons. Could a derrick be designed that would shoulder the staggering load—and then lower into the well an even heavier length of alloy-steel casing? Could engines be built that would handle such dead weights, and still turn a drill miles away with velvety smoothness and delicate control? Insurmountable as the difficulties seemed at the time, forward-looking experts conceded that some day it might be done. Today the 15,004-foot "KCL A-2" is the realization of their dream, and the likely forerunner of still deeper shafts to come.




FINDING THE OIL LEVEL. When the electric probe has shown the level in a well at which oil is present, the exploding perforator seen at right is lowered to that point. It shoots bullets from the cartridges shown, tearing paths for oil

"Machine Gun" Fires Bullets To Start Oil



Big Business



In their office, boys of this Junior Achievement "company" are discussing production methods best suited to a project. Later, in the shop at right, they apply their plans, making articles

**HOW YOUNGSTERS ORGANIZE AND
RUN CRAFTWORK COMPANIES THAT
TEACH BUSINESS METHODS AND
PAY STOCKHOLDERS DIVIDENDS**

By
Kenneth M. Swezey

WORKING in cellars and neighborhood clubs, in attics, barns, churches, and spare rooms of private homes, more than 20,000 American boys and girls between the ages of sixteen and twenty-one are conducting an amazing big-business venture in miniature. As members of the Junior Achievement movement, with fifty units or "companies" in New York City alone, and 1,000 more scattered through cities along the Atlantic Coast and as far west as Denver, Colo., these young craftsmen are not only creating things of usefulness and beauty, but, in conducting their business, are also thoroughly grounding themselves in modern merchandising and business administration.

During the present year, these companies will probably gross nearly a third of a million dollars, derived entirely from articles they have made and sold. In times when many established adult business houses may falter and fail, all these junior companies expect to meet their expenses, including rents and wages, and wind up with enough profit to buy additional equipment. And a good many of them will declare a ten-percent dividend to stockholders!

But, immediate cash returns are only an incidental phase in the work of these ambitious organizations. Training for life and work, through practical experience, comes first. Horace A. Moses, head of a large paper company, and the late Theodore N. Vail, telephone magnate, had enough faith in the idea to contribute \$250,000 each to help found the organization. Now, several large industrial and business concerns have standing regulations that all new young employees be recruited from Junior Achievement companies. Other con-

cerns are sponsoring units among their own employees.

How does it work? Just like any regular manufacturing corporation, except in scale. A group of older boys, girls, or both, decide they would like to start a company for making furniture, say, or fine leather work, or hammered pewter. Four adults agree to cooperate with them: a business man, a crafts leader (often an experienced home-workshop hobbyist or a manual-training teacher in a local school), a sales counsel, and a chairman. These four make up the advisory committee. President, treasurer, production manager, sales manager, advertising man, and secretary are chosen from the company membership, while all members are directors. For the sake of close cooperation, companies generally have but fifteen members.

After a name and trade mark have been chosen, and the company has been

Although he punches leather in the shop, this young worker, like all of his associates, is a company official



incorporated, tools must be bought and the rent paid for a meeting place. A cash surplus must remain for materials and emergency expenses. Different crafts require different capitalization. Metal working, woodworking, and leathercraft, require fifty dollars each; paper working and needleworking about

in Miniature

twenty-five dollars; while a company for working in wrought iron may need seventy-five dollars. This capital, just as in big business, is raised by selling stock to members of the company and their friends. Twenty-five or fifty cents may buy a share, and, so that no one person will have a controlling interest, no one may buy more than five or ten shares.

Then the company starts operation. The boy and girl members run it with only as much guidance and advice as they may desire from their adult partners. Junior Achievement headquarters, in Springfield, Mass., New York City, Philadelphia, and other cities, suggest programs, act as clearing houses for projects and designs, and maintain completely equipped schools for training both craft and business workers.


A company may tackle any craft. "The Anvil," a company in Jamaica, N. Y., is doing a rushing business in sterling-silver jewelry and other small-article metal work. "The Printcrafters," in a neighboring place, handle a nice bit of the card, letterhead, handbill, and similar small presswork of the community. "The Knick-Knacks," a unit of girls, all employed by a large insurance company in New York City, turn out hosts of pins, brooches, candlesticks, napkin rings, and the like from plastic material, besides handling a line of needlework.

Projects are as varied as the groups, and may range from a simple key ring or bookmark, to a fine leather desk set for an exclusive club, or built-in bookcases for an entire room. One large project was an elaborate doll house, four feet high, and furnished to the last minute bit of upholstery and to its tiny brass candlesticks. Completed, it weighed more than a ton.

Work must be sold in competition with regular commercial products on a quality basis, so there can be nothing



Customers may view the work produced by this company in its well-designed display shop. Here a prospective buyer examines a composition plaque, priced to bring a fair profit



Trade marks such as these identify each of the self-supporting midget businesses

amateurish or cheap about it. The members design their articles carefully to meet modern trends. When a design is approved by all of the

members, a sample is made, and its cost is carefully checked. Time, material, overhead, depreciation of tools, and profit, are all considered in the calculation. If the estimated price of an article seems reasonable, regular production may begin. Well-known industrial designers, architects, and artists often judge the merits of a striking design or of a project that might be distributed to groups throughout the entire organization.

There are no labor disputes in these junior companies, because every worker soon learns the financial problems of his own concern, and can himself compute to the penny what his work is worth. Depending upon workers' ability and the cost of the materials of the product being made, wages may run from five to thirty cents an hour. In some companies the workers are so proud of their growing achievements that they voluntarily turn back their wages to help buy new equipment.

Selling generally is done direct to the customers, and unusual articles are often made to customers' specifications. Each member of the firm must take his turn with the sales kit, and bring in his share of new business. In this way, patronage is gradually built up.

After several years of operation, most companies become so successful that the members try to buy in all the outstanding stock, so that they themselves may reap the dividends. The stock of one company, that sold for fifty cents a share seven years ago, is now quoted proudly at a dollar fifteen. In a number of companies business has become so pressing that the members have given up their regular occupations and have established full-time, going concerns.



Girls alone conduct the shop at left, using modern business methods and turning out a line of highly saleable plastic novelties

Plane Takes Off and Lands on Speeding Auto

TAKING OFF from the top of a speeding automobile and alighting again upon it, a dare-devil stunt pilot recently thrilled spectators at the Oakland Airport in California. A wooden platform mounted on top of the car offered barely enough room for the plane at rest, requiring the most skillful piloting and teamwork with the driver of the car for the hair-raising feat of a landing. In the picture at the right, the plane can be seen settling onto its tiny "landing field."



It took skillful handling to bring this plane down on the narrow platform built over the car top



Spring Heels for Shoes

A SPRINGY step is assured the wearers of sports shoes created by a Los Angeles, Calif., designer. Instead of conventional heels, the novel footwear employs resilient coil springs, which are said to absorb shocks and prevent fatigue.



Cigarette Match Holder

MATCHES are always handy when they are attached to a cigarette package with the new holder illustrated. With the transparent wrapper removed from the package, the aluminum holder for match books slips into place as shown.


Dwarf Flowers Grow in Table-Top Garden

ANY child can plant a table-top flower garden that really grows, with an outfit just placed on the market. Ornamented

in the style of the popular movie, "Snow White and the Seven Dwarfs," the miniature set provides a metal box with specially treated soil, white gravel for making a path, and the seeds of four dwarf varieties of flowering plants, together with complete instructions for planting and care. When in bloom, the miniature garden is a beautiful decoration for a room.



Miniature garden in bloom and, right, the set as purchased with specially treated soil and dwarf flower seeds



New ultra-violet lamp in use for treating the skin of the hand

Ultra-Violet Lamp Has Glass "Window"

ULTRA-VIOLET rays stream from a bulb of common glass, in a lamp developed by Westinghouse engineers for treating skin disorders. Special materials like quartz have previously been employed, because glass is ordinarily opaque to the rays, but an extra-thin "window" blown into the new bulb transmits them effectively.

Odd Blimps Hold Net To Snare Bombers

RESEMBLING a herd of flying elephants, grotesque captive balloons are being tested in England as a means of combating possible air raids on London. The weird balloons, anchored to special trucks by steel cables and drifting upward as high as 25,000 feet, support a great steel net. Raiding planes, it is believed, will strike and become entangled in the net before they can release bombs on vital municipal areas.

"Lost-Chord" Fiddle Plays 300-Tone Scale

A NOVEL musical instrument invented by Paul W. Thomas of Oklahoma City, Okla., is said to produce at least 300 tones within the range of the thirteen-note piano octave. Strung across a metal frame, seven steel strings are either plucked, struck with a hammer, or bowed. Magnetic pick-ups reproduce the sound in a loudspeaker. Overtones, which on other instruments blend together, can be separated and sounded individually, it is claimed.



Four of the "flying elephants" that will spread a net of steel in the sky around London, England




Paul W. Thomas playing the novel instrument on which separate overtones are sounded



Headlight Tilts on Hills

SWINGING inside the lamp housing, a reflector unit for automobile headlights automatically throws the light rays down onto the road as the car climbs a hill. The reflector is hung on a pivot so that gravity keeps it vertical, reducing the danger of blinding the drivers of other cars.



Pivoted at the top, the reflector remains vertical as the car climbs a steep hill

Bait Seller Supplies Movie Insect Plague

SELLING grasshoppers for anglers to use as bait is the odd business of Cliff Jones, of Hollywood, Calif. Recently, when a movie director needed 7,000,000 live 'hoppers for an insect-plague scene, Jones made a quick trip to Utah and came back with thirty-five barrels of the insects within the two weeks' time specified by the odd order. After their film debut, the grasshoppers were killed.



Cliff Jones with 'hoppers boxed for bait

Camera on Police Gun "Shoots" Criminals in Action



Test of revolver camera, and three "shots" made by it

FASTENED below the barrel of a revolver, a tiny gun camera devised by Abraham Kurnick of New York City is less than two inches long and weighs only six ounces, including its special lens. Both shutter action and the turning of the film are automatically controlled by the gun trigger. Designed for police use, the camera enables an officer to photograph a criminal in case a shot misses.




Pulling the trigger of the gun opens the camera shutter and also turns the film. Upper picture shows the six-sided spool on which the half dozen exposures are made


Electric Ear Tests Musical Instruments



Measuring pitch of a clarinet. At right, one of the twelve stroboscope disks used



MUSICAL pitch is accurately measured with the eye in a new electrical machine that operates on the principle of the stroboscope, or stop-motion device. When a given note is sounded into a microphone, a whirling disk appears to stand still if the pitch is exactly correct. If the note is sharp, the disk appears to rotate to the right and, if flat, to the left. The amount of sharpness or flatness is determined by turning a knob until the disk appears stationary, and reading a dial.



When a patient dials, the indicator tells the nurse what service is required


Patient Dials Needs

SYMBOLS on the bedside dials of a new hospital signaling system represent the ten most frequent needs of patients. By selecting a symbol and flipping the dial, the patient makes any desire known.

Dust-Bowl Plow Digs Dikes To Hold Rainfall

COMBINING the work of a shovel and a plow, a new cultivating machine invented by C. T. Peacock, Arriba, Colo., farmer, digs a checkerboard pattern of dikes in a field to hold rain water and check erosion. Specially designed for "dust-bowl" areas where rainfall is scanty, the system prevents surface water from running off the soil and collecting in low spots by holding it in miniature dams so that it will soak into the ground at all points. The treatment is also said to check wind erosion.

Below, rain water caught and held in shallow ditches



Plow "chiseling" dikes in a field to stop erosion



Sword Swallower X-RAYED

SCIENCE ALSO GIVES INSIDE DOPE
ON GLASS-AND-TACKS EATERS AND
OTHER CIRCUS FREAKS

Sebastian Montenero, below, thrives on a diet of tacks, razor blades, and glass. At the left, the X-ray camera discloses a "hair ball," or mass of tacks actually at rest in the performer's stomach



Here's your chance to "see through" a performance that astonishes thousands every year. At the left, above, a famous sword swallower is doing his stuff. The X-ray shot alongside is scientific proof that the long blade actually extends down the esophagus into the abdomen



DO SIDE-SHOW sword swallows really gulp down their long steel blades?


Do tack eaters actually swallow their metal meals? Can any man, even a circus freak, twist his head so that he faces directly backwards? Or are these performances merely secret tricks of the circus trade, done with folding swords and other devices?

The answer to these questions is revealed by the pictures on this page showing X-ray photographs made by scientists and proving that the men pictured actually perform the amazing feats claimed for them by circus barkers.

At the top of the page a famous sword swallower is seen with the blade jammed down his throat to the hilt. That this is no illusion is revealed by the adjacent X-ray photograph, which shows the sword blade extending down his esophagus.



Sebastian Montenero, the tack eater pictured at the upper right, has swallowed thousands of carpet tacks, razor blades, glass, and metal objects with no ill effects. That the tacks seen in his mouth, which he later swallowed, were really metal and not some fake soluble material is proved by the adjoining X-ray shot.

The photographs at the right show "inside" and outside views of the amazing stunt performed by the man with the turntable neck.



There is nothing abnormal in the appearance of the man in the photograph at the far left, but the X-ray picture reveals an unusually long, flexible neck...

... which probably explains how he is able to turn his head 180 degrees on his shoulders as seen in the views below. Unable to breathe in this position, he can hold it half a minute



PLANE FLIES 63,875 MILES IN A SHED

**Indoor Test of Mammoth Skyliner
Equals Three Trips Around World**

WITHOUT leaving its hangar, a new 65,000-pound transcontinental airliner, designed to carry twice as many passengers as present-day transport planes, was subjected recently to all the strains of taking off, zooming, diving, landing, and flying nearly three times around the world. Engineers at the Douglas plant, Santa Monica, Calif., inaugurated the new method of putting costly planes through grueling tests without running the risk of trials in the air. Such "standstill flights" promise to become standard practice in the future.


One million pounds of lead, giant hydraulic jacks, block-and-tackle chains, and steel frameworks that looked like parts of a skyscraper skeleton were employed in the tests. As many as 200 sensitive instruments had to be checked and their readings recorded as each successive strain was applied. To be sure that every man was letter-perfect in his share of the work, elaborate rehearsals were held before each part of the tests began. All told, more than 100,000 hours of shop and engineering labor were expended in making the flightless trials.

In one of the tests, cables hooked to the leading edges and top surfaces of the wings pulled upward to duplicate the "suction" lift of flight. In another, huge hydraulic pistons drove downward on the engine mountings with a force equal to 180,000 pounds, straining the 139-foot metal wings to reveal their strength. The combined force of pistons and lead-bar weights, in some instances, equaled three and a half times the entire weight of the plane.

The new-type, three-wheel landing gear employed on the big ship received special attention. More than fifty times, the wheels, tires, and struts were




The Douglas DC-4, largest overland transport plane in America, undergoing load tests that duplicated all the stresses met in normal flight



Workers operating the pulleys that applied loads of 180,000 pounds to the wings. Right, twenty tons of pig lead, in fifty-five-pound bars, to be piled inside the fuselage






Details of the elaborate set-up for the tests, in which all load conditions to be encountered by the plane in the air were accurately reproduced in the shed

smashed down with impacts up to 120,000 pounds. Each time they struck, the deflection of tires and struts was filmed by automatic, high-speed motion picture cameras. Miniature seismographs also recorded on revolving drums the force and character of the vibrations set up by the impact.

A test that took days to complete reproduced all the strains the plane would undergo if it were pulled up into a 2,000-feet-a-minute zoom while traveling 240 miles an hour. This is the top speed of the forty-two-passenger plane, which was designed at the order of five major air lines. According to the calculations of the engineers, the load-applications and vibration tests piled up a strain equal to that encountered by a plane flying 63,875 miles.

The gigantic size of the new plane is indicated by the fact that when mechanics tackled the job of adjusting the controls, a portable telephone system had to be used for communication between a worker in the cockpit and another at the tail of the ship.



A mechanic in the cockpit of the plane communicating with another worker in the tail, at left, by portable telephone while adjusting the controls



This bow doesn't bend, but strong rubber bands give it power to shoot regulation arrows

Aluminum Bow Uses Rubber Bands

STRONG rubber bands supply the "spring" for a rigid aluminum bow introduced for archery fans. Weighing less than twelve ounces, the new bow is only about half the size of the ordinary wooden type, but is strong enough to shoot regulation arrows. The bow's pulling power is adjustable.

Egg Candler Spots Embryo Chicks



Ordinary egg candler being equipped with colored-glass slides. Right, eggs are viewed through blue glasses



AS AN aid to poultry raisers, Dr. C. W. Knox, of the U. S. Department of Agriculture, has devised a method for distinguishing between fertile and sterile eggs when they have been incubated only from thirteen to twenty hours, making it easy for poultrymen to eliminate eggs that would never hatch. Glass slides, one yellow and one green, are placed before the light of a conventional electric egg candler and the eggs are observed through blue spectacles. Embryos appear as dime-size spots.

Wind-Tunnel Projector Helps Train Pilots



Smoke flowing over a model plane wing is pictured on the screen

AVIATION students in a California school study the action of air on the wing of a plane by means of the laboratory projector pictured at the left. As smoke blows across the surface of a wing model in a miniature wind tunnel, a sectional view is projected by a system of lights and lenses onto a screen where the streams and eddies of air may be easily observed for instruction in airplane design and operation.



With the leg unfolded from its barrel, pencil is a compass

Folding Leg Makes Pencil into Compass

DRAWING compass and mechanical pencil are combined in one unit just placed on the market especially for engineers, draftsmen, and students. The compass leg folds like a jackknife into the barrel of the unit, while the lower end houses the pencil mechanism and the upper end has a durable eraser.

Moving Bonfire Destroys Weeds


TO REMOVE field weeds and trash before summer plowing, Elmo Irwin, Ritzville, Wash., farmer adopted the novel method pictured at the right. Drawn by a tractor, four harrows spanning eighty-five feet collected the trash in their steel teeth. This was then ignited, and additional weeds, gathered as the harrows moved along, caught fire and were destroyed.



Pulled by a tractor, an eighty-five-foot span of harrows drags burning weeds and trash across the field


Horse and Car Compete in Hurdle Race

HORSE and automobile were matched recently in a spectacular hurdle race in New Orleans, La. Jimmie Lynch, nationally known stunt driver, piloted a stock-model car down a straight runway and onto a ramp at a mile-a-minute pace. The horse came to the barrier at the same instant, and horse and car soared over together to land on the turf beyond. The photograph reproduced at the right shows the car and the horse side by side in mid-air as they passed over the hedge-topped hurdle.



Talk about mechanized cavalry—here's a stock-model car taking a steeplechase jump with the help of a ramp

Toy-Train Transformer Shows Model's Speed



A TRANSFORMER for toy trains that has just been placed on the market is equipped with a vernier control that permits minute changes in voltage and therefore in the speed of model trains. Compact in size, and fitted with an indicator dial calibrated in "miles an hour," the transformer allows changes in voltage as small as fifteen one-hundredths of a volt.



Novel Eraser Holder

ANCHORED to the side of a typewriter by a rubber suction cup, a novel eraser holder consists of a flexible chain attached to a spring-operated reel. The eraser is pulled out for use, and springs back when released.



Grooves in tops and bottoms of blocks interlock for stability

Kiddies' Blocks Are Skidproof

CHILDREN'S building blocks of a new type have grooved surfaces on the top and bottom to prevent them from toppling over when in use. Because the grooves on one block fit into those on another, pyramids and other block structures will not collapse easily. The blocks are painted attractively in bright colors with various animal figures and letters of the alphabet.

Detector Identifies Phone-Cable Wires

NICKNAMED a "bliffy sniffer," an exploring amplifier developed by telephone engineers unerringly "sniffs out" a desired line from the maze of wires in a telephone cable. A pencil-shaped instrument, wired to an amplifier and thence to headphones worn by a workman, is passed over the bundle of insulated wires in a cable. When the correct wire is touched, the unit picks up an identifying tone signal that is being sent on that wire from a central telephone office, and reproduces it in the workman's ear-phones.



When the desired wire is touched, an identifying signal is heard

Scientific Worm Farm Keeps Fishermen Supplied




Mr. and Mrs. Don Wyatt at work on their worm farm. Above, they are packing worms in tins. Right, selecting specimens from the novel harvest

WORM farming is the novel occupation of Mr. and Mrs. Don Wyatt, of Lynwood, Calif. Sold as bait for fishing, the worms are scientifically selected and bred, and raised on specially prepared soil that contains all the elements necessary for healthy growth. At "harvest" time, the worms are picked from the soil and packed in groups of fifty into tin containers. The photograph reproduced below shows the worm farmers at work on a bed of their fish-bait crop, and at the left they are seen packing the worms for shipment.



Audible Chart Teaches Music

LEARNING the sequence of notes in the musical scale is made easier by the unusual instrument pictured at the right. Musical metal bars tuned to the right tones are fastened over each note on an enlarged black scale against a white background. When a teacher indicates any note by touching it with a small hammer, the bar sounds the note itself, so that students learn by both seeing the scale and at the same time hearing the tones sounded.




Striking the "notes" on this scale sounds the actual tones

Handy Portable Drill Is Battery-Powered

DESIGNED for work in locations away from power lines, a new half-inch drill operates on either six or twelve-volt current supplied by one or two storage batteries. Unlike most drills, it has no gears, but employs a special motor that is said to produce a sufficient range of speeds for drilling wood or metal and, with a grinding wheel attached, for sharpening tools.



Using the battery-driven drill on a farm machine, far from a regular power source



As the bus enters the laundry, an electric eye starts the brushes

Unit Cleans Busses in 40 Seconds

FORTY seconds is all the time required to wash a bus in the novel automatic bus laundry pictured at the left. When the bus driver maneuvers into place and blinks his headlights, a photo-electric cell starts the electrical mechanism, water sprays over the bus, and whirling brushes wash away collected dirt and grime.

TEST-TUBE Forest Fires

SHOW NEW WAYS TO SAVE TIMBERLANDS

WHAT are the best methods of stemming forest fires that annually destroy \$50,000,000 worth of timberlands in the United States? To determine this, scientists of the U. S. Forest Service have been deliberately touching off roaring blazes in the heart of woodlands, making minute observations of the spread of the flames, and then extinguishing the fires with chemical solutions that are the result of intensive research in fire-fighting laboratories. Manned by experts, a special truck is driven to the scene of a test blaze, carrying portable and stationary pumps, cameras, chemical-spray units, shovels, axes, and even a complete set of weather-recording apparatus to permit an accurate estimate of the effects of temperature, humidity, and wind on the spread of a forest fire. When a space has been selected and every precaution taken to confine the area of the test fire, piles of branches, brush, and shrubbery of measured amount and known moisture content are ignited. The spread of the flames is then timed with a stop watch, and the efficiency and speed of extinguishing methods and chemical solutions are noted.



Rolling forest-fire laboratory with its crew. The truck carries the equipment and supplies required for the tests




Crew members noting weather conditions. Wind, moisture, and temperature are important factors in the behavior of forest fires



Experimenter manipulating the valves that control the flow of liquids being applied to a test fire




1 U. S. Forest Service workers igniting a pile of branches with a gas torch, to create a forest fire in miniature



2 Twenty seconds later, the pile is a flaming inferno, on which new fire-fighting methods can be given a real test



3 Extinguishers quickly smother the flames, while stop watches check their efficiency



By E. W.
MURTFELDT

Learn to Sail

ON YOUR DINING TABLE




LUFFING. When the model boat is pointed directly into the wind from the electric fan, the sails flutter aimlessly. In actual sailing, this maneuver is used in approaching a mooring, and in "coming about"

YOU may not know a mainsail from a jib or a centerboard from a halyard. You may never have been any closer to a sailboat than a picture in your Sunday paper. Yet with a tiny model boat that you can put together easily, and an electric fan to whip up a realistic breeze, you can master the fundamentals of sailing right on your dining-room table. With a little experimenting, you can learn the basic principles that apply equally to the humblest home-built dinghy and to the most elaborate sailing yacht.

All you need besides the fan and the table to sail on, is a bit of cloth, a few scraps of wood, a dozen or so straight pins, and some string. Following the design shown in the photograph on the next page, saw out the flat hull of the model from a piece of pine. Drill a hole for the dowel-rod mast, drive in bent pins for cleats and string guides, and

cut out the sails from an old handkerchief or shirt tail. After you have hoisted the sails on strings, tie the bottom of the larger sail (mainsail) to a boom which pivots on the lower end of the mast. Finally, attach your sheets or sail-control lines, two for the small front sail called the jib and another for the mainsail. When this is done, you are ready to cast off and head out into the electric-fan wind.



PICKING UP A MOORING. The job of "parking" a sailboat puzzles landmen. The diagram at left shows how the craft is maneuvered into the wind to slow it down so the buoy can be reached with a boat hook




To produce a breeze more nearly like that encountered on the open water, tie or tape a cardboard separator, of the kind used in packing eggs, to the wire guard in front of the fan. This will break up the eddies and cross currents which are created by the whirling blades.

In its simplest form, sailing is being pushed through the water by a wind blowing against a sail from the rear. The resistance of the sail to the wind is greater than that of the boat to the water and the craft moves forward. Modern boats, however, can sail at an angle to the wind, and by zigzagging, or tacking, can even work their way against the wind. How they do this is always a mystery to the layman. The explanation lies in the fact that the keel and hull of the boat offer strong resistance to sidewise movement, while the sharp-pointed prow cuts through the water easily.


As you slide your model boat out into the air stream on your table-top ocean, study the action of the

breeze on the sails. Naturally, the model won't give you the feel of a real boat sliding through the water under a spread of canvas, but by pointing the bow in various directions in relation to the electric-fan wind, and studying the movement of the sails and the pull on the lines that control them, you can pick up a good deal of valuable information about the three primary ways of sailing—with the wind, called running; across the wind, called reaching; and into the wind, called beating or pointing.

To see how a boat runs before the wind, turn your model so that the bow points away from the fan, letting the mainsail swing out until it rides practically at right angles to the center




COMING ABOUT is one of the most important maneuvers in sailing, as it is the basis of tacking, or zigzagging against the direction of the wind. The boat is headed into the wind and the sails swing over to the other side of the vessel



JIBING resembles coming about, except that it is done with the wind astern. If controlled, it is a safe sailing trick, but an accidental jibe can be very dangerous as the boom may be whipped across so violently as to do considerable damage

REACHING. For sailing sidewise to the wind, the boat is turned in the desired direction and the sails are let out until they begin to flutter. Then they are hauled in to catch the breeze



Here's the craft you use in your table-top yachting, with names of its rigging. You can put it together in a couple of hours with a few pieces of wood, a dozen or so of pins, strings, and some scraps of cloth

A Simple Homemade Model and an Electric Fan Illustrate the Fundamentals of Yachting

line of the boat. Loosen the strings holding the jib so that this sail can also belly out and fill with wind. This is the oldest method of sailing, and the only one known in ancient times. On the Nile, thousands of years ago, Egyptians needed only to sail with the wind, for the northward flow of the current would carry their ships down to the river mouth, where the early square-type sails could be hoisted to let the prevailing northerly wind blow the boats back upstream.

Now turn the model sidewise to the wind. Let the sails out until they flutter, then haul them in so that they catch the breeze. This is the position of a boat and its sails when she is reaching, or sailing across the wind. But if a real boat had a flat bottom like your model, the wind would drive the boat sidewise instead of forward. All sailboats, therefore, have a keel, centerboard, or leeboards that project down into the water below the boat's hull to resist and check this lateral movement.


Point the bow of your table-top craft toward but not directly at the fan, tighten down the sheets (lines) that control the angle of your sails, and the model will be in the position of a sailboat moving toward the wind. This is what sailors call beating to windward, or sailing close-hauled—that is, with the sails hauled in almost parallel to the center line of the boat.

In this position, your model will not heel, or tip sidewise from the force of the wind, but a real sailboat in a stiff breeze will sometimes dip its side right into the water as it races along. If this angle of heel becomes dangerous, the boat can be straightened up either by steering more into the wind, or by letting out the sails so that they ride at less of an angle to the wind.

The average sailboat will not move unless it is pointed at an angle of about forty-five degrees or more off the wind. You can easily tell if your model is pointed too close into the wind for efficient sailing by watching the sails. When the leading edges, or luffs, start to flutter, wind is getting in back of the sails and you must turn the bow of the boat a little farther away from the wind until this flapping stops.

Now swing your dining-table boat slowly into the wind until it is facing directly at the fan and you will see the sails catch the wind from both sides and flutter aimlessly. This is called luffing, and is used to stop a sailboat when approaching a dock or mooring, and in "coming about."

When your model boat is pointing at an angle into the wind in a close-hauled position, turn it slowly toward the fan until it luffs, and then continue turning it until it points away from the wind on the opposite side of the fan. The sails will first flutter as the boat



CLOSE-HAULED. How a sailboat can steer close into the wind is always a mystery to laymen. Sails are hauled in nearly parallel to the center line. The model is being held a tilt to represent the "heel" or slant of a real boat

points directly into the wind, and then will swing over to the other side of the boat, as you continue turning it, and finally fill up again with wind. Called coming about, this maneuver is used in tacking, or following a zigzag course to sail a boat to a point that lies directly in the teeth of the wind.

Coming about is also the safe way of changing direction when running before the wind, but a boat can shift its sails from one side to the other when the wind is blowing from astern, or

behind, instead of from ahead. To demonstrate this, place the model in the position of running before the wind, with the mainsail boom out practically at right angles to the boat. Now turn the boat slowly so that the tip of the boom moves toward the fan and watch the sail. When the breeze catches the back of the sail, it will whip the boom around to the other side of the craft.

Called a jibe, this maneuver can be extremely dangerous if it happens accidentally, as the lunging boom of a sailboat may crash into passengers, rip away the rigging, snap the mast, and even capsize the boat itself.

Controlled jibing, however, is a legitimate sailing maneuver and can be accomplished with safety, as you can determine by trying it on your model. Place the boat once more in the position of running before the wind, but this time as you turn it toward the boom, haul in the mainsail gradually until it is almost parallel with the boat before the wind has a chance to catch the back of the sail. When this finally occurs, the sail will move only a short distance and will not have a chance to gain speed and momentum before its swing is checked.


Jibing, it has probably occurred to you, is just the reverse of coming about. In coming about, the boat shifts from one tack or direction to another when the wind is ahead, and in jibing, when it is astern. Watch your model when you place it in the position of running before



RUNNING, or sailing before the wind, is simplest of all. Sails are about at right angles to the center line

(Continued on page 92)

The Man



with the Net

ELECTRIC washing machines exercise trout at one American hatchery.

CORNFIELDS are eroded 100 times as fast as pastures.

CALIFORNIA Indians used chewing gum long before the coming of the white men.



REAR TIRES, on automobiles driven over hard-surface roads, wear out twice as fast as front tires.

BLACKSNAKES can climb as high as thirty feet into trees.

DRY FLIES for fishing were used by the Romans as early as 200 A.D.



ONE MILLION pounds of silver each year go into the manufacture of photographic films.

SHARK OIL is being used to lubricate Japanese airplane engines.

EVERYBODY in the world could be supplied with one full-length garment of artificial silk out of the present annual production of rayon.

HOUSE FLIES on the wing can attain a speed of more than six feet a second.



ONE THIRD of all present-day factory products were unknown in 1880.

HEATED NAILS, driven in the wall, are less likely to crack the plaster than cold nails.

SYNTHETIC MOONLIGHT has been developed by a New York lighting engineer.



Pollen Census Aids Hay-Fever Sufferers

Glycerin-coated slide being put in tube to catch pollen samples



Technician examining slides to count and identify pollen

the air at various points throughout the city. Each evening, the slides are collected and sent to a laboratory, where mi-

A CENSUS of air-borne pollens that cause hay fever is now being made every day in New York City. Clean glass slides coated with a glycerin jelly are placed in metal tubes and exposed to

croscopic examination is made to determine the types and quantity of pollen present in the atmosphere. Results are made available to doctors, hospitals, and newspapers.

Letter Opener Doubles as a Postage Scale


LETTER OPENER and postage scale are combined in a new desk accessory just marketed. To determine whether a letter weighs more than one ounce, the blade is pulled forward to a spring stop in the handle and the device laid on a flat surface. When the letter is placed on the handle the blade will tilt upward if more than minimum postage is required.




The blade tips up if the letter needs more than minimum postage

Permanent Magnets Hold Metal for Working

ELECTRIC CURRENT is not required to operate a new magnetic chuck for holding metal while it is being worked. Employing magnets of a special alloy, the chuck uses an ingenious system of movable conductor bars and non-magnetic separators that shift the path of magnetic flow to hold or free the work.



Movable magnets give control of the work



Metal parts on magnetic chuck for grinding

Tests Show Way To Reduce Plane Fires

USING a giant wind tunnel as a blower, U. S. Bureau of Air Commerce engineers have tried out a method for emergency dumping of gasoline from the tanks of an airplane in flight, that is said to minimize the fire hazard.

Through experiments like that pictured below, experts found that if fuel is dumped so that it does not touch fuselage or tail surfaces, any fires that may start will be snuffed out by the air blast from the propeller.



This test indicated that, in a strong blast of wind, burning gasoline will not set fire to an airplane wing



Lens and Mirror Locate Cinders

MAGNIFYING glass and mirror are combined in a new accessory said to be useful for locating cinders or other foreign particles lodged in the eye. When the magnifying lens is held over the mirror, examination of the eye can easily be made, as shown in the photograph above.



Treadmill Walks the Dog


A TREADMILL exerciser, shown above, enables dogs to walk or run while remaining in one spot. It is designed for use by dogs kept in city apartments.

Device Tries Color Combinations for Cars

TO VISUALIZE the effect of various color combinations for automobile and truck bodies, one Detroit factory uses a novel color-mixing machine. Disks of the colors to be used are placed together to form sectors of a circle, and the composite disk is rotated rapidly. When the blended color effect is satisfactory, the relative amounts of the two colors making up the disk are noted, and the colors are applied in the same proportions in working out the decorative scheme for the car-painting job.



Colored disks being placed in the rotating machine for mixing



Board used in table-top golf and, left, two players following up their "shots"


Bridge-Table Golf Game Played with Cards

PLAYED on a board that represents a nine-hole golf course, a novel parlor game just introduced offers many of the features of the real sport. The presence of traps, bunkers, and water hazards, and the selection of the proper club all play a part in the success of contestants. Tiny balls in different colors are used as markers to follow the movements of the game as designated by cards drawn from a specially designed pack. In the course of the game, players can make clean, straight "shots" down the fairways, or fall into difficulties through slices and hooks into bunkers and other hazards.

Helps for Lawn and Garden



No need to kneel with this garden "horse"




"Tailored" Lawns Laid Like Linoleum

LAWNS can be laid like linoleum and tailored to fit around walks, drives, and buildings by the use of a material consisting of grass seed sandwiched between sheets of special vegetable paper. Cut to shape and laid on the ground, the paper is moistened and covered with topsoil. Soon the paper disintegrates and grass springs up, resulting in a more evenly sown lawn than could be produced by hand scattering of seed.

Nozzle Serves as Sprinkler

NOZZLE and sprinkler are combined in one unit in a garden-hose accessory now available. Threaded to fit any standard hose coupling, the device has a built-in metal stake which can be stuck into the ground to hold the sprinkler in position. An adjustable plate in front of the nozzle stream creates four different types of sprays.



Nozzle with spike and spray plate

Rocking Seat Makes Weeding Easy

TIPPING like a hobbyhorse, a novel garden seat makes it easy to weed vegetable or flower beds without stooping or kneeling on the ground. Made of metal, the garden horse has a hollow neck through which weeds may be dropped into a refuse container after they have been pulled up, for later disposal. A bar set across the opening serves as a handle for carrying the lightweight seat from place to place.




Porous Canvas Hose Saturates Soil


A HOSE of porous canvas laid along the ground is a new method of applying water to lawns, gardens, and hedges. Water seeps through the hose, as demonstrated above, supplying moisture to the ground evenly and without waste. The open end connects to a regular garden hose in place of the nozzle.

Spray Kills Fungus and Dyes Grass


BROWN PATCH, a fungous disease that causes unsightly brown spots on lawns, is controlled by a new chemical spray that also colors the patch to the shade of the surrounding grass. With a green dye as a base, the chemical is mixed to match any hue.

Colored chemical spray being applied to grass to kill fungus and restore the natural tint to the lawn





J. J. Dunkel with model of stratosphere gondola. Proposed balloon, left, has a parachute for gas bag



TWENTY-ONE-MILE

Veteran Stunt Balloonist Plans

ONE OF the most daring and fantastic stunts ever attempted—a twenty-one-mile parachute leap—is now being planned by a Cleveland, Ohio, dare-devil. Using a bomb-shaped gondola and stratosphere balloon of his own design, he hopes to rise to the top of the sky. At 110,000 feet, he will cut the balloon free and plummet toward the earth in his streamline metal cabin, speeding downward for more than 80,000 feet before releasing a parachute built into the gondola's tail.

The airman who plans this thrilling journey is no amateur sky rider. He is no crackpot, unaware of the dangers and difficulties in the way. He is Joseph J. Dunkel—the man who has made more parachute jumps than any other person in the world.

At the age of forty-one, this veteran has piled up a record of nearly 1,300 jumps. His longest drop was 28,800 feet; his shortest 250 feet. Once, he bailed out at 18,000 feet and plunged 16,500 before he jerked the rip cord. Another time, he hit the air going 300 miles an hour,

leaving a plane in the middle of a power dive.


When he goes into the stratosphere, he will have two goals in sight. During the ascent, he will try to reach the greatest height ever attained by man. And, during the descent, he will seek to reach the greatest speed ever experienced by a human. To achieve these goals, Dunkel has been working on the plans of a radically new type of stratosphere craft.

The bag of the balloon has been designed so it will be impossible for the neck to freeze shut and cause the balloon to burst in the frigid, rarefied air at the peak of its ascent. Another innovation is said to prevent dilution of the hydrogen gas. Lifted by this great gas container, Dunkel expects to penetrate the upper reaches of the sky to a height of nearly twenty-one miles. The present altitude record for stratosphere balloons is approximately fourteen miles.

This long ascent, however, will be only the preliminary to the real drama of the trip. High above the earth, Dunkel will jerk a cord, cutting loose the gondola and at the same time ripping open the gas bag, which will de-

By
WALTER E.
BURTON

Below, what a 'chute jumper sees: a landing field with circle marked as a target



Dunkel owns fifty-six kinds of parachutes. Here he is using a triangular 'chute which can be steered

PARACHUTE LEAP

Daring Jump from the Stratosphere

flate itself and float to earth supported by a parachute. In the meantime, the streamline gondola will plummet downward like an arrow, held on its course by fins at the rear. It will be traveling, Dunkel calculates, 2,000 miles an hour before it reaches denser atmosphere.

To withstand tremendous strains, the man-carrying meteor is to have a framework of steel tubing covered with sheets of superstrong alloy. An inner chamber of aluminum, an upright cylinder slung on special shock absorbers to eliminate unnecessary jars, will hold the standing passenger and scientific instruments. Should Dunkel lose consciousness and slump down in the cylinder, during the terrific plunge to earth, the act will automatically release the parachute at the tail of the gondola. This thirty-two-foot 'chute is designed to land the metal car at a speed of less than twenty miles an hour.

If all goes well, Dunkel plans to cut loose from the balloon at 110,000 feet, then wait until he is 30,000 feet above the earth before releasing the tail parachute. At 5,000 feet he will open a trapdoor in the nose of the gondola and drop out to descend, by means of a

small pack parachute, to the ground.

The cost of constructing the stratosphere craft and of making the flight would be in the neighborhood of \$100,000, he estimates. However, he believes, the scientific data on stresses and strains at meteoric speeds, which the flight would show, would be of incalculable value in designing high-flying speed planes of the future.


If Dunkel succeeds in making this spectacular ride to earth, it will climax a career of danger and daring which began when he was less than fourteen years old.

For, literally, Dunkel has been on the jump all his life. As a youngster, he was fascinated by the hot-air balloon exhibitions at Cleveland amusement parks. His heroes were the aeronauts who rode these frail craft aloft to cut loose *(Continued on page 99)*

Drawings at right and below show details of the plan for a leap from the stratosphere



For nearly thirty years, Dunkel has thrilled crowds by his daring jumps at fairs and other gatherings



Factory workers lined up outside the X-ray truck to be examined for diseases of lungs



Rolling Laboratory X-Rays Workers

CALLED the first of its kind, a cruising laboratory just placed in service by New York State health authorities can roll up to any factory or quarry, plug a 150-foot electric cable into the nearest outlet, and X-ray workers for traces of lung disease at the rate of one every two minutes. It will be used in a survey to determine what industrial processes expose workers to the greatest risk of silicosis and other diseases caused by inhaling dust.



A subject standing before the X-ray camera. The test takes two minutes



Sidewalk Signal Boxes Halt Trolley Cars

TO SAVE pedestrians from dodging speeding automobiles to board street cars, ninety-eight sidewalk signals are being installed in Detroit, Mich. When a prospective rider presses a button, as shown above, a lamp signals the motorman to stop, and the passenger need not leave the curb until traffic has also halted.

Auxiliary Vise Jaws Grip Fragile Parts

AUXILIARY jaws of new design, instantly attached to any vise, firmly hold odd-shaped or fragile parts without marring or distortion. The set includes hinged jaws for beveled parts, fabric-padded jaws for flat pieces of nickel, brass, and wood, and slotted jaws for round and square rods.



Weighted adapters hold the special jaws in place on any vise. Inset shows three of the four styles included in the complete set



Whistle Is Made of Chewing Gum


YEARS ago, toy whistles were often made of candy. To keep in line with the modern trend, manufacturers now mold similar noisemakers out of chewing gum. After a child has tired of using it as a whistle, he can chew it like a stick of ordinary chewing gum as there are no metal or wooden parts.



When you get tired of blowing these new whistles, you can chew them up

Melons Make Noises for Radio Dramas

STUNTS with a melon now provide realistic sound effects for radio gangster dramas. Hitting one with a mallet imitates the thud of a revolver butt upon a victim's skull, and dropping it from the top of a ladder to the floor sounds in the loudspeakers like the impact of a falling human body.



Hitting a melon with a mallet represents a blow from a gun butt



Newest Aids for Camera Users

Camera Gun Gets Long Shots

A TWIN-TRIGGER camera gun is now available for use in the field by explorers, naturalists, and sportsmen. It consists of a miniature camera equipped with a telephoto lens and mounted on a rifle stock. Focusing is done by moving the lens back and forth while watching the image on a ground-glass screen through a telescopic sight. The forward trigger on the gun snaps the shutter and takes the picture, and the rear one sets the shutter and winds the film ahead. Photographs can be taken with the outfit as fast as the triggers can be pulled. By loosening two knurled knobs, the camera can be removed for reloading. The total weight of the outfit is eight and three quarters pounds.



The camera gun in use. It is focused by moving the lens with the left hand while the image is viewed through a telescopic sight. Illustration at right shows arrangement of the parts



Motor Gives Rapid-Fire Action

BY CLAMPING a spring-motor attachment to the bottom of a leading make of miniature camera, users can turn an ordinary outfit into a "photographic machine gun" capable of snapping a dozen pictures in rapid succession. The attachment, designed especially for sports photography, permits sequence pictures showing the different stages of an action. They can be taken at intervals of either one half second or one second. A key at the bottom winds the spring motor. If fewer than twelve sequence shots are desired, the motor can be wound until the desired number appears in a window at the back. The camera can be operated independently, to obtain single pictures, while the motor attachment is in place.



Teeth Operate Shutter

DEvised by an Ohio inventor, a new cable-release attachment enables you to operate the shutter with your teeth, leaving both hands free to adjust the camera. The end of the release is clipped between the leaves of a rubber-covered spring held between the teeth. Biting down on the spring pushes the release plunger down.


Transformer for Floodlights

ORDINARY electric-lamp bulbs can be made to produce the brilliant illumination needed for indoor photography by using a compact transformer unit recently placed on the market. Lamps totaling 500 watts can be plugged into the unit at one time. With the switch at "low," they burn with normal intensity. After the camera is focused, the switch is moved to "high." This increases the voltage until, the manufacturer reports, the lamp gives off from five to six times as much light as normally. This high-voltage current reaches the bulbs only for the short interval while the picture is being snapped. The device is fitted with a convenient handle.



Bubbleproof Developing Tank

SPECIAL channels in the walls of a new hard-rubber developing tank carry the chemical solution downward so the container fills from the bottom, preventing air bubbles from forming on the films and producing blank spots on the negatives. Three sizes of plates, cut films, and film packs are accommodated by the stainless-steel holders within the tank. The negatives can be developed, fixed, and washed without removing them from the holders or the tank.



Stainless-steel holders accommodate three sizes of plates, cut films, and film packs in the tank


Carpets and Bells Guide Blind Ball Players

CARPETS three feet wide mark the base lines of a diamond specially prepared for blind baseball players in California. Using a soft ball whose hollow center contains a tinkling bell, the blind players are guided by bells and buzzers of various tones op-

erated by an umpire from a central control box. When the ball is hit, one bell signals all players that it is in fair territory, and buzzers under each base inform runners that it is safe to start running in an effort to reach the next base.



With the control box above, the umpire rings bells at the bases informing blind ball players it is safe to run



Wind Models Aid Student Flyers

STUDENTS at the Boeing School of Aeronautics, Oakland, Calif., visualize movements of the air with the aid of graphic models made of transparent cellulose paper and cotton. Sheets of the paper represent major air movements, while cotton shows the turbulence that arises when two air masses meet. Models are studied in connection with meteorological charts.



Aeronautics students using the cotton model of air currents

McCarthy Now Stands on His Own Feet

CHARLIE MCCARTHY, famous dummy used by the ventriloquist Edgar Bergen, is no longer a strictly sedentary worker. Outfitted with a pair of ingenious wooden legs, Charlie can now perform his amusing antics while standing or in a variety of other positions at the will of his master.



Charlie McCarthy trying out his new legs



Taking samples of air to learn its effect on bridge paint

Analyze Air That Bridge "Breathes"

WHAT is in the air that a bridge "breathes"? Sulphates, coffee chaff, soot, and salt, among other things, according to tests on the San Francisco-Oakland Bay Bridge with a novel air collector devised by the California Division of Highways. Designed to collect air samples for later analysis of components in the atmosphere that are destructive to paint, the instrument has a wind-powered pump that forces air into a test bottle.



Archer's Arrow Smashes Bottle To Christen Airliner

STANDING on the wing of a new transport plane, a modern Robin Hood recently christened the craft by shattering with his arrow a bottle of ale suspended over the plane's nose from a long pole. An instant after the


photograph was taken, the archer released the arrow. The steel-tipped shaft sped to its mark, smashed the bottle, and sprayed the contents down over the nose of the new airliner for the traditional christening.

Holder Guards Blasting Caps

Capped fuses for detonating explosive charges in a mine or quarry are carried safely in a new rubber container invented by R. J. Murray, Colorado mine inspector. A cylindrical rubber block has perforations in one end for inserting the capped ends of the fuses. If accidentally dropped, the rubber container absorbs the shock to prevent the blasting caps from exploding.



Fuse caps stuck into a rubber container to prevent explosion




No, He's Not a Fire Eater!

EXPERIMENTING with liquid air, whose temperature is about 330 degrees below zero F., a New Jersey hobbyist has devised amazing tricks. In one, he takes the frigid liquid into his mouth and blows it out as a cloud of "steam," as illustrated above.

Bike Saddles Get Shock Absorbers

EASIER riding is claimed for bicycle saddles equipped with a new hydraulic shock absorber that controls the action of the saddle springs. It is mounted as shown at the right.




Gas "Fireproofs" Gasoline in Storage

TO REDUCE the hazards in handling gasoline and oil, especially in connection with airplanes, a new safety system employs an inert gas refined from motor exhausts. Introduced into fuel-storage tanks, it forms a protective blanket immediately above the liquid to prevent accidental combustion. A novel test of its effectiveness is illustrated in the photograph below, showing workmen welding a tank partially full of gasoline. The inert gas, introduced into the tank from storage cylinders, prevents the welding-torch arc from causing an explosion.





Gas forced into this drum blanketed the gasoline against a welding flame

Skimmed



Drawing by
B. G. SEIELSTAD



Dwarfed beside a huge coal breaker located in the coal mining region near Shenandoah, Pa., this building houses the equipment that separates pure coal from the waste that accompanies it from the mines. The tank in foreground settles used chemicals, which are distilled and returned to be used again

SKIMMING coal from the top of a heavy liquid as easily as cream is skimmed from milk, a new coal-cleaning process converts the raw material from the mines into pure fuel for your furnace many times faster than most existing methods. Demonstrated for the first time just a few weeks ago at Shenandoah, Pa., the new chemical cleaning process is the result of thirty years of research by Du Pont engineers.

To visualize how the system works, imagine tossing a handful of stones mixed with wood chips into a bucket of water. The stones would sink and the chips float, because stone is heavier than water and wood is lighter. Now, imagine a liquid weighing more than coal, yet less than the heavy slate, stone, and other impurities that are naturally mixed with it. This liquid would "float" the coal and "sink" the impurities. Just such a fluid—a special mixture of organic liquids—is the lifeblood of the new "sink-and-float" separation process.

In operation, the unique plant taps the mined materials from the early processing stages of the coal breaker. Crushed to medium size, the coal and waste are first fed to washing screens. Powerful jets of

Coal


NEW SINK-AND-FLOAT PROCESS REMOVES SLATE AND SPEEDS PRODUCTION

water spray the materials, removing loose dirt and silt. A chemical mixed with the washing water causes each particle to be wrapped up in a virtual blanket of water that will not run off. Finally, the materials are plunged into the separation tank containing the heavy liquid and a layer of water which floats on top like oil on vinegar and prevents evaporation. The stone and slate immediately sink to the bottom of the heavy liquid, while pure coal floats to its surface, underlying the layer of water.

Along the bottom of the tank, and at the dividing line of the water and heavy liquid, are chain conveyors. The lower one drags out the refuse. The upper one skims away the floating coal.

Strange to say, neither the refuse nor the coal has actually been touched by the heavy liquid, and therein lies the economic secret of the process. If the heavy liquid clung to the particles, it would be impossible to recover it cheaply. If it touched them, it *would* cling. What heavy liquid comes out of the tank with the chunks of coal and slate touches only the water "blanket" wrapped around them, and is easily washed off by water sprays. This wash water is then collected in tanks, as is the original wash water, and settling and distillation easily recover all the chemicals for use over and over again.

By varying the specific gravity of the heavy liquid, the process, according to its designers, can be used for the separation of many minerals.



In this demonstration, coal and slate dropped in a jar of the heavy liquid have separated, coal rising to the top

Right, workmen inspecting pipes connecting a chemical-storage tank with the coal-cleaning machinery of the plant

Below, coal completely freed of refuse coming from the machinery in a steady black flow on an endless-chain conveyor



Using a Heavy Liquid that Floats Coal and Sinks the Refuse that Comes with It from the Mines, Engineers Have Devised a Swift New Way of Cleaning Coal and Many Other Minerals

POPULAR SCIENCE

Question Bee

Watch your step! For each of the numbered questions below, only one of the accompanying answers is correct. The others, no matter how reasonable they may sound, are put in just to fool you. See whether you can pick out the correct answer in each case, and make a note of the corresponding letter. Then turn to page 99 and check up to see what score you made



1 A juggler entertains people by maintaining objects in a state of (a) ionization (b) aerostation (c) suspended animation (d) unstable equilibrium (e) trial balance.

2 The things in your heart that pump blood into your arteries are called (a) mandibles (b) ventricles (c) spiracles (d) oracles (e) tentacles.

3 Hydrogen sulphide smells like (a) gardenias (b) burning sulphur (c) new-mown hay (d) rotten eggs.

4 The world's largest telescope, employing a 200-inch mirror, is to be installed (a) on Canton Island in the Pacific Ocean (b) atop Palomar Mountain in southern California (c) in the dome of the United States Capitol (d) on Mount Everest in the Himalayas.

5 Bank-and-turn indicators are used upon (a) bank-vault doors (b) racing automobiles (c) airplanes (d) roulette wheels.

6 What a community does for protection against a night air raid is known as (a) a fade-out (b) a black-out (c) a hide-out (d) bailing out.

7 The only mammals capable of true flight are (a) birds (b) bats (c) bumblebees.

8 Movies depend upon a phenomenon called (a) retinal fatigue (b) double refraction (c) persistence of vision (d) myopia.

9 If a tree is deciduous, it (a) stays green all the year 'round (b) bears edible fruit (c) grows only in tropical climates (d) sheds its leaves in the fall.

10 To assure us of a supply of the "No. 1 strategic mineral" in case of war, the U. S. Navy Department has placed contracts that encourage domestic mining of (a) gold (b) manganese (c) salt (d) diamonds.

11 The gram and liter are units of the (a) Culbertson system (b) metric system (c) Bedaux system (d) vascular system.

12 Silicosis is (a) a disease transmitted by parrots (b) the process by which trees become petrified (c) an ailment caused by inhaling rock dust.

13 The U. S. Department of Agriculture introduces and promotes the use of new foods such as (a) dinosaur eggs (b) cube roots (c) Jerusalem artichokes (d) wing nuts (e) niter cake.

14 One of a car's rear wheels is allowed to turn faster than the other, in rounding a corner, by a (a) universal joint (b) loose coupler (c) turn-buckle (d) differential (e) radius rod (f) Scotch yoke.

15 Whether people can read each other's minds is currently being tested with (a) devices that measure electric currents in the brain (b) packs of cards bearing emblems such as circles, squares, and stars (c) conversations over telephones with the transmitters removed.

16 An animal reverting to an earlier stage of evolution is called a (a) switchback (b) throwback (c) fullback.

17 To conserve filing space, books and documents are now being (a) squeezed into compact bales by hydraulic presses (b) photographed on motion-picture film for inspection through an enlarging viewer (c) read aloud for phonographic recording.

18 A device to read a graduated scale with high precision is known as a (a) vernier (b) decrement (c) terminator (d) megger.

19 Coaxial cables (a) support large suspension bridges (b) transmit television programs (c) operate small rotary tools through flexible shafts.

20 A substance that promotes a chemical reaction, without undergoing any chemical change itself, is called (a) an oxidizing agent (b) a reducing agent (c) a catalyst (d) an ester (e) an isotope.


21 A rhombus is (a) a popular Cuban dance (b) a puzzle in which words or syllables are represented by pictures (c) a rain-bearing cloud of uniform gray color (d) a lozenge-shaped geometrical figure.

22 Wire of any desired size is produced by drawing the metal through a (a) bushing (b) mandrel (c) tap (d) die (e) pillow block.

23 A celebrated mirage is known as the (a) fata morgana (b) passo Romano (c) Mona Lisa (d) miasma.


24 What makes tap water sometimes look milky is (a) carbon dioxide gas (b) precipitated chalk (c) air bubbles (d) a compound formed from iron in the pipes.

25 A dangerous habit-forming drug, in which a widespread illicit traffic has developed in recent years, is called (a) curare (b) marijuana (c) tung oil (d) luminiferous ether.



Un-Natural History


By
GUS MAGER




MANY NATURALISTS NOW SAY THAT THE OPOSSUM DOESN'T REALLY "PLAY DEAD" WHEN FACED BY DANGER, BUT COLLAPSES FROM FRIGHT. TESTS HAVE SHOWN THAT AT SUCH TIMES THE CREATURE'S BREATHING IS AFFECTED AND ITS SURFACE BODY TEMPERATURE IS LOWERED—IN OTHER WORDS, HE'S JUST FAINTED, THAT'S ALL.



WHEN TULIPS WERE INTRODUCED INTO EUROPE AROUND 1600, THEY STARTED A GAMBLING CRAZE. FORTUNES WERE PAID FOR RARE VARIETIES OF BULBS, UNTIL THE DUTCH GOVERNMENT SUPPRESSED THE "TULIPOMANIA" IN 1636.



STRANGE SEA SHELLS CALLED LAMP SHELLS CAN HEAVE TO AND THROW OUT ANCHORS THAT HOLD THEM SO FIRMLY THAT EVEN THE HEAVIEST SEAS CANNOT TEAR THEM LOOSE. STRANGER STILL, THESE ODD CREATURES ARE NOT MOLLUSKS BUT WORMS.



SOME INSECTS APPARENTLY POSSESS A MYSTERIOUS POWER OF SECOND SIGHT. ONE OF THE PARASITIC RUBY WASPS STRANGELY SENSES JUST WHEN AND WHERE THE MASON WASP'S GRUB HAS FORMED ITS COCOON INSIDE THE SHELL OF HARDENED MUD, AND DEPOSITS ITS EGGS RIGHT ON THE COCOON. AND THE CHALCID FLY, ANOTHER PARASITE, SIMILARLY LOCATES THE MASON BEE'S CELLS THROUGH THE THICK WALLS OF THE NEST.




LIKE A HUMAN HOUSEWIFE, THE POCKET MOUSE GOES MARKETING WITH HER SHOPPING BAG. IT IS THE ONLY NORTH AMERICAN MAMMAL THAT HAS EXTERNAL POUCHES FOR CARRYING FOOD—REAL HAIR-LINED POCKETS IN THE CHEEKS FOR BRINGING HOME THE BERRIES.



THE LARGEST PLANT IN THE SEA—AND THE TALLEST IN THE WHOLE WORLD—IS THE ANTARCTIC LAMINARIAN SEAWEED, WHICH GROWS UP TO 1,000 FEET LONG.

QUEEREST OF ALL SHELLS THAT ANCHOR THEMSELVES IS THE WATERING-POT SHELL FOUND IN THE RED SEA. WHEN EXCITED, THE ANIMAL SPRINKLES WATER THROUGH HOLES AT THE TOP OF ITS BONY TUBE. ITS RUFFLED ANCHOR IS SO FIRMLY MOORED THAT THE CREATURE MAY BE TORN APART WITHOUT THE ANCHOR GIVING WAY. AND SEE HOW SMALL THE ACTUAL SHELL IS.



New Appliances



HOLDER FOR COFFEE MAKER. A handy feature of a new vacuum-type coffee maker is a special holder in which the top section may be set, as seen at right, after the coffee is made. A container catches the late drippings




TOOTHBRUSH AIDS. Slipped around the head of a toothbrush, the metal guard below prevents waste and mess in using powder. The lower picture shows a novel dispensing cap for tube products, which allows paste to pass through and then closes itself automatically



SWING-OUT BROILER. Attached to the door of a new gas range, the broiler compartment illustrated below swings out of the oven for easy inspection, turning, or removal of broiled foods



WAFFLE MOLD. Made of cast aluminum and attached to an L-shaped handle, this odd waffle mold is dipped in batter and placed in hot cooking oil. As the batter expands, the mold is lifted and the waffle automatically drops off



ADJUSTABLE EGG BEATER. Set at any convenient angle, the handle of an improved egg beater is equipped with an adjustable grip that makes it easy to use. Special design of the dasher blades is said to end splashing

for the Household

FAUCET WATER HEATER. Hot water is produced right at the tap by the electrical fixture pictured below. Turning the hot-water faucet automatically switches on an electric arc that supplies the heat




EXPANDING MIXER. Operated by pumping the handle up and down, the ingenious mixer below has a dasher unit that is expanded by centrifugal force to conform to the size of any vessel, from a wide bowl to a small jar



REFRIGERATOR-BOTTLE FAUCET. Liquids are drawn from this refrigerator bottle by pressing the button on the self-venting faucet, which is not affected by acids in fruit juices or wine

BUILT-IN DISHWASHER. Installed in a standard sink cabinet, a new electric dishwasher opens from the front. The interior is lighted automatically when the door of the washer is opened




COMPRESSED WASHCLOTHS. Cotton washcloths, compressed into small disks and packed in a cardboard cylinder, are handy in traveling. Placed in water, each swells into a thick pad six inches square



FOLDING GARMENT RACK. Mounted on a closet door, the rack shown at the left holds six clothes hangers. The horizontal bar swings up and locks in place, holding garments in small space

Harry filled the barrel, and Gus clamped the motor to a block of wood in the vise so that its propeller was in the water. Then he poured fuel in the tank and pulled the starting cord



• GUS GIVES SOME TIPS ON Outboard Motors

By MARTIN BUNN

IT WAS a midweek afternoon in the Model Garage. In the little office, industrious Joe Clark was happily engaged in making out the customers' monthly statements. From the depths of the greasing pit outside came, hollowly, the voice of Harry, the musical mechanic, raised in lugubrious song. Gus Wilson listened to it as he took apart a balky carburetor. "Why don't these kids ever sing anything cheerful?" he wondered, his thoughts on the ragtime of his youth.

A car stopped in the driveway, and Gus heard the crunch of footsteps on the gravel of the yard. Then a peppery voice snapped:

"Mr. Wilson, I've been defrauded!"

Gus didn't have to look up to know that it was Professor Clapp. The professor had been staying up at his cottage at Coldspring Lake since the closing of the local high school over which he tyrannized, and the Model Garage hadn't seen much of him.

"Hello, Professor," Gus said, grinning. "What's that—you've been defrauded? Well, just step into the office and talk to Joe Clark about it. He's the fellow who takes care of that branch of our business!"

Professor Clapp refused to smile. "It isn't the Model Garage that has defrauded me—this time," he conceded grudgingly. "It is another—another dealer in motors. And in addition to being cheated, I have been made to look like a fool before every one at Coldspring Lake!"

Gus had to bend over his workbench to hide a grin. Before he dared to raise his head, another voice joined in the conversation with: "Why Father, it really wasn't *that* bad!" The voice belonged to an auburn-haired young woman with violet eyes and a piquant, freckled face, dressed in a play suit that revealed a generous length of sun-browned legs.

"Why, Bev!" Gus said, wondering at the remarkable transformation that a couple of years away at school had made in the professor's scrawny, red-headed daughter. She smiled at him, and called "Bring it in, Harry, please." Harry, beaming through the black grease with which his face was liberally smeared, came in carrying a large brown canvas bag that seemed to be heavy.

"It's just this outboard motor, Mr. Wilson," Beverly Clapp started to ex-

plain. "Father has had a little trouble—"

"My dear, I'm quite capable of explaining this unfortunate affair to Mr. Wilson!" the professor snapped. "For many years, Mr. Wilson, I have been an ardent devotee of the pastime of rowing. But my daughter, like all the young people of this unfortunate time, has succumbed to the lure of speed. All summer she has been pestering—has been trying to induce me to buy an outboard motor for my boat. While we were spending a few days at the seashore last week, I yielded. From a dealer said to be reputable I purchased, second-hand, this outboard motor.

"I took it to our cottage at Coldspring Lake. Following the dealer's instructions to the letter, I attached it to the stern of my boat. After some little effort, I started it. For a few minutes it ran smoothly, and I confess that I found the swift motion through the water enjoyable. But my enjoyment was short-lived. The motor began to make a terrible rattling racket. It would slow down, nearly shaking me to pieces, almost stop, then run again at its full speed.

"The erratic movements of my boat, together with the insufferable noise of the motor, attracted the attention of my neighbors sitting on their lake-side lawns and of the crowd of young idlers on the yacht-club float, who soon were roaring with empty-headed laughter. Hoping that among them there might be one with sufficient intelligence to adjust the infernal contraption, I headed for the float.

"When I was close to it, I pressed the button marked 'stop,' as directed by the dealer. The motor did not stop. Instead, it speeded up without warning. I crashed into the side of a canoe, doing considerable damage. In my frantic efforts to turn back into open water, I somehow reversed the motor, causing my boat to run backward into a new mahogany runabout, and seriously mar its finish.

"At last I succeeded in getting my boat back into the open lake. My further efforts to stop the motor were fruitless. So I had to circle around and around, now fast and now slow, listening to the laughter and jeering remarks of the idiots on the float. It wasn't until my fuel was exhausted, and the motor stopped, that I was able to row back to my cottage. Never have I been so humiliated!"

Harry was grinning openly. Gus tried to keep his face straight as he leaned over the outboard and started to take it out of its bag. "It's a long time since I've had anything to do with these put-puts," he said, "but maybe I can put this one right."

"Put-put it right," Bev said demurely. That gave Gus (*Continued on page 101*)

BUILDING A Contest Winner

SPEEDY MODEL PLANE
EMBODIES NEW IDEAS


SEVERAL new ideas for the 1938 contest season are embodied in this easily built model plane, the Experimenter No. 3. First is the single strut landing gear, which reduces parasitic drag, and the double rudders to provide ground stability. Second is the simplified keel construction, which aids in streamlining. Third is a new method of making a propeller spinner and an improved rear-hook assembly.

Fuselage. The precut upper and lower longerons are shaped from sheet balsa after the plans have been drawn full size. Place the balsa sheet under the drawing and prick pinholes along the curve. Then superimpose the side longerons over the plan and pin in place.

Set the upper longeron above the sides with temporary supports and cement in the braces. The end of each brace that is glued to the side longerons is cut at an angle, but the other end is allowed to protrude and cut to size after the brace has been fixed. When all the braces are in place and cut, cover the upper longeron with a soft capping strip. Cement temporary cross braces in place, and remove the assembly from the pin jig.

Make the lower portion similarly, but before completing the nose, make the plug from balsa as shown, with a square piece cemented in the rear. Using the plug as a guide, fill in the nose portion with $\frac{1}{8}$ -in. sheet balsa. Arrange the rear hook as shown. The brass bushings are best inserted before the upright pieces are cemented

By
Frank
Zaic



The unique one-strut landing gear is simple to make and cuts down the parasitic drag, while the twin rudders give the needed ground stability



Starting to wind the motor, which consists of six strands of $\frac{1}{8}$ -in. rubber. The model has a wing spread of $20\frac{1}{2}$ in.

in place. Cement the $\frac{1}{16}$ -in. square stringers as indicated. The landing gear may now be cemented in place.

Wing. Make a full-size drawing and cut ribs and trailing edges to shape from sheet balsa. The edges are made like the longerons. Cut all ribs the same

size because they are tapered by measuring the distances from the spar cut-in to the leading and trailing edges. Before cutting off the lower flat camber, make the two tapered spars, $\frac{1}{8}$ by $\frac{3}{8}$ in. at center and $\frac{1}{8}$ by $\frac{3}{16}$ in. towards the tip. Mark the rib positions on them and insert the corresponding rib. Note how much the rib protrudes below when the spar is pushed into the slot, and cut off the excess. Towards the tips, the rib ends may be larger than the edges, but just sand the upper camber to suit.

The wing is made in two pieces. First slip the ribs on the spar while it is superimposed on the drawing; then cement the precut trailing edges. Bend the leading edge while cementing it.

Remove from the jig, sand trailing



Complete working drawings of the Experimenter No. 3, with a scale in inches. The design is by Zaic, construction by Roger Hammer

edge to taper, clean up tips, and bevel spars for the proper dihedral angle. Cement the two wing halves together, being sure they have identical incidences. Finally, cement 1/64-in. sheet balsa along the leading edge as shown.

Stabilizer and Rudder. Follow the drawings and be sure the wood is strong. The rudders are fixed to the stabilizer after they are covered. An extra cement coat over the rudders will allow adjusting without cracking.

Covering. Use yellow paper, covering wing and tail first. Then cement wing to fuselage. Run an extra piece from the side longeron to the center spar through the paper. Cover the fuse-

lage, and use several small pieces at fuselage and wing junction. Note that 1/64-in. balsa is used on the section behind the nose plug. Mist-spray the whole job and coat with clear dope.

Filleting can be done, if desired, by cementing a piece of sheet balsa to the trailing edge and then filling the deep triangle with stiff writing paper. Paint the nose and wing with blue dope or enamel approximately as illustrated. Masking tape will help in outlining the painted area.

Propeller. Note that the blank is tapered from the center to the halfway point before the carving is begun. The lower camber is first completely carved

and finished, and be sure to give a bit of undercamber. The upper camber is carefully cut to correspond and so that it tapers from the center out, forming a sort of airfoil. The outline is easily made if the sharp corners where the various diagonals cross are rounded before carving; then only the tips need shaping after carving. Sand smooth and apply several coats of dope and a final coat of color after the spinner and freewheeler are fixed.

Cement disks of balsa on the hub so the spinner shape can be built up by cementing several balsa strips to them. If the propeller shaft is fixed and no freewheeling is used (in that case, in-

crease the dihedral to 3 in. to take care of the still prop in the glide), extend the strips to a point, and also extend them over the larger disk to cover the ball-bearing washer. If freewheeling is used, make a balsa cone tip and cement it to the winding end of the shaft. Insert the shaft into the plug bushing and bend the motor hook. Note the extra hook-back on which a rubber band is started and ended to bind the hook into a ring when the rubber is in place.

Checking and Flying. The motor—six strands of $\frac{1}{8}$ -in. flat rubber—is inserted by dropping it through the nose opening. A rear opening is not essential because the motor can be seen by holding the model in front of a light or against a bright, sunny sky. When the rubber end is in position over the rear bearings, the pin is pushed through. If a small opening is made at the rear, the rubber may be threaded through with a wire hook, and the hole covered with cellulose tape.

The model balances by holding it at the tips where the spars are. If necessary, add a bit of modeling clay to bring the center of gravity to about this point. Check the incidence and look out for warpage, especially on the stabilizer.

WHEN it comes to inside dope on contest flying, model airplane champions everywhere rely on Frank Zaic's "Model Aeronautics Year Book." An outstanding authority in his field, he gives in this exclusive article his ideas for improvements it will pay to use

Set the model on ground, lift the tail slightly, and give a gentle push. It should rise about a foot off the ground and commence a shallow glide. Then wind the motor about 100 turns. After that, if conditions permit, try it fully wound. If tests are unsatisfactory, check for warpage. Bend up the stabilizer's trailing edge to correct diving.

The original model has been duplicated several times, and every one has performed well. One was a high-speed job that clocked about 50 m.p.h., but solid wings and a hardwood prop with plenty of power were used. In calm weather with light risers, a minute and a half was clocked, and the model has traveled well over 1,000 ft. in windy weather.




Assembled wing and fuselage before being covered. Left, the propeller, nose plug, and landing gear. Right, the streamlined fuselage is unusually easy to construct



The wing framework superimposed over a full-size drawing. Actually, the wing is made in two halves, the ends of the spars are beveled to give a dihedral angle of $2\frac{1}{2}$ in., and the parts then cemented together. Left, ready for covering

The glass, which slides in felt channels, is kept closed by flat springs applied as shown below



Easy Method of Installing Windows in House Trailer

IF YOU desire to install rattleproof windows in a homemade house trailer, but cannot afford expensive hardware, this device will serve the purpose very well. The window is pulled up by means of a strap, and a light steel spring keeps it in position. Large windows require two springs and two straps.

Paint the inside of the window wells with asphaltum paint and provide for drainage at the bottom. Tack felt channels along the inside of sides and top of the window opening. Have auto glass

cut and ground to run smoothly up and down between the channels. Attach a metal window channel to bottom of glass and fasten a cotton web trunk strap to this to pull the window up.


For the spring, use annealed steel from an old, heavy clock spring or obtain a piece of annealed spring steel about 1/32 in. thick and 1/2 in. wide. Bend to shape, round all corners, and polish; then retemper and install. Cement felt to the spring where it touches the window glass.—FLOYD M. MILLER.

Six Painted Emblems for Canoe Paddles

CANOEISTS can give a touch of individuality to their equipment by decorating their paddles. Six designs are suggested. A, for example, is appropriate

for a fisherman, D for the canoeist who likes swift streams and rapids (the design being the Indian totem for "swift current"), and E for an expert swimmer. First draw the selected design on a large piece of paper, then transfer it to the blade of the paddle.


Paint with bright colors, especially A, B, and E, and when dry, outline the designs in black or dark blue, and apply two coats of transparent spar varnish. The same design may be used smaller in a circle on both sides of the canoe at the bow as at F.—GRAY WOLF.



The chosen design is brightly painted on the canoe paddle and repeated at the bow

Tennis-Court Edge Returns Passed Balls

MANY tiring steps to retrieve tennis balls may be saved by placing a 45-deg. incline along the entire length of the backstop and side walls of the court. The incline can either be permanent or made in removable sections of convenient length. It is formed by nailing 3/4-in. boards to 45-deg. supporting blocks about 1 in. thick, placed from 4 to 5 ft. apart. The width of the incline should not be less than 4 in. A good job can be done by using two 3-in. strips of tongue-and-groove flooring, as shown. With this width, most passed balls will return almost to the feet of the player at the base line. A coat or two of paint will help protect the wood from decay.—K. F. KEITH.



When a passed ball strikes the incline, it usually rolls back to the feet of the player

Horseshoe Coat Hooks Symbolize Good Luck

OLD horseshoes, which have so long been a symbol of good luck, may be converted into attractive coat hooks or costume hangers for use in a cabin, ranch house, hunting lodge, or any place where there is an interest in horses. Heat the calk part of one end of the shoe, hammer it to form a flat surface, and make a half twist an inch or two from that end so the shoe may be screwed against the wall as shown below or on a costumer. A dull oxidized iron finish may be given the shoe by applying sufficient heat to make the iron red-hot.—GEORGE A. SMITH.




One end of the shoe is heated, hammered flat, given a twist, and drilled for screws



Glass Used as Glue-CanTop

MUCH better than the metal cover of the conventional liquid-glue can is a small glass canister cup of the type used under table

legs. Placed upside down over the opening, it never sticks because the glass does not touch the rim of the opening. It also serves as a convenient place on which to lay the paddle or brush.—DONALD R. FOSLER.



Besides holding books, this useful piece of built-in furniture has an extra wide top that serves as a table

Dwarf Bookcase

FITS UNDER WINDOW



LOW bookcases, built to fit under wide windows, are very useful and add much to the appearance of a room. In the design illustrated, the top is wide enough to serve as a table, and the modernistic end compartments may be used for other things besides books, such as bowls, vases, smoking accessories, large magazines, or sewing materials.

The dimensions should be modified to suit the window under which the case is to stand. After cutting and planing the partitions and shelves, make four dados in each partition. These are easily cut with a dado head if a circular saw is available. It is advisable to make the dados a little narrower than the thickness of the shelves, then cut the shelf ends to exact thickness. This is done by placing the upper surface of each shelf against the ripping fence and running the ends


over the saw so that the waste is removed on the underside of each shelf. It follows that the height of the dado head over the saw table should not be changed. In this way perfectly fitting joints are assured.

Glue together the main parts; screw two pieces of $\frac{3}{8}$ -in. plywood backing to the rear edge of the outer partitions; then glue the rounded end shelves into their dados and screw the plywood back to them.

The lower rails are screwed to the lower shelves and the

back. Strips $\frac{1}{4}$ by $1\frac{1}{4}$ in. are glued to the front edges of the partitions, thus covering the dado joints. The top may be fastened with $\frac{3}{4}$ -in. square cleats screwed to the inner sides of the partitions.

The bookcase illustrated was made of birch, stained dark brown and finished with three coats of thin shellac. The first two coats were rubbed down with No. 2/0 steel wool, the last with No. 6/0 or 280 waterproof sandpaper and crude oil on a wooden block covered with cloth. A varnish finish, may be used instead.—HERMAN HJORTH.



Top and front views of the case, and details of the dadoed shelves and method of fastening the top. The dimensions are merely suggestive since the piece must fit the window

Mucilage Bottle Moistens Envelopes

AN OLD mucilage bottle of the type illustrated at the left, when washed out and filled with water, is a neat and efficient moistener for envelopes and

stamps. If the rubber tip is rubbed lightly over the gummed surface as illustrated, just the right amount of water will be applied.—PAUL AMES.

This is the idea of a five-year-old boy and was forwarded on his behalf by his uncle, Charles M. Dorris. Other boys have contributed excellent suggestions to the Home Workshop in the past, but Paul is the youngest contributor of whom we have any record.




An empty mucilage bottle is filled with water and used as of the right



Flame Spreader Is Aid in Burning Off Paint

A FLAME spreader made from sheet iron and applied to a blowtorch as shown enables old paint to be burned off with less danger that the concentrated part of the flame will scorch the surface. Paint may also be removed close to window glass or to polished metal or plated fittings.—W. C.



Hull nearing completion but before the inside is painted



Although intended chiefly for use with outboard motors ranging from 3 to 16 horsepower, the boat handles exceptionally well with oars. It is 11 ft. 6 in. in length

WE GET OUR NEW Fisherman's Boat



IN FITTING the planks of our new fisherman's outboard boat (see P.S.M., June '38, p. 55), it will simplify the work to put in the battens as they are required, rather than all at once.

After each plank is fitted, mark along its edge on the frames for the center

line of the batten. Fasten battens to frames with 1-in. No. 7 screws. There will be five bottom planks on each side of the keel. An ordinary pencil compass will come in handy in fitting one plank to the next.

Start with the bottom planks next to the keel—the garboards. They will have to be wrapped in rags and steamed with boiling water at the forward ends. Use 4-in. planks for the garboards; 6-in. can be used for the other bottom planks, and 4-in. widths

for the sides. Before these planks are in place, notches should be cut in the frames, next to the keel, so that water can run from one part of the boat to another.

The planks below the water line should be left open about 1/16 in. at the

joints to allow for swelling. After the first three planks on each side of the keel are in place, put on the bottom side planks and fit them to the forward ends of these three planks. Then the side planks should be dressed down flush with the chines; the last two bottom planks on each side will merely lap over them.


Just before screwing down each plank, coat with marine glue the battens, transom and transom frames, stem, keel, chines, and all joints that need to be waterproof. Then lay a strip of cotton flannelette over the glued surface and coat the cloth with glue. The battens that cover the bottom transom seam should be made water-tight in this manner. No cloth or marine glue is necessary in seams above the water line.

When fastening a plank, first clamp it in place and then drill holes for the screws. Use a stop on the drill so that all holes will be the right depth. The screws should be countersunk enough to allow for covering later with seam composition or putty.

Screw the planks down with flathead screws as follows: (1) Into transom frame, a double row of 1-in. No. 7, spaced not over 1 in. apart; (2) into stem, 1 1/4-in. No. 8, spaced about 1 in. apart; (3) into keel, chines, inner chines, and frames, 1-in. No. 7, spaced 1 1/2 to 2 in. apart. The planks



The rowing seat may be made removable by notching the seat frame over a cleat screwed to the side frames. Right, a stern view of the completed boat



The planking is started with the planks on each side of the keel. Boiling water is used to help in bending them at the forward end



Cross-section drawings at two of the stations. The garboards—planks nearest the keel—are fitted to the stem as illustrated below

Ready to Launch

can be fastened to the battens with 1-in. copper or galvanized nails spaced 2 in. apart. Unless very soft wood is used for planking, holes will have to be drilled for the nails. Clinch the nails by first knocking them over from inside with a hammer, then hammering on the head while holding a piece of iron against the nail on the inside of the batten. The planks may be screwed to the battens with $\frac{7}{8}$ -in. No. 6 screws instead of clinch nails. This is more work, but will make repairs easier

in case a plank ever needs to be removed. If screws are used, the battens should be spruce $\frac{1}{2}$ by 1 in.

Before the top side planks are put on, the boat should be removed from the form and set right side up on horses. It will be necessary temporarily to remove the deck frames to do this. The breasthook should be fitted and fastened to the sheer battens before the top planks are

put in place. Fasten with $1\frac{3}{4}$ -in. No. 8 and 2-in. No. 10 screws.

After the side planking is finished, the entire inside of the hull should be given a coat of paint. Before starting work on the decking, true up the sheer line, deck beams, and breasthook. Bevel the battens and planking along the sheer line and also the top of the transom so that the decking will fit perfectly. The inwales should be notched slightly into the side frames and fastened with $1\frac{1}{4}$ -in. No. 8 screws. The transom braces should be at least $\frac{3}{4}$ by $2\frac{1}{2}$ in. and fastened securely to the transom frame and frame No. 7, as shown in the last drawing, with several 2-in. No. 10 screws. Deck battens for the aft decking should be notched into the transom frame and screwed firmly to help brace the transom. Only a center batten is necessary for the forward decking. The decking is laid in 4-in. widths, nailed or screwed as desired.

Blocks to hold the oarlocks should be fitted between the sheer battens and inwales between frames Nos. 5 and 6. Make the seat frames from the same material as the frames, and the seats themselves from left-over planking. The rowing (Continued on page 91)

Planks are fitted more easily if the battens are put in one by one as required. Below, the planks are fastened to the battens with nails or screws



Wind-Driven Generator


SUPPLIES ELECTRIC CURRENT FOR A SUMMER HOME



wise, and place one in each slot with the ends extending an equal distance as the winding progresses. The paper may be obtained wherever motors and generators are repaired.

The armature winding requires $1\frac{1}{2}$ lb. of No. 20 celenamel wire. Cotton-enamel may be substituted, but the generator will require a higher speed since fewer turns can be used. In that case, see that each coil is reduced the same number of turns. Number the armature slots from 1 to 14 with a sharp tool, and the corresponding commutator bars from 1 to 28 (Fig. 1).

Divide the wire into two equal amounts, wound on separate spools, as two wires are wound together. Solder two ends of wire in slots 6 and 7 of commutator, place



Winding the armature. Two wires are wound at once and they are kept parallel in the slots to save space



Paper is put in slots as winding progresses. Below, rewound armature



By
KENDALL FORD

ELECTRIC current for lights and radio in a vacation home may be obtained at a cost that should not exceed ten dollars by building a wind-driven plant from a used automobile generator in good condition and some odds and ends of materials, most of which may be obtained from salvage.

The generator may be geared up for proper speed, but it is much better to rewind it to run at a greatly reduced speed. Practically any type of automobile generator may be adapted, but the outfit described is built around a

twenty-eight bar commutator, such as is used on the Ford A, Chevrolet, Plymouth, and Pontiac.

Remove the cut-out coil from the generator, noting which terminal is connected to the generator terminal. Remove armature windings carefully. Note arrangement of original armature coils. Clean slots in commutator bars with a hack-saw blade. Cut fourteen pieces of insulating paper, 2 by $2\frac{1}{2}$ in., fold length-






FIG. 3
Field coil with
one side of wind-
ing form removed




FIG. 4




FIG. 6

FIG. 5





FIG. 8

BRAZE OR SOLDER
TO BLADE

SMALL PULLEY

PIPE SPACER

1/4 THREADED
ROD

COLLAR
1/4 PIPE

BEARING
COVER NOT
IN PLACE

BALL BEARING
AND RACEWAY

1" PIPE

VANE-
ADJUSTING
CABLE

WOOD
CYLINDER

3/4 x 3/4 x 1/8
ANGLE IRON

PHOSPHOR
BRONZE
OR BRASS
BRUSHES

2x2
WOOD BLOCK


SWIVEL
JOINT

FIG. 11

NOT LESS THAN 12"

No. 10 LEADS TO
CUT-OUT AND BATTERY

FIG. 10



the two wires in armature slot 1, and continue around to armature slot 7, then back through armature slot 1, and continue winding until fourteen double turns have been wound on the armature. Connect the coil ends to commutator bars 7 and 8 (Fig. 2). For clearness, one armature wire is shown as a solid line, the other as a broken line. To save space, all wires in the armature slot should be parallel with each other. Press them in with a flat piece of fiber or wood.

Connect ends of coils to commutator exactly as in Fig. 2, so mark the wires as the coils are being wound, or test the coils with a dry cell and buzzer before they are connected to the commutator.


Continue this procedure until the armature is completely wound. See that the solder does not bridge two sections of the commutator.

Cut the insulation paper off about 1/8 in. above the armature, fold the ends into the armature slot, and hold down with a fiber or wood wedge similar to that used on the original winding.

Paint the (Continued on page 93)




FIG. 9




Wiring Diagram

FIG. 12




Completed generator,
propeller, and vane. At
right is a close-up of
the generator showing
a pulley and the cable
for adjusting the vane




EVEN A LOW-POWERED BOAT
CAN BE USED TO TOW THIS

Floating Aquaplane

By BRUCE and WILLARD CRANDALL



Its buoyancy makes this aquaplane easy to mount and ride, and it will never nose-dive



tens in place. True up the entire surface so the bottom and top planks will fit perfectly. Screw the planks to the battens, frames, and stem with $\frac{3}{4}$ -in. No. 7 brass screws not more than 2 in. apart. Lay strips of cotton flannelette or similar material, soaked in marine glue, over the joints that must be water-tight. Drill three holes through stem

and planking as shown. After painting or varnishing the aquaplane, tack on toweling or rubber matting.

If water-tight—and the secret of that is well-fitting joints and plenty of screws—this board will give excellent service.

YOU need not own a powerful and expensive speed boat to have good sport with this aquaplane. It floats buoyantly so that even the slowest outboard motor can pull it and give some measure of the thrills of aquaplaning. A floating board of this type is also much easier to mount and handle, and it never nose-dives into the sandy bottom.

If suitable materials are at hand, the board can be built in an afternoon. Here is what you will need:

1 pc. $1\frac{1}{4}$ by 6 by 21 in. spruce, oak, mahogany, or pine for the stem.

1 pc. $\frac{1}{2}$ by $3\frac{1}{2}$ in. by 14 ft. spruce, oak, mahogany, or pine for the frames.

3 pc. $\frac{1}{2}$ by $1\frac{1}{4}$ in. by 12 ft. spruce, mahogany, oak, or pine for the battens.

4 pc. $\frac{1}{4}$ or $\frac{3}{8}$ by 6 in. by 12 ft. cedar, mahogany, or cypress for the planking. If, however, the motor to be used is about 15 h.p. or over, it is best to use $\frac{3}{8}$ -in. rather than $\frac{1}{4}$ -in. planking.


1 pc. $\frac{1}{2}$ by $3\frac{1}{2}$ in. by 12 ft. spruce, mahogany, or oak for the side planks.

2 gross $\frac{3}{4}$ -in. No. 7 brass screws; 6 doz. 1-in. No. 8 brass screws; 1 pt. marine glue.

Cut the stem as shown, tapering it to a wedge shape so that it is $\frac{1}{2}$ in. thick at the bow (front) and the full thickness of $1\frac{1}{4}$ in. at the back. Make the frames and drill several holes in each to enable any water that may leak in to run through to the last frame. In this frame there is a water-outlet hole, kept plugged when the board is in use. Note that this back frame is made of two $\frac{1}{2}$ -in. pieces screwed together.

Build the aquaplane upside down, with the frames and stem laid out on a flat surface 1 ft. apart. The side frames must fit accurately against the stem and last frame. Coat the surfaces with marine glue before fastening them.

Cut notches for the battens in the frames and stem, and screw the bat-



A top view of the aquaplane with the planking partly broken away to show the framework, and a sectional side view. Above are the frames and stem. Frame No. 6 is made double thick


Driveway Gate Built of Rough Boards

OF HEAVY stockade design, the gate shown below is substantial and durable. A good type for auto driveways at country homes, estates, and farms, it is made entirely of rough

boards 1 in. thick and 6 in. wide, spaced 4 in. apart. The taller boards are 40 in. high; the short ones, 34 in. The end boards are doubled. Roundhead carriage bolts $2\frac{1}{2}$ by $\frac{1}{2}$ in. are used in assembling the gate—123 altogether. One longer bolt is used in attaching the heavy strap-iron latch. All the bolt-heads are placed on the street side.

The gates can be hung on wood or stone posts with regular lag-screw gate hinges. With stone

posts the hangers will have to be placed between the stones when the posts are being built. The gates are stained with brown shingle stain or can be painted if so desired.—HAROLD JACKSON.



Metallic Wall Pictures in Chinese Style


DECORATIVE wall pictures can be fashioned with comparative ease from wire and sheet metal. The two illustrated are copies of Chinese originals.

To make the cherry-tree scene, first sketch the drawing full size on paper. Obtain about 4 ft. of heavy steel wire, such as fence wire, about $\frac{1}{8}$ in. in diameter. Form this in an 11 $\frac{1}{2}$ -in. circle and solder the ends with a butt joint, where it will later be concealed by the tree trunk. Solder on two small rings of 1/16-in. wire to form lugs as shown, and add the bent wire hanger.


By means of carbon paper, transfer the drawing of the tree (omitting the flowers, flower stems, and bird) to a sheet of copper or tin, which should not be any thicker than 1/32 in. Cut out the silhouette with tinner's shears. Reverse the metal, place it on a block of soft wood, and indent it as indicated with a blunt punch. Then peen the edges with a small hammer over the edge of the wooden block. The smaller limbs may be beveled into a semblance of roundness with a file.

Place the tree within the frame and solder it with butt joints at the two spots where the upper limbs touch the frame. With a small hammer, peen the base of the tree down on the frame, hold it with small clamps, and solder securely from the rear.

From the scraps of metal remaining, shape and drill or punch twenty pieces for the flowers like A, and twenty like B. Crimp the petals and centers into a realistic shape over a block of soft wood



PEEN
EDGE OVER
WOOD BLOCK




WHEN
CUTTING,
ALLOW FOR
LAPPING OVER



1" SQUARES



Innumerable designs in silhouette can be cut from copper or tin with a pair of tinner's shears



with the bluntly convex end of a $\frac{3}{8}$ -in. round punch. Assemble the flowers with rivets, the heads being uppermost.


Cut short pieces of 1/32-in. wire for the stems and solder them flat on the back of the flowers. Then solder the stem ends to the tree limbs.

Above, an attractive flower pattern. Left, full-size drawings of the bird and flowers. Parts A and B are fastened with rivets and crimped to shape

Crimp the flowers marked X to represent half-opened buds. Now cut out the bird and solder it in place from the back.

Apply a metallic priming coat and a finishing coat of glossy black enamel. Dry thoroughly before hanging—C. H.


Split Pieces of Rubber Hose Train Vines



TO TRAIN a climbing vine on a fixed trellis in such a way that the vine may be removed in the fall for mulching or covering, cut a number of short sections from a length of bath hose, split these along one side and tack them on the trellis as shown. The sections may be opened for inserting the vine, but close around it when released and hold it securely.—G. E. HENDRICKSON.

Large Magnet Holds Tools

A LARGE, powerful horseshoe magnet mounted over the bench forms a handy holder for small tools. They can be removed and replaced quickly.




Cleaning Mower Guards

GUARDS on the mower or binder are readily cleaned with the tool shown above. File four or five sawlike teeth in the center of a 20-in. piece of strap iron, and bend the ends up and back. Use the toothed part to clean the nose of the guard, the square ends of the handles for the plates.—NORVAL WRIGHT.

Arched Lattice Gateway for the Garden



Almost any garden or back-yard entrance can be dressed up with this unusually attractive latticework gate. Dimensions may be altered to suit any conditions



THIS latticework gate with side wings can be used at the garden or backyard entrance with pleasing results. White pine, cypress, and redwood are all good weather-resisting woods for such work, and galvanized nails must be used. The gate may be hung with galvanized T-hinges and a latch provided, or it may be nailed in place if the trellis is intended purely for decoration and the gate is not to be used.

The gateposts are 4 by 4 in. and 10 ft. long, although they actually measure about 3 1/2 in. square. They are set in the ground 3 ft. apart on the inside and project 6 ft. 6 in. above the ground level. The tops of the posts are notched at each side to receive the segments of the arch as shown in the drawings, be-

fore setting the posts into the ground.

The arch is made of four segments cut from 1 by 12-in. material. Two curved tie blocks are used to join the center of the arch. The lower ends straddle the tops of the gateposts. The 8-in. long lattice crossbars are then nailed around the top of the arch. The arch is completed on the workbench, then lifted to its place and securely nailed from both sides.

The gate and side panels are simple latticework construction. The strips are about 3/4 in. thick and 1 1/2 in. wide, and twenty-six will be needed. Twenty-four are 4 ft. 9 in. long, but the other two, which go at the sides of the gate, must be 6 in. longer. All are spaced 1 1/2 in. apart. The crosspieces are lightly nailed

to the shop floor, and the up-and-down strips then nailed to them. One strip is used to do the spacing with, which saves time and a lot of measuring. The cross strips and gate braces are 2 in. wide.

The round opening at the top of the gate is 36 in. in diameter, and the tops of the gate strips are cut to conform to this circle. The wings are rounded off at the top at the same curvature, that is, with an 18-in. radius.

The outer posts are 2 by 6 in. by 9 ft. long and are set 22 1/2 in. out from the gateposts. They project 5 ft. 3 in. above the ground and are rounded off at the top. The side panels are fastened to blocks nailed to the inside of the posts. The front of the latticework is flush with the front of the posts.—H.J.


Camp Blankets Made into Sleeping Bag



Seltzer Puts Out Fire


SELTZER bottles, which are inexpensive and can be placed in convenient locations about the home, workshop, or farm buildings, will serve as fire extinguishers. Just squirt the liquid full blast at the base of the fire.—W. W.

Two single 4-lb. blankets, if cut as shown and sewed into a double bag, provide a lightweight, economical camp bed. The outside blanket should be of hard-woven fabric to stand wear; the inner blanket, loosely woven and very soft for warmth. In sewing, whip the edges with an over-and-over stitch. Have the inner bag 1 in. smaller each way. By making the blankets into bags, you discard about 1,100 square inches from each and save about 1 1/2 lb. in pack weight.—MAURICE H. DECKER.





Use either plywood or slash-grained wood for the two paddles. Cover the ends of the racket handles with leather



This Badminton Set

COSTS LITTLE TO MAKE

A SUBSTITUTE for a regular badminton racket can be made at a cost of twenty-five cents or less by the method illustrated. The main body can be of 1/2-in. slash-grained wood (the slashed grain to protect against splitting) or from 1/4-in. plywood. Care should be taken to balance the racket at the throat in the same manner that a tennis racket is balanced. The end of the handle is finished with leather.

For the shuttlecocks, small two-for-a-nickel, sponge-rubber balls or large five-cent corks will serve. Cut the sponge-rubber balls in half, if they are to be used, and burn eight or more holes around the flat edge at an angle of 45 deg. Cut off most of the quill end of the wing feathers from a chicken and insert the cut ends into the holes as fast as the holes are burned. The soft-

tened rubber will help to cement the feather in place. Place the feathers so that their surface is approximately parallel with the curved edge of the ball. Trim off the ends of the feathers to govern the speed; the more feathers, the slower the action. Rubber shuttlecocks are faster than the cork ones.

The cork shuttlecocks are made in the same manner except that the angle is only 15 deg. for the feathers. Glue the feathers in the small end of the cork and grind the large end round on an emery stone.—R. H. JENKINS.



Two methods for making the shuttlecocks. The rubber ones are faster. At right, a completed badminton set



Advertising Thermometer Adapted for Chemicals

SMALL thermometers used on advertising calendars and for similar purposes are sometimes surprisingly accurate. If such a thermometer is cut out and inserted in a small vial, which is fitted with a one-holed cork to receive a glass tube as shown, it will serve for measuring the temperature of liquids used in the laboratory, workshop, and photographic dark-room. Several drops of mercury poured in the vial will make the thermometer respond quickly.



Nonsnagging Boat Anchor

A MUSHROOM anchor for small boats can be made from an 8 by 1/2-in. galvanized eyebolt, one or two pigs of lead, and a 6-in. frying pan from the ten-cent store. Remove the nut from the bolt, file a 1/4-in. notch in the threaded end as shown, stand the bolt in the center of the skillet, and melt the lead in the pan over a hot fire.



After the lead has cooled, the anchor may be lifted out of the pan. Its advantages are many: it won't snarl its line, it is small and compact, it works on practically any bottom except smooth rock, and it will not snag on roots or stumps.—J. E. GUY.

Sails for the 'ALABAMA'

IF SAILS are to be set on your model of the Confederate commerce raider *Alabama**, they should be fastened to their yards before the yards themselves are placed—or "crossed," to use the nautical term.

Any opaque material will do for the sails, provided it is quite thin. So-called "balloon cloth" serves nicely. The

*This series of articles began in the February, 1938, issue.

shape and size of the fore-and-aft sails can be taken from the rigging plan (P.S.M., June '38, p. 74) by making the necessary enlargement of all dimensions. Paper patterns should be made for each sail. Separate plans are given in the accompanying drawings for the square sails and stunsails.

The square sails should be cut slightly oversize to allow them to be bent around the yards to the jackstays and

to give a little fullness along the foot. In addition, of course, allowance must be made for the hems.

Rows of stitching at $\frac{1}{4}$ -in. intervals can be run up and down to represent seams. On the fore-and-aft sails these rows will be parallel to the after leeches (edges), and on the square sails, vertical. A narrow hem is sewn all around.

Except along the top edges, a thin brown cord is stitched to the extreme edges. To port on the fore-and-aft sails and abaft on the square sails, loops are formed in these cords at the corners to make clews. Topsails and trysails have rows of reef points stitched on.


Trysails are laced to their gaffs, which are placed in position and held there by the throat and peak halyards (see drawing near end of article). Their forward leeches are stitched to the mast bands at $\frac{1}{2}$ -in. intervals. The sheets are single blocks at the clews with cords leading to cleats in the deck. They may have a brail on each side to blocks at the jaws. The vangs





Main topsail and topgallant sail and their stunsails, looking forward. The forward side of the main topsail and one stunsail is sketched at the right



Two anchors of the iron-stock pattern are required. They may either be bought or made



Square sails, flags, and boats are shown at the right. Below, a jib with essential rigging



By Capt.
E. ARMITAGE
McCANN



The realistic effect of the sails is enhanced by running even rows of stitching up and down to represent seams in the canvas



go from near the gaff end to cleats in the bulwarks. The original ship had bonnets to these sails, which were cloths laced to their lower edges, but I omitted them on the model.

Spanker is similar to the trysails except that the sheet reeves through a hole in the boom end and belays to a cleat on the boom (see the detail drawing of the boom in the June issue), and there are two brails. The boom sheet has a double block, and there is a single block bolted to the deck on the midship line; and the ends of the tackle belay to cleats in the deck. There are also topping lifts from the boom end on either side, through blocks under the trestle-trees, and to the deck with a single-block tackle.

Gaff topsail is stitched to six mast hoops about 5/16 in. apart. It has a halyard with two single blocks. The sheet goes through a hole in the gaff, through a block at the jaws, and down. The tack leads down to windward.


Jibs are stitched to their rings on the stays and have two single-block halyards to the mastheads and leading down abaft to the pinrails. The downhauls are thin cords from the head through a block on the stay at the boom, and then to the knight-head belaying pins.

The fore-topsail sheet is a block strapped to the clew; the standing part goes to a ring in the forecandle deck, and the hauling part to the pinrail. The jib sheets are double with long pen-nants and single blocks. The lee sheets are drawn tight; the others hang slack.

Topsails. The head is hitched to the jackstay. The clew lines (two small single blocks) are rove off; the topgallant sheets are rove; three small blocks or beads are fastened to the jackstay on each side, and the yard is set in position. The chain (Continued on page 97)

Try to visualize the "Alabama" as a real ship with sailors aboard; it will help you keep the details properly scaled

The finished model. Captain McCann set the yards as if the wind were quartering



Last lines of the article, written just before Captain McCann died


That would appear to be all
and I think you will agree that you
have by now a very good looking
& interesting model ship.
E. Armitage McCann

Decorative Baskets

WOVEN FROM THIN WOODEN STRIPS



A sewing basket and cover of white pine. The darker parts are stained, but the weaving strips are natural



Suggested dimensions for a basket. At left, using the template to adjust cutting tool at angle required for making grooves in upper ring

The upper ring of the basket and the bottom disk can be turned from one piece because of the slant of the sides



By **HOWARD R. HEYDORF**

ATTRACTIVE baskets may be woven from wooden strips with little difficulty by any home worker who owns a power saw and a lathe. The finished pieces may be used to hold sewing materials or fruit or for purely decorative purposes.

Although any kind of wood may be used, the writer prefers white pine, which may be stained to produce the contrasting effect. This material is light, easily worked, and unequaled for the weaving strips, which must be very pliable.

The disk for the bottom, the upper ring, and the ring for the top are turned to shape on the lathe. In cutting the grooves for the uprights, a template is needed, the shape of which is shown in the drawing. A small three-cornered file, ground to form a cutting tool, may be used in making the grooves. These turnings are carefully sanded and may be stained if desired.


The upright strips are $\frac{5}{8}$ in. wide and the thickness of the (Continued on page 96)



A piece of wood in the miter gauge is used to adjust thickness of strips when sawing them. Left, the upright strips are set in a grooved block while being cut off to the right length



The upright strips are glued into grooves in the bottom disk. After each weaving strip has been inserted, it is pressed firmly downward as at left



Better SHOP Methods

Difficult Repairs Made by Brazing



Hopeless as the job looks, it was cheaper to repair this cast-iron cap by brazing rather than form a substitute out of sheet metal. All the broken edges were ground clean and beveled before the work was started


be brazed. The coating of copper often helps make the bronze adhere to the iron.—W. C. CHENEY.

This is the last of a series of three articles on oxyacetylene brazing.


Improved Grinder Trues Chuck Jaws

EVENTUALLY the jaws of every three-jawed lathe chuck become so worn as to be unsuitable for really accurate work. To restore their precision, a tool may quickly be improvised as shown below. A small grinding wheel ($\frac{1}{2}$ or $\frac{3}{4}$ in.) with a shank is mounted in the end of a 4-in. shaft made from $\frac{1}{2}$ -in. polished shafting. The shaft is fitted in a bronze sleeve about 2 in. long. It may be necessary to run in the bearing with valve-grinding compound. Drill an oil hole, solder the sleeve to a lathe tool shank, and pin a 1-in. pulley to the shaft.

Set up the chuck jaws on a small, thin section of accurately round steel shafting to hold them in position while being ground. The wheel can be driven by a $\frac{1}{4}$ -h.p. motor, and use a long round belt to facilitate the operation. Run the lathe opposite to the direction of the grinding wheel, and move the grinder back and forth inside the jaws, taking light cuts. Then remove the piece of steel in the rear and grind down any projecting part of the jaws that could not be reached before.—W. WALDEMAR.



Simple tool-post grinder for restoring accuracy of chucks. It is also used for truing lathe centers



This deflector for an air-conditioning unit saved a week's wait for a cast-iron factory replacement


OXYACETYLENE brazing is unsurpassed for certain types of repair work. For example, a cast-iron deflector in an air-conditioning unit had broken and fallen into the mechanism, doing other damage. It was replaced by an unbreakable piece made by brazing a piece of $\frac{1}{16}$ -in. sheet iron to a mild steel slab $\frac{1}{2}$ in. thick.

The thin section was blocked up to the proper height, and the torch played on the thick section until it was red-hot. The flame was then moved so it partly covered the thin sheet. The filler rod was kept in the flame, and just as the sheet turned red, the rod was melted into the joint. Considerable flux was used to keep the metal from scaling.

the edges were beveled to about 45 deg. With the help of some sheet asbestos to support the pieces from the underside, the parts were set in place and then heated until the bright parts of the iron were just changing color. The broken parts were next brought to a dull red, and the flux and rod applied. Since the iron was fine grained and of good quality, the bronze spread over the parts in an even coat. The cap was finally smoothed on a grinding wheel.

Beginners are likely to overheat cast iron, and the bronze will then merely roll around. The only thing to do if this happens is to let it cool, grind the surface clean, and start over.

If the brazing is to be done on the surface of the iron and all the dirt and grease have been cleaned off, it is not necessary to grind or chip the surface. Sometimes, when the iron is coarse grained, it helps to peen the surface with many light blows until it takes on a polish. If the iron still refuses to take the bronze, clean it off bright and rub wet blue-vitriol crystals on the part to



Three-Jaw Chuck and Level Used for Simple Indexing

WHEN holes have to be drilled through a shaft accurately at right angles to each other, the indexing can be done with a three-jaw lathe chuck and a machinist's level.


For example, to divide into thirds, chuck jaw No. 1 is leveled at the front of the chuck; No. 2 is also leveled at the front, and then No. 3. In dividing into four, six, eight, or twelve parts, it is necessary to level one or more jaws more than once, the chuck being turned half around and realigned with the aid of the same jaw. The level is used in as many positions as necessary—as a level, as a plumb, or at 45 deg. The scribing may be done with a pointed tool moved along by the carriage.—G. F. LAMPKIN.

Heavy-Duty Mounting for a Shop Anvil

FOR fifteen years the mounting illustrated has supported a 185-lb. anvil and withstood the hardest possible service.

The bottom framework was welded from eight pieces of 1½-in. angle iron. In this frame were placed three 6 by 12-in. wood blocks 20 in. long, ends up. An angle-iron frame was then made to fit over the top of the blocks and, in turn, welded to the four upright angles of the bottom framework. These last welds have been designated by drawing white lines across the angles. In making them, a large tip must be used and the work done quickly; then no serious burning of the wood blocks will result.

The anvil is fastened to the wood blocks with two long ½-in. iron U-bolts. These cross each other and are placed diagonally through the blocks after holes are drilled as indicated by the dotted lines in the drawing at the right. The nuts were kept drawn up tight until the base of the anvil was firmly seated, after which they required no further attention, except for an occasional checking.—W. C.





The anvil is supported on heavy blocks of wood set in a welded frame of angle irons

Roller on Drawing Board Saves Back Strain

IF ANY considerable amount of large-scale drafting has to be done, such as is required in the preparation of full-size cabinet or furniture drawings, large shop layouts, and the like, you can save yourself considerable back strain by using the device illustrated. It makes it unnecessary to keep away from the edge of the board to prevent the drawing from being creased. The extra paper is slipped between the 1-in. wooden dowel and the edge of the board, and you can lean comfortably against the rod while drawing.

The dowel is held to the boards by two window-shade brackets cut down to fit the thickness of the drawing board and screwed into a metal core eye, which pre-

vents wearing holes in the edge when attaching or removing the device from the board as may be desired by the draftsman.—JAMES F. SCHINDLER.



Power Hack-Saw Blades Given Longer Life

POWER hack-saw blades can be made to last longer by distributing the wear evenly along the blade. In the case of the usual type of power hack saw, which has a set stroke, this can be done by placing five plywood blocks ½ in. thick in the saw vise. With these blocks the work can be adjusted so the wear will be equalized.



Multiple Tool Holder Speeds Lathe Work

THREE or more cuts may be made with one set-up by using the homemade lathe tool holder illustrated. For example, you can cut threads, inside and out, shoulder an adjusting collar, and cut it off, or face, chamfer, and taper-bore a part. Used in combination with the compound of the slide rest (where this will not conflict with the setting of the other cutters), it is possible to cut tapers with the same set-up.


The size of the plate will, of course, be governed by the size of the lathe. The one shown was made for a 10-in. lathe, and is 6 by 6½ by ¾ in. It must be stiff enough to avoid any chatter. The arrangement of the slots is optional, and the other slots or holes for the tool-post screw may be added if found desirable.

Square cold-rolled stock was used for the tool posts, to support the cutters throughout their entire length, and socket-head cap screws for their toughness and durability.—R. G. BULLARD.

Timely Aids for Motorists


Paste Finds Gas-Line Leaks

TINY seam leaks in the oil or gas line of a car, although they are negligible as far as wasted fuel is concerned, often disturb the correct functioning of the gasoline or oil system. The minute leaks are usually difficult to locate, but they invariably show up when the following method is employed. Wipe a suspected line with a clean cloth and then apply a mixture of lime and water, or flour and water, with the aid of a soft brush. This will dry almost immediately and a greenish-brown stain will form at points where there are small leaks. Once these are located, it is an easy matter to mend them by taping or soldering.—A.H.W.



Leaks show up quickly when flour paste is brushed on a gas or oil pipe

Dry Ice At Ventilator Cools Closed Car



Tied under the ventilator, dry ice wrapped in paper cools fresh air entering the car



WHEN extreme summer heat makes your next long automobile drive too uncomfortable, stop at a drug store or roadside refreshment stand, buy a chunk of dry ice, and have it wrapped in heavy paper. Close all the windows of the car, open a cowl ventilator, and then suspend the dry ice just below and in back of this opening. Then turn back the paper covering. Air rushing through the ventilator and over the ice as you drive along will quickly cool the entire car. Because the dry ice vaporizes without melting, there will be no liquid drippings to spot enamel or upholstery. Be careful not to handle the ice itself, as your fingers might freeze fast to it and cause you some trouble and discomfort before you got them loose.—W.B.

Disks Drive out Bushings

TO REMOVE spindle bushings quickly, cut a half-inch disk from a steel rod slightly smaller in diameter than the bushing. Saw this in two and drop the halves inside the spindle, maneuvering them with a wire until they lie flat. Then, by inserting a bolt or punch against the disk halves, the bushing can easily be knocked out with a hammer.—W.H.A.




Cutting the small disk in half allows its two parts to pass one bushing so that the other can be driven out



Rubber Hose Holds Pliers Open

WHEN working with pliers in cramped or awkward spots around a car, fit a section of small-size rubber hose over the handles, as pictured above. The hose will then spring the plier jaws apart for a fresh hold whenever you loosen your grip on the handles. Incidentally, the hose will also serve to insulate the pliers when you are doing electrical work, either on your car or on the lighting circuit of the house.—F. C.




How the relay-operated warning lamp is wired into the tail-light circuit

Dash Light Warns of Burned-Out Tail Lamp

IMMEDIATE warning of a burned-out tail-light bulb is given to the motorist who rigs up the simple electrical circuit shown in the diagram above. A relay connected in series with the tail light is energized as long as the bulb continues to function. If it goes out, however, the relay magnet is de-energized, releasing an armature which is drawn up by a spring to make contact and light the warning bulb on the dash.—D.C.L.

Auto Clock Registers Driving Time on Trips

BY CONNECTING the self-starting electric clock in my car to the gasoline-gauge lead on the ignition switch, I can use it as a fairly accurate indicator of total driving time on cross-country trips, since the clock starts when the engine does and stops only a few minutes after the motor is switched off. A switch, wired as shown below, allows the clock to be used as a conventional timepiece.—J.D.D.



To show driving time, the clock is wired to ignition switch which turns it off and on

YOU CAN UNCOVER THE



Secrets of Photography

WITH YOUR
MICROSCOPE



Natural-color film transparencies are excellent microscope subjects. The dye images are easily studied

Right, film-negative emulsion showing "reticulation" caused by sudden cooling while film was wet. Below, how film developed with ordinary chemicals compares with that processed in special fine-grain solutions and with positive movie film



PHOTOGRAPHY and microscopy often travel hand in hand, largely because the making of pictures through the microscope is a fascinating and useful activity. But there is another way in which the microscope and the camera can work together. Remember, the microscope was always a "candid" instrument. By using it as a kind of photographic accessory, you can draw on its power to make little things look big, and discover the hidden secrets of film, developers, and other materials of picture making.

You may be a camera bug to whom there is nothing more thrilling than running down some obscure trouble in a miniature-camera film. And again, you may not care a whoop about picture making as a hobby. But if you are a serious microscope enthusiast, sooner or later you will want to make photomicrographs. And you will produce better results if you first do a little exploring with your microscope of some of the important phases of photography. Besides, you'll find it a lot of fun.

Illustrated magazines are using natural-color photographs in ever-increas-

By MORTON C. WALLING

ing numbers, both on the covers and inside. Some of these pictures fill almost a whole page. But, did you know that many, perhaps most of them, were reproduced from transparencies, that is, transparent colored films, measuring only about one by one and a half inches? Such enormous enlargement of tiny color transparencies without loss of detail is possible because the image is composed of dyes rather than grains of metallic silver. In other words, the image is practically grainless.

If you can obtain a color picture on 35-mm. film, the size usually employed, you can have a lot of fun examining it

with your microscope. At fifty or so diameters, the detail remains surprisingly sharp and distinct, and with your microscope you can read obscure signs and observe other things that are difficult to see even when the picture is projected on a screen in the usual manner.

Photographers seem to worry about grain more than anything else, particularly if they are users of miniature cameras. Grain, in this case, refers to the particles of silver, or clumps of particles, forming a photographic image. Because of their small size and the necessity of subsequent enlargement to produce a useful print, min-

lature-camera negatives must be fine-grained. Various developers have been devised to keep the grain size down, although grain never is entirely lacking. The photographer who has a microscope can keep tab on the grain size of his negatives without the necessity or expense of making prints from them. All he has to do is clamp a bit of film on the microscope stage, with or without a glass slide to help support it, and examine the silver image at magnifications of 100 diameters and up. Only for extremely close study, such as study of grain shape, are powers as high as 1,000 diameters required.


In this way, the camera enthusiast can compare the grain produced by various developers, and select the one that suits his purposes best. He also can compare different films on the basis of grain size, and discover for himself the fact that positive motion-picture film developed in a coarse-grain developer usually has a finer grain than fast, panchromatic film processed in a fine-grain formula!

Sooner or later, every photographer, particularly the miniature fan, bumps squarely against a film "disease" known as reticulation. He will find that a prized film has a dull surface that, on close examination with the naked eye, looks somewhat like textured leather. When a print is attempted, the picture is found to be overlaid with a network of fine lines. Reticulation is most common in warm weather. Under the microscope, the emulsion (gelatin coating containing the silver salts before development, and the metallic silver image afterwards) is seen to be broken up much like the cracked mud on the bottom of a dried-up pond.

Careful examination at moderate power sometimes shows that the cracks

are in only one layer of a double-coated film. The film frequently looks as if it were marked with innumerable, tiny folds forming a close network, instead of cracks. Care must be taken in making the diagnosis, for merely by shifting the microscope focus a trifle, reticulation cracks, which are lighter than the surrounding emulsion, can be made to change into dark lines that look like tiny ridges or folds. Such is the fickleness of light! Reticulation can be prevented by keeping the temperature of all solutions and the wash water the same—sixty-five to seventy degrees Fahrenheit.

A stunt that will provide considerable entertainment for the microscopist-photographer is the observation of film development through the microscope. Cut a small piece of film and lay it on a slide. Cover it with a clean cover glass, and focus your microscope on the film emulsion. With a pipette or medicine dropper, place a small quantity of dilute developer at the edge of the cover glass. Capillary attraction will draw it across the film, wetting the emulsion. Watch carefully all the time through the eyepiece, for development will begin quickly and proceed




By placing some dilute developer on a piece of film on a slide, you can watch the developing process through your microscope

rapidly. Thus you can actually see the basic chemical reaction of photography—the transformation of silver bromide particles into tiny grains of metallic silver which, because of its finely divided state, is black.

A very useful stunt is to employ the lowest power of your microscope to examine the *(Continued on page 100)*




At the left, a microphotograph, or tiny photograph, made on a glass lantern-slide plate is being mounted on a microscope slide. Below, solutions of photographic chemicals are placed on slides to evaporate, forming beautiful crystal patterns



For making microphotographs, a microscope is substituted for the lens of a photographic enlarger. A hand lens helps to focus the image upon the film

Cleaner Air To



How smoke is eliminated electrically in a factory chimney is demonstrated by the easy experiment illustrated at the left

This time you will be unable to smell the onion. You can substitute other odorous objects for the slice of onion, to see whether the charcoal will work as well with them. In industry, practical use is made of the way charcoal clings to the impurities that it abstracts from the air, for the profitable recovery of solvents that would otherwise be wasted.

Fumes and metallic dusts, belching from the stacks of smelters, once destroyed all vegetation for miles around. Now they have been conquered by an electrical process that precipitates or settles the smoke before the hot gases leave the chimney. On a small scale, you can reproduce this remarkable "Cottrell process," as it is named after its inventor, in your home laboratory.

To represent the chimney from which smoke is to be precipitated electrically, mount a glass tube about three quarters of an inch in diameter and a foot or more in length in an upright position. Run a thin piece of copper wire—say, No. 30 B. & S. gauge—up through the tube and back down the outer side, twisting it together at the bottom to make a closed loop. Make a second loop in the same fashion, at the opposite side of the vertical tube. These loops will serve as electrodes, and should not touch each other at any point. Connect them to any convenient source of high-voltage electricity. Ordinary house current will not do, but you may use an automobile spark coil, a laboratory induction coil, or a step-up transformer such as a neon-sign transformer operating from 110-volt alternating current. To avoid a shock, take care not to touch the electrodes while the current is on.

Hold a stick of burning punk or an ignited cone of incense beneath the tube, so that the smoke will rise through it. With the current off, the smoke will

"MONOXIDE Kills Two in Garage." "Farmers Protest Ruin of Crops by Smelter Fumes."

"Solvent Vapors Fell Three." Newspaper headlines like these proclaim the constant menace of polluted air to life, health, and property. Beneath much smaller headlines you may also read, from time to time, how chemists are combating the perils of noxious gases, smoke, and dust in the atmosphere—and sometimes eliminating them completely. Some of the means that have been found effective for purifying the air, and for warning when it is unfit to breathe, will be interesting to try out in your own home laboratory.

The remarkable power of finely divided charcoal to "adsorb" or remove impurities in the air affords a striking experiment. Because of this property of charcoal, it is one of the principal ingredients in the contents of canisters of wartime masks for use against poison gases. To test its effec-



tiveness in your laboratory, the odor of an onion will take the place of the gas.

Suspend a slice of onion in a side-necked test tube, and arrange to pass a slow current of air past it. This may be done by letting water flow from a full gallon jug, through a siphon, to an empty gallon jug at a lower level. This drives air from the empty jug, through suitably arranged tubing, into the side-necked test tube, where it bubbles through water in the bottom of the tube. The water serves as a telltale device to aid in keeping the flow of air constant—say, one bubble a second.

Lead the escaping air from the side-necked test tube through a piece of glass tubing about half an inch in diameter and ten to twelve inches long, containing three plugs of absorbent cotton. Your nose will readily detect

the odor of the onion in the air issuing from the apparatus.

Now fill the space between the plugs of cotton with powdered charcoal, replace the tubing, and proceed as before.

Detecting Dust, Fumes, and Poisonous Gases in the Atmosphere, and Getting Rid of Them, Is One of the Jobs of Industrial Chemistry

By RAYMOND B. WAILES



Exhaled breath shows more carbon dioxide than the air

Breathe

HOME-LABORATORY TESTS EXPLAIN PURIFICATION METHODS


emerge from the upper end. Turn on the voltage, and the smoke will magically disappear. What happens is that the suspended particles composing the smoke become electrically charged and are attracted to the wires, removing themselves from the stream of heated air. In commercial applications, the precipitated particles then fall by gravity to a catch bin at the bottom of the flue. Not only is smoke abated, but valuable metallic dusts are recovered before they escape into the air. Cement and slate-milling plants have also found the process a boon for abolishing dust, and it has been applied for tar removal in gas manufacture.

Far more insidious and deadly than the most obnoxious smoke, however, is the poisonous vapor that miners know as "white damp," motorists and naval gunners as "monoxide," and chemists by its full name of carbon monoxide. Invisible and odorless, it strikes without warning. By a simple chemical test, however, its presence in the air may be detected.

Palladium chloride is the name of the substance to use, and the test with it for carbon monoxide is so sensitive that the smallest quantity you can buy of this rather expensive chemical will be sufficient. Dissolve an amount of palladium chloride about the size of a pin-head by heating it in five cubic centimeters, or approximately one and a half teaspoonfuls, of water. To test a flaskful of air for the presence of carbon monoxide, one cubic centimeter of this solution may be poured into the bottom of the flask.

Try waving a flask in the air, after inserting this amount of the palladium chloride solution, within six feet of the exhaust-pipe opening of a running automobile motor. Then cork the flask and await developments. A second flask containing a like amount of the solution may be exposed to ordinary air and corked for comparison.

After the first flask has stood for twenty-four hours, you should be



A simple chemical reaction detects carbon monoxide in a sample of air captured near an automobile exhaust, as seen at the right





able to observe a black film of palladium metal that has formed upon the liquid exposed to carbon monoxide. The liquid in the second flask will be devoid of such a film.

Now, as a confirming test, add to the first flask five cubic centimeters of a solution made by grinding five grams (about a teaspoonful) of ammonium molybdate in a mortar with 100 cubic centimeters (or a little less than half a glassful) of water. Then add 100 cubic centimeters of a hydrochloric acid solution made by mixing ten cubic centimeters of strong, chemically pure hydrochloric acid with ninety cubic centimeters of water. Let the flask stand for twenty-four hours more. The beautiful blue color that will appear within this time confirms the presence of carbon monoxide. It will not be pro-

duced when the contents of the second flask are treated in the same way.

By the means just described, air can be tested in any locality where contamination with carbon monoxide is suspected—from automobile exhausts, a defective heating plant, or any other source. For collecting such air samples, a flask may be fitted with a rubber bulb like that of a perfume atomizer, so that a few squeezes of the bulb will fill it with the air to be tested. The palladium chloride solution should always be made up freshly before use. The sensitive confirming test producing the blue coloration is a recently developed one, new even to professional chemists.

In contrast with deadly carbon monoxide, carbon dioxide gas is not ordinarily considered poisonous. This is the gas that makes *(Continued on page 92)*



This apparatus shows how wartime gas masks work, by removing onion odor from the air. Powdered charcoal "adsorbs" the pungent aroma

KNAPSACK



Two small packs—one worn in front, the other in back—house the complete earphone receiver

By ARTHUR C. MILLER

HAVE you ever wished for a small, light-weight radio that you could take with you on your summer bicycle jaunts or hikes into the woods? It was to fill this need that the author designed the compact knapsack receiver illustrated. Powered by its built-in battery supply, and needing no other antenna than its own specially designed frame aerial, this novel radio will enable the user to receive his favorite programs while he is walking along the country lanes, or pedaling his bicycle.


The knapsack receiver can be slipped on in a few seconds, being worn in much the same way as a life preserver. As

shown in the photographs, the outfit is divided into two sections. One half, which is worn in front, contains the receiver circuit and the power supply. The other half, worn flat against the back, houses the specially designed loop antenna.

In order to insure satisfactory reception when at a distance from local stations, and because of the low efficiency of the loop compared with ordinary ground and antenna, the knapsack receiver employs a sensitive five-tube untuned radio-frequency circuit. Because of their low battery consumption and small size, special midget tubes, which have been recently placed on the market, were used. Although designed primarily for use in the automatic ultra-midget transmitters that are attached to balloons for meteorological purposes, they make good receiver units. They operate on a single dry cell, and their low filament consumption makes it possible to design a receiver with a total "A" drain of only 300 milliamperes.

Although the circuit design calls for five tubes, by using a dual-purpose unit, the actual number of tubes is reduced to four. The RK43 tube provides two separate triodes. The tubes are mounted on a chassis measuring $1\frac{1}{4}$ by 8 in. Standard midget wafer sockets are used, but since their diameter is slightly more than $1\frac{1}{4}$ in., they must be cut down to the required diameter with a pair of strong shears in order to fit on the chassis.

To obtain the highest possible amplification from the two untuned radio-frequency stages, chokes with an iron core were selected. An 80 millihenry choke serves for the first stage, while a 125-millihenry unit is used in the second. It is necessary to use chokes of different values to prevent the two stages from oscillating.



The antenna pack, shown at the extreme left, consists of a wood frame supporting the loop aerial and a cloth cover to protect it from the dust and rain

RADIO for Cyclists and Hikers

lating and thus spoiling the reception.

Insulated mica fixed condensers were used throughout the entire receiver, even for the coupling condensers in the two audio-frequency stages. This was necessary to save space. Also, since it was out of the question to use a large air-spaced tuning condenser, one of the new ultra-midget insulated types was chosen instead.

The cabinet for the receiver circuit is constructed entirely of 1/16-in. aluminum, and consists of two parts, a back and a front so designed that one slides inside the other to form a completely inclosed cabinet measuring 1 3/8 by 8 by 9 1/4 in. in outside dimensions.

Only two controls are needed to operate the set, and these are mounted one above the other on the front of the cabinet as shown in the photographs. The upper knob operates the on-and-off switch and the 15,000-ohm potentiometer to control the oscillation of the first tube. The lower knob is for tuning to the various stations. On the right side of the chassis are the two insulated binding posts which serve as connections for the headphones. These headphones should be of the featherweight

type, weighing but a few ounces, thus enabling the user to wear them for long periods without fatigue.

Below the two binding posts are two rubber-insulated flexible leads connected to the small 1 1/2-volt "A" battery which is fastened by means of an elastic band to one of the leather shoulder straps. As shown in the photographs, the two midget forty-five-volt "B" batteries are held securely in place inside the cabinet by black elastic bands 1 in. wide. These bands can be attached to the aluminum panel with paper fasteners or pieces of stiff, light wire.


In the photograph showing the rear of the receiver circuit, three insulated

wires can be seen extending through the side of the cabinet. These are the antenna connections, and lead over one shoulder strap to the special loop antenna that forms the back pack. The antenna consists of twenty-one turns of No. 30 double-cotton-covered wire wound on a wood frame consisting of a 3/8 by 8 by 9 1/2-in. baseboard fitted with 1-in. corner posts to support the wire. The aerial should be tapped at the fifth turn; this smaller section serving as the equivalent of a tickler coil. To protect the antenna, a cloth cover should be made. This can be of any convenient waterproof material held in place with nails or short straps.



WHAT YOU NEED

- Volume control and switch, 15,000 ohms.
- Tuning condenser, wafer-type, .00036 mfd.
- Plate choke, iron-core, 80 mh.
- Plate choke, iron-core, 125 mh.
- Fixed condenser, mica, .0003 mfd.
- Fixed condensers, two, mica, .0005 mfd.
- Fixed condensers, two, mica, .01 mfd.
- Fixed condenser, mica, .004 mfd.
- Fixed resistor, 2 meg., 1/2 watt.
- Fixed resistor, 3 meg., 1/2 watt.
- Fixed resistors, two, 1/2 meg., 1/2 watt.
- Fixed resistor, 100,000 ohms, 1/2 watt.
- Fixed resistor, 50,000 ohms, 1/2 watt.

Miscellaneous: Tubes, wafer sockets, knobs, dials, two-piece cabinet, chassis, earphones, two forty-five-volt "B" batteries, one midget 1 1/2-volt cell, wire, solder, etc.




This rear view of the receiver panel shows how the circuit and power supply are arranged




Five-tube results are obtained with four tubes when connected as at left. Above, the socket diagram

New Ideas for Radio Fans




Fastened on your bed, this combination radio and reading lamp forms a convenient bedroom accessory



WITH its illuminated dial facing down for convenience, a novel radio designed to be fastened on the head of a bed also serves as a convenient reading lamp. The compact and efficient receiver consists of a metal-tube circuit covering both the broadcast and short-wave bands and operating on either alternating or direct current. Two small frosted bulbs on either side of the decorative cabinet provide the necessary light for reading. Metal hooks hold the unit in place on the bed.

Soldering-Iron Stand Prevents Overheating



HOLDING an electric soldering iron at a uniform working temperature during continued use, an automatic stand protects the iron's tip from damage caused by continued overheating. Placing the iron in a groove in the stand, as illustrated, automatically switches off the full voltage and applies a reduced, "idling" voltage from a built-in step-down transformer.




Tiny New Electrolytic

SMALLER than a package of mints, a new electrolytic condenser is now available in a wide variety of capacities from four to forty microfarads, and in working voltages ranging from 100 to 450. Despite its small size, the condenser is sealed in a metal can and protected by a strong paper jacket. Long leads support the unit.

All-Wave Antenna Is Packed in Handy Kit

COMPLETE even to insulators, a handy antenna kit contains all the necessary parts for an efficient, all-wave antenna for amateurs. It is said to reduce man-made interference effectively on all wave bands and requires no complicated antenna rigging. Parts included in the kit are magnetic-core antenna and receiver-coupling transformers, antenna, ground, and lead wires, and a ground clamp.



All the necessary parts are included in the all-wave antenna kit

Waterproof Condenser Is Sealed with Glass

SO resistant to moisture that it can be even placed in a glass of water without injury, a unique fixed condenser, shown undergoing such a test at the left, is sealed within a glass tube by means of a special compound that in itself cannot be penetrated by water. The permanent seal eliminates the possibility of the condenser being damaged by moisture in the atmosphere, a frequent cause of condenser failure.



Transformer Has Adjustable Taps

MOVING four jacks from hole to hole in the panel of a transformer designed for small radio transmitters allows the current supply to be varied to give a range of voltages. The units are available for use by amateurs either as modulation or as driver transformers.

Pocket Folder Holds Parts for Making Tube Adapters

TUBE-BASE adapters for any tube can be quickly assembled from the parts contained in a handy pocket kit now available. By installing individual prong contacts in the holes of the adapter designed for the tube in question, any arrangement of connections can be made through the base prongs to connect earphones, a phonograph pick-up, or other accessory.





BUSINESS GIRL - 1938 MODEL - Office manager Olive Tucker keeps disarmingly calm despite nerve-nagging phones, buzzers, interviews. "If anyone needs healthy nerves, I do," Miss Tucker smiles. "That's one reason why I smoke Camels. They

never get my nerves upset." Later—much later—Miss Tucker skips to the roof-top gym for a quick work-out. Next—shower—rub—a Camel—and she's off again! Tired? Miss Tucker's answer: "Camels give my energy a refreshing 'lift.'"

Cigarettes may *look* alike—but what an appealing difference there is in Camels!

As a smoker, you'll be interested to read what Miss Tucker, successful young office manager, said to Miss MacGregor about the difference between Camels and other cigarettes (at right).

"Olive, do you always serve Camels because you feel that there's a big difference between Camels and other cigarettes?"



THERE ARE LOTS of Camels around Miss Tucker's living room. Miss Tucker says: "Camels are the favorite with my guests and are delightful for topping off a meal. I smoke Camels 'for digestion's sake.'"

"I'm very glad you've brought that question up, Helen. I've tried many kinds of cigarettes, and I'm amazed at how *different* Camels are. Camels are extra-mild—they never bother my throat. And Camels taste good, yet never leave that 'cigaretty' after-taste. In so many ways, Camels *agree* with me."

WELKER COCHRAN, who has won many championships at billiards, says about his choice among cigarettes: "Camels give me *real* smoking pleasure. Under the strain of a championship match, Camels never make me feel jittery or unsure of my 'touch.' 'I'd walk a mile for a Camel' too!"



Camels are a matchless blend of finer, **MORE EXPENSIVE TOBACCOS**—Turkish and Domestic

THEY ARE THE LARGEST-SELLING CIGARETTE IN AMERICA

Copyright, 1938, R. J. Reynolds Tobacco Company, Winston-Salem, N. C.

ONE SMOKER TELLS ANOTHER

"CAMELS AGREE WITH ME!"

"You bet Camel is our choice of cigarettes," say these tobacco planters—and they *know* tobacco because they *grow* it!



Mr. George Crumbaugh, well-known planter, had his best tobacco crop last year. He says: "Camel bought the choice lots—paid more than I ever got before. Camel's the cigarette I smoke myself. Fact is, most planters favor Camels."



"I know the tobacco in various cigarettes," says Mr. Reckham Wright, 19 years a grower. "Camel got my choice grades last year—and many years back. I know Camels are made from **MORE EXPENSIVE TOBACCOS**."



Last year, Mr. Walter Devine says, his tobacco brought highest prices. "Camel took my best lots," he says. "Other planters also got top prices from Camel for choice grades. I'm partial to Camels. Most growers here are too."

YOU CAN DEPEND ON CHAMPIONS



FOR CHAMPIONSHIP ENGINE PERFORMANCE

THE ITALIAN 1000 Mile Race pictured above, the most gruelling of all European road races, is held over all kinds of highways, and this year, as for many years past, the winner, and most cars, were Champion-equipped.

Engines equipped with Champion Spark Plugs consistently, for the last fourteen years, have won the great majority of all races, and record-breaking events, the world over.

It simply and positively demonstrates that Champion Spark Plugs make every engine perform better—give championship performance.

Champion research, engineering and manufacturing facilities are not even approached by others in the spark plug field. Better spark plug performance comes from better and highly specialized engineering, exclusive developments and processes. For twenty-seven years Champion has devoted all of its resources solely to spark plugs. This is why Champion is the

world's largest exclusive spark plug manufacturer.

Insist on Champions for your car because you can depend on them to insure the kind of ignition that makes championship engine performance.


MODEL BUILDERS— ATTENTION!

ACTUAL SIZE
V PLUG



V-3/8", 24 Thread
V-2 1/8", 32 Thread
65c

Specially designed for model gas engines giving the same dependable performance as regular Champions. Absolutely gas-tight, alloy needle point electrode, one-piece construction. If not available through your dealer, write Champion Spark Plug Company, 901 Upton Avenue, Toledo, Ohio.



Bringing Out Details in Poor Negatives

A PHOTOGRAPHIC print that is too dark in some part because the original scene was unevenly lighted can often be corrected or at least greatly improved by using a hand printing frame and holding it at an angle to a lamp, as illustrated above. The two prints reproduced below, much reduced in size, show the remarkable improvement that can be made with this simple procedure.

If the negative is darkest at one end, tilt the printing frame at an angle of about 45 deg., with the thin part of the negative farther from the light. The distance from the light may vary from 1 in. for a very dark spot to a normal distance for negatives that are less unevenly graduated.

When there is a dark spot in the center, as sometimes happens, hold the frame with this spot about 1 in. from the center of the light and expose very briefly.

By this method, details will appear in the print that are entirely lacking when the normal printing procedure is used.—O.R.S.

A passable print made from a poor negative by holding the printing frame at an angle



When printed in a normal manner, the same negative gave the darkly shaded picture at the left

CHECK AND CLEAN SPARK PLUGS WHEN YOU CHANGE OIL

P. R. Nalder, secretary of the Coulee Dam (Wash.) Homeworkshop Club, at his lathe. Note how he carefully saves odd pieces of wood in racks nearby

The Guild Offers You a Hearty Welcome

... IF YOU LIKE TO MAKE THINGS, THAT'S ENOUGH.
YOU DON'T NEED AN ELABORATE WORKSHOP



Official Magazine
POPULAR SCIENCE
MONTHLY

WHAT'S your home workshop like? Is it the kitchen table on which you build ship models, a bench in the garage where home repairs are made, or perhaps an elaborately equipped shop in the basement for constructing almost anything? No matter what the equipment may be, the National Homeworkshop Guild would like to have you as a member, if you are at least sixteen years old.

You can, of course, be a lone wolf and keep your hobby to yourself, but thousands of home workshop enthusiasts in the United States now realize


that their enjoyment increases greatly when they belong to home workshop clubs. Pictured on this page and on page 98 are a few Guild members and their shops. If they could speak to you, they would tell you how much more valuable their home workshops became when they began to associate with others interested in making things.

And your craftsmanship improves, too. Exhibitions held during the past few months provide a striking example of what Guild members are now able to accomplish. Ship models, inlaid pictures, metal silhouettes, pieces of furniture—nothing is too difficult or elaborate for some Guildcrafters to construct.



Fourteen members of the Edison Club, *Chicago, Ill.*, won prizes in the annual contest and exhibition. The winning projects and their owners follow: ship model *Preston*, C. E. Knutson, Jr.; spinning wheel, L. Luetgert; lamp table, E. C. Groeschel; combination card table, Leo St. Jacques; marquetry panels, N. Clemens; steel silhouettes, L. L. Austin; twin end-table lamps, L. F. Holstein; pilot-wheel clock, J. H. Faulkner; inlay table, J. L. Williams; book ends, L. H. Juhnke; charcoal drawings, H. Conway; bowl and candlesticks, H. O. Sandberg; modern end table, J. J. Jensen; coffee table, D. G. Arnett. Norman Clemens has been elected president; O. L. Anderson, vice president; E. M. Dittmer, secretary-treasurer; Leo St. Jacques, librarian.

Approximately 1,200 persons attended the hobby show which the *Seattle (Wash.)* Homeworkshop Club held




The home workshop of J. T. Potts, a former president of the Jacksonville, Fla., club

in its club workshop for two days. First prize was won by W. H. Slayton for his walnut radio cabinet; second prize, G. A. Spaulding, carved end table; third prize, M. L. Eggleston, inlaid drawing table; honorable mention, R. D. Brownson, Talbot McGar, Harvey Hansen, and F. L. Strong. The club also held an exhibition in a department store in connection with a model display. Twenty-eight members joined recently. L. J. Larcom spoke on spray and varnish finishing.

Judges announced for the third annual display contest of the *LeRoy (N.Y.)* Homeworkshop Club are Louis W. Steuber, Jacob Fischer, Frank Kurtz, Frank Hall, Arch Creiger, and Henry Thomas. The committee consists of Richard Hutchinson, chairman, Robert H. Howard, Dr. R. L. Skinner, Paul Wirsing, Ernest Curtis, and H. L. Canfield. At a recent meeting L. R. Ferguson talked about dry ice.


Jack Wilcox gave a painting demonstration before the Town Hall Homeworkshop Club, *Ottawa, Ill.* W. E. Nye-land was elected librarian . . . A sailboat and several tents for a summer camp are being made by the St. James Workshop Club, *Montreal, P.Q., Canada.* Many of the members have taken up photography . . . A second club in the same city, (*Continued on page 98*)



Herman Moodt, of the Lakeside Homeworkshop Club, owns the best equipped shop in Muskegon, Mich., perhaps in the entire Guild. It is set up in his basement and cost \$1,800

Nonslip Tilt-Top Head

FOR CAMERA TRIPOD




Details of parts for the tilting head. It is easy to adjust, yet holds a camera firmly

Below, the completed head attached to the tripod. Note the very durable construction



Boring the body and, right, the machined parts. The project is an interesting one for those who own a lathe



thread on the other. A template of thin brass, copper, or celluloid will have to be made to the exact radius of the finished ball. Just keep cutting the ball with a hand tool a little at a time until the template will fit in any position.

The locking handle is of steel. The cam is turned on

the end by throwing the rod off center in the four-jaw chuck. Polish with fine emery cloth. The plug for the bottom is tapped to take the tripod screw ($\frac{1}{4}$ -in.-20) and is held in the body by three No. 6-32 machine screws, countersunk. The little cup that locks against the ball should be turned so that it fits snugly around the ball. The round washer is $\frac{1}{8}$ -in. thick brass sheet, turned to diameter.—EARL ENSIGN.

PHOTOGRAPHERS who own a bench lathe will find the construction of this tilt-top tripod head a pleasant evening's diversion. The head is larger than commercial ones and will hold large cameras as well as miniatures very firmly.

The body is turned from round or hexagon brass and bored all the way through except for the last $\frac{1}{8}$ in. where the ball seat is formed. The tool is

ground to the correct radius of the ball before starting to bore. The outside is then cut down at that end so the wall is a full $\frac{1}{16}$ in. thick. Smooth the part nicely, round the corners with a fine file, remove it from the lathe, and file the slot in the side, which enables the camera to be held in a vertical as well as a horizontal position.

Make the head from brass rod with the ball on one end and a $\frac{1}{4}$ -in.-20


Adhesive Tape Lifts Glass

IF NEGATIVES are sandwiched between sheets of glass for projection printing, considerable time can be saved, and finger marks prevented, by attaching a small tab of adhesive tape to the upper glass. This affords a grip for raising the glass as illustrated.—K.L.R.



Clothes Dampener Washes Prints

HOME-BUILT washers for photographic prints often have such a strong stream of water that it causes occasional blisters and the breaking of the paper. If an ordinary five-cent perforated clothes dampener is attached to the water hose, it can be used to flush the prints gently and keep them in motion. Wired to a spring clothespin, the improvised washer can be clipped to the edge of a tray or tank.—W.K.



Eastman's

"Miniature"


Family



KODAK RETINA II... Choice of two extra-fast lenses—*anastigmat f.2.8* or *anastigmat f.2.0*. Compur-Rapid shutter (9 speeds, 1 to 1/500). Coupled coincidence-type range finder. Body shutter release. Double-exposure prevention device. Automatic exposure-count dial. Depth-of-focus scale. Kodak Retina II, *f.2.8*, \$115; Kodak Retina II, *f.2.0*, \$140. Prices include sportsman's field case.




KODAK BANTAM SPECIAL... Lens, Kodak Anastigmat EKTAR *f.2.0*, extra-fast, super-corrected. Shutter, Compur-Rapid, 9 speeds to 1/500 second. Built-in coupled range finder of the split-field military type finds the range and focuses in one operation. Film-centering device locks film accurately in position for each exposure. New low price, \$87.50, includes field case.



KODAK DUO SIX-20 (Series II)... The miniature that takes album-size pictures ($1\frac{5}{8} \times 2\frac{1}{4}$). Lens, the brilliant Kodak Anastigmat *f.3.5*. Shutter, 1/500-second Compur-Rapid. Eye-level finder frames action—makes it easy to follow. Body shutter release minimizes danger of camera movement. Bracket for Kodak Pocket Range Finder. Price, \$57.50.

KODAK RETINA I... the famous original Retina, now equipped with the new, ultra-precise Kodak Anastigmat EKTAR *f.3.5* lens. Shutter, 1/500 Compur-Rapid. Film-measuring mechanism. Exposure counter. Depth-of-focus scale. Enclosed direct-view finder. Special plunger release. Bracket for Kodak Pocket Range Finder. Price, \$57.50.



*Only EASTMAN
makes the KODAK*

LOAD WITH A WIDE RANGE OF BLACK-AND-WHITE FILM

Kodak Retina I and Kodak Retina II load with Kodak "SS," Panatomic, Super X, and Infra-Red Film; Kodak Bantam Special, with Kodak Panatomic and Super X; Kodak Duo Six-20, Series II, with Kodak Verichrome, "SS," and Panatomic.

ALSO LOAD WITH KODACHROME (FULL-COLOR) FILM

Kodak Retina I, Kodak Retina II, and Kodak Bantam Special also load with Kodachrome Film for gorgeous full-color transparencies. These may be viewed as they are, or mounted in slides for large-size projection with Kodaslide Projector. Your dealer will be glad to demonstrate for you Eastman's miniatures, and to show you examples of their brilliant work in both black-and-white and full-color Kodachrome. . . . Eastman Kodak Company, Rochester, N. Y.



KODASLIDE PROJECTOR...

Ideal means of projecting mounted Kodachrome transparencies. Built to precision standards. Yields big images of unsurpassed over-all clarity. With 8-foot cord, switch, plug, $4\frac{7}{8}$ -inch lens, \$48.50.

Unloading Miniature Camera Roll Film



IT MAKES anyone impatient to wait until the last shot is taken with a thirty-six exposure miniature camera. You can overcome this by cutting the roll approximately in half after about fifteen pictures. Go into a dark room, wind the film knob one extra turn, open the camera, and cut the film apart. Un-



Fasten the tongue to the unused film with cellulose tape, or splice it with cement

wind the used portion until you reach the long loading tongue and cut this off, together with an inch or so of full-width film. Put the used part of the film into a regular film can and seal edge with tape. Fasten the tongue end to the end of the unused film that projects from the cartridge. Care must be taken that the perforations match perfectly at the joint.—CARL FROEN.

Speeding up Your Film with Mercury Vapor

AMATEUR photographers who wish they had a camera with a faster lens may now gain the same results with their present camera by hypersensitizing their film. By a method recently developed, this process becomes cheap, simple, and sure. All that is required is a little mercury and a few wide-mouthed bottles.

Mercury hypersensitizing will increase the speed of any amateur film from 50 to 150 percent. With an average increase of 100 percent, your box

the inside of this should be given several coats of either shellac or varnish.

To treat a roll of film, put a few drops of the mercury in a cardboard pill box that has several small holes cut in the top. Place this box in the bottom of the jar and stand the roll of film upon it. Now put the cover on the jar, and seal it with several turns of opaque tape. Loosely wrapped film will be fully hypersensitized in about thirty-six hours at ordinary room temperature. Tightly wrapped film should be left from six to eight days. By providing a number of containers, each labeled with type of film and date, the processing may be staggered so that the required number of rolls will be ready just when you want them. The effects of the process last in full force for about three weeks. Development should be carried through in the ordinary way.—K. M. S.



A few drops of mercury are placed in a cardboard pill box which has holes in the top. Then the pill box and film are sealed tightly in a black-painted mayonnaise jar



camera with its F/11 lens can do the work of a camera with an F/8 lens using untreated film, while the F/2 lens of your minicam is boosted to F/1.4.

An amazing feature of the process is that film may be treated either before or after exposure, the greatest improvement in speed occurring when treated at the latter time. Another feature is that film may be treated in tightly wrapped rolls.

Large cold-cream jars or half-pint mayonnaise jars are excellent containers for the processing. To hypersensitize your film without loosening it on its spool, these jars may be used just as they are. For loose film, they should be given several coats of opaque paint on the outside. Be sure to cover every spot. If the cover of the jar is metal,

Improvised Sunshade for Folding Camera


A SUNSHADE for an ordinary cut-film or film-pack camera, when used in a horizontal position, can be provided by turning the wire view finder as shown below and laying the film slide across it.—PAT MACDONALD.



Tripod braced with pieces cut from a discarded radio condenser

Aluminum Plates Stiffen Light Wooden Tripod

LIGHT wooden camera tripods that vibrate excessively can be stiffened by fastening metal braces across the upper sections as shown. Aluminum plates taken from an old variable radio condenser are excellent for this purpose and add very little weight to the outfit.—MERLE TERRILL.



Enlarging Paper Held with Adhesive Tape

WHENEVER a photographic enlargement has to be made that requires the full area of the enlarging paper, it is difficult to hold the paper perfectly flat. Covering it with glass is not entirely satisfactory, as all the flaws in the glass are shadowed on the paper and sometimes a double image may be produced. A better method is to glue photographic tape with the adhesive side upward to an old drawing board or other suitable flat surface in the form of a rectangle large enough to enable the paper to be stuck down as shown. A gap of several inches is left at one corner so the paper may be lifted easily. No trace of adhesive remains on the back of the paper.

Eyedropper Used as Oiler

OUT-OF-THE-WAY bearings in typewriters and other small machinery can often be oiled more conveniently by using a small suction-type eyedropper than a conventional oil can.—E. T. ROBINSON.

Fishline Spider Keeps Tripod from Spreading

TO KEEP a camera tripod from doing a "split," nothing is more effective than a brace made from strong fishline and a few rubber bands. The line, which should be of the type intended for deep-sea fishing, especially if the tripod is a large one, is cut and tied so that it forms a spider having three equal segments of such length that they are stretched



Looped rubber bands pull the cords up out of the way when the tripod legs are folded


to a horizontal position when the tripod legs are spread normally apart. The ends are fastened to the tripod legs by means of small screw eyes or any other convenient method. Some tripods are equipped with loops to take such braces.

Loop rubber bands together until their total length is such that, when fastened between the center of the fish-line spider and the tripod-head screw or upper end of one of the legs, they will pull the line up out of the way when the tripod legs are folded together. The ends of the spider can be equipped with snap hooks, paper clips, or any device that will permit quick attachment or removal.—W. E. B.

Varnish Remover Cleans Clogged Sanders

OWNERS of belt and disk sanders often find the abrasive surface clogged with pitch and powder. This renders them useless long before the abrasive has worn off. I have found that applying prepared varnish remover will dissolve the gum or pitch, which may be removed easily with a stiff wire brush. This treatment has been used as often as four times on the same belt before discarding it.—DONALD R. FOSLER.

OL' JUDGE ROBBINS'



THE STORY OF SMOKING JOY

PRINCE ALBERT TASTES THE WAY IT SMELLS—**RICH BUT MILD.** AND THE **NO-BITE** PROCESS TAKES OUT RAWNESS

"MAKIN'S" SMOKERS
P.A. TWIRLS UP
QUICKER, SMOKES
MILDER, AROUND 70
SWELL "MAKIN'S"
SMOKES TO THE TIN

50 pipefuls of fragrant tobacco in every 2-oz. tin of Prince Albert

READ THIS GENEROUS OFFER

Smoke 20 fragrant pipefuls of Prince Albert. If you don't find it the mellowest, tastiest pipe tobacco you ever smoked, return the pocket tin with the rest of the tobacco in it to us at any time within a month from this date, and we will refund full purchase price, plus postage. (Signed) R. J. Reynolds Tobacco Co., Winston-Salem, N. C.

PRINCE ALBERT
THE NATIONAL JOY SMOKE

**"You've never
HEARD
anything like it"**



**THE NEW
Western Electric
HEARING AID**
Ortho-technic Model

**...built on new principles
...gives new hearing ease!**

With Western Electric's new Audiphone scientifically selected by Audiometric tests to meet your needs, you'll *hear clearly, easily again*. Men and women now using this new Ortho-technic Model say "you've never heard anything like it."

And you *haven't!* Built on entirely new principles in hearing aid design, this latest achievement of Bell Telephone Laboratories does things no previous hearing aid could do.

It enables you to hear clearly in group conversation—it will operate in any position—no "cut-off" when you lie down or recline. It greatly widens your hearing circle. It gives you natural tone, with either air or bone conduction receiver. It has greater power than any previous aid, yet its batteries last much longer.

You owe it to yourself to try this remarkable new Audiphone. Send the coupon today for full details.

GRAYBAR ELECTRIC CO., Graybar Bldg., New York.
Please send details on New Western Electric Audiphone
(Ortho-technic Model) and name of nearest dealer.

P.S. 36

Name.....

Address.....

City..... State.....

Punch Cuts Out Windows in Passenger Cars


IN MAKING the cardboard sides for model railway cars of the O0 and H0 gauges, much time may be saved by constructing a punch and die as illustrated. The die consists of two pieces of strap iron about 1 by 2 by $\frac{1}{8}$ in. with identical holes drilled and filed in them to the size of the windows. The hole must be the correct distance from the right outer edge of the iron to give the desired spacing between windows.

One of these pieces is set flush in the wooden block as indicated, with a hole below for the punchings. The other piece goes on top with a metal spacer between. The spacer is the same thickness as the cardboard and is placed to serve as a stop, so that each window will be the desired distance from the top of the car. Nails are added as guides.

The punch is filed from steel and must be a tight fit.

A small shoulder is left to keep the punch from going through the hole.

—W. D. SMITH.



How the punch and die are made and used

Abrasive on Screw Driver Prevents Slipping

IN LOOSENING a tight screw, the screw driver sometimes keeps slipping out of the slot and chewing up the slot. The next time this happens, try dipping the point of the screw driver into some emery or other abrasive powder. If no such powder is handy, dip the point in the grinding dust around your grinder or use ordinary kitchen cleanser.

Flat-Drying Process Paint for Finishing Models

POOR painting probably spoils more scale models than anything else. Amateurs often use high-gloss paints over a surface that has not been properly prepared with the result that every blemish shows distinctly and the whole looks like a cheap toy.

Anyone can now obtain a fine-looking flat finish on models by using what

is commonly called "process paint" or "silk-screen stencil paint." It brushes easily, dries flat, covers well, and is very durable. You will not find this in ordinary paint stores, but it may be purchased at any sign painters' supply house or from the larger nationally known paint stores, as well as by mail from certain specialty paint dealers. The price range is generally from \$1.25 to \$1.75 a quart.

Do not follow the directions on the can, because they are intended for silk-screen stencil work, but thin the paint approximately twenty-five percent with mineral spirits, painters' petroleum, or gasoline. It dries tack free in about thirty minutes, and is hard in from two to four hours.

Be sure to get flat-finish process paint, because it is also available in a gloss finish, lacquer finish, and synthetic enamel finish.—C. A. VOELCKEL.

Model Railway Materials

A HEAVY rubber band makes an excellent belt for transmitting power from one axle to the other in the power trucks of MU or interurban models. Small pulleys to fit the axles may be obtained from discarded drapery fixtures, where they are used to carry the cords for traverse draperies. With a little reaming, the pulleys can be made a press fit on the axles.

Serviceable worm-and-pinion sets for use in light models may be obtained from children's structural building sets or purchased direct from the manufacturers at much lower cost than the worm-and-gear sets usually used in models.

How To Free Tight Journals on Model Railway Trucks

TIGHT truck journals are sometimes a source of trouble to model railway engineers, but they may usually be remedied by holding the wheels against a rapidly moving belt. The high speed quickly loosens the bearings.—A. F.

Three Hints on Using Soldering Coppers

WHEN a considerable amount of solder has to be deposited on work that is more or less inaccessible, it pays to file a reservoir groove the full length of one of the faces of the soldering copper. Extend the groove right to the point, and tin it well.


Electricians who frequently have to solder wires in awkward overhead positions can save themselves trouble by using a bit with only one face and bevel tinned. It should be kept for this special purpose. The solder will not run all over as is the case where all four faces of the point are tinned.

Those who heat their soldering irons over charcoal, gas, or gasoline can remove the oxidation so the bit will heat more rapidly by dipping the copper while hot in a solution of $\frac{1}{2}$ oz. powdered sal ammoniac dissolved in 1 qt. water. Keep this in an earthenware jug or crock.



Simple Model Railway Loading Platforms


SCALED for "O" gauge model railway track, these loading platforms supplement the main passenger stations to form freight depots or train sheds. If necessary, the base and roof can be cut in the shape of an arc to fit around curved portions of the track, or several of the platforms may be placed between the tracks to create a terminal shed. In the latter case, extend the roofs so they touch to give the impression of a continuous roof, or use one large roof. Gray paint, sprinkled with sand while still wet, will imitate cement on the base and columns. Use green or brown paint on the roof.—C. ELMER BLACK.



Three views of a platform for "O" gauge, although length and width may be varied

Switch for Reversing a Model Locomotive

THIS reversing switch for model-railway use requires a piece of fiber with four roundhead screws (Fig. 2). The lever is cut from the same material and carries two roundhead screws (Fig. 1). A fairly stiff spring is used on the center bolt. The screw-heads on the lever must each contact two screws in the plate. The method of wiring is shown in Fig. 3. If the headlight is connected directly to the third-rail shoe when the switch is in midposition, trains can stand with the lights burning, and a flip of the lever 45 deg. will set the train in motion. If small screws are used, the switch will fit in a cab.—JAMES M. BOWLES.



NOW READY! At your Willard Dealer's A NEW BATTERY THAT LASTS 68% LONGER

Get the Protection of This New Heavy Duty Willard that...

...does all the things you've always wanted a battery to do—and keeps on doing them for 68% longer than the average of over 100 other brands, including all the best known makes!

...starts your motor over and over and over again—countless times—quickly—without fuss—and regardless of the weather!

...takes the strain of hard, continuous driving—day after day—without flinching.

...is a made-to-order power house to handle the extra demands of car radios, heaters, and other current-consuming devices.



7 OUTSTANDING FEATURES OF THE WILLARD "H-R"

- 1 Protected with the new-type Willard Thread Rubber Insulators that give the battery 68% longer life.
- 2 Reserve Capacity means longer life, plenty of power for radio or accessories.
- 3 Plates expertly designed, formed and processed to insure top performance.
- 4 Extra power for Winter starting—and superior resistance to summer heat.
- 5 Delivers high voltage to starter—saves gasoline, and oil dilution.
- 6 Handsome, new-style Hard-Rubber Container—tough and rugged.
- 7 Written guarantee and adjustment policy, backed up by 42,000 Willard Dealers from coast to coast.

This Willard "H-R" was developed after a 9-year study of 78,000 batteries driven over one billion miles. Its unusual performance is due to new developments in battery construction, exclusive with Willard. Most important single feature is a *new type* of Willard Thread Rubber Insulator that definitely increases battery life—and protects you against the sudden failures so often caused by "shorts" or buckled plates.

If you are one of the millions of car owners who will need a new battery this Fall, be sure to see the *new* "H-R". Its long life and low price mean true economy. Now on display at your Willard dealer's.

HERE'S WHY THE "H-R" WILL LAST 68% LONGER

No battery can last longer than its insulators. The positive and negative plates are like fighting roosters always trying to get at each other through the "fence" or insulator. If the plates wear a hole through an insulator and touch each other a "short" occurs and the battery goes dead immediately. This is the cause of many battery failures.

After years of research, Willard engineers have perfected a new insulator of cotton threads and latex. This new Thread Rubber is porous enough to permit fast chemical action between plates—yet tough enough to keep the plates apart until they wear out.

Combined with Willard's superior plate construction these Thread Rubber Insulators give the "H-R" top performance and a life 68% above the average of competing batteries.

WILLARD STORAGE BATTERY COMPANY • Cleveland • Dallas • Los Angeles • Toronto



THAT'S NOT "OLD FAITHFUL!" JUST A GUY WHO DIDN'T USE **SANI-FLUSH!**



A CLOGGED radiator may be the beginning of an expense account. The motor overheats. You lose power. Expensive repairs often result from a neglected radiator. Don't take a chance. You can keep radiators clean with SANI-FLUSH. Keep motors running cool and efficiently.

Just pour 10c worth of SANI-FLUSH in the cooling system of your car. (25c for the largest truck or tractor.) Follow directions on the can. Run the engine. Drain. Flush. Refill with clean water. It takes very few minutes and SANI-FLUSH removes rust, scale and sediment. It cannot injure motor or fittings. You'll find SANI-FLUSH in most bathrooms for cleaning toilet bowls. Sold by grocery, drug, hardware, and five-and-ten-cent stores. 25c and 10c sizes. The Hygienic Products Company, Canton, Ohio.

Sani-Flush *Safe* NOT CAUSTIC
KEEPS RADIATORS CLEAN

LeJay Electric Troller
LIGHTWEIGHT—CLEAN—SILENT

Ideal for boats or canoes because of its variable speed from maximum to just moving. So simple a child can operate yet strong and sturdy for general use. Operates 8-12 hours on good battery. Silent operation plus use of both hands for fishing and other features make it the perfect outboard. Free Details.

It's easy to build your own electric outboard from old auto generator. We show you how. Dims brings simplified plans and valuable catalog.

LEJAY MFG. CO., 523 LeJay Bldg. Minneapolis, Minn.

29.50

9" x 3" SOUTH BEND LATHE

New Low Terms
ONLY \$6.92 A MONTH
Ask for FREE Catalog

Write for details on this new 9" x 3" Workshop Precision Lathe—back geared, screw cutting. Made in 8 different drives, 4 bed lengths. 38 practical attachments available for use with this lathe. Weight 320 lbs., crated.

Ask for catalog 15K—sent Free, Postpaid.

\$85 LESS MOTOR DRIVE

SOUTH BEND LATHE WORKS
325 E. Madison St., South Bend, Indiana, U.S.A.

Homemade Flexible Shaft Does Fine Work



Chasing a silver ring with the unit, which is a homemade copy of a dentist's drill

THIS dentist's type flexible-shaft grinder is a useful tool for model making because it operates at high speed with little vibration. Small grinding wheels, sanding disks, and burrs may be obtained from a dental supply house, or your dentist will perhaps give you some of his discarded ones.


The writer has used the outfit illustrated for drilling, chasing, grinding, and polishing in connection with jewelry work; for grinding small dies; for carving, drilling, and other fine work on ship models, and as a tool-post grinder on a small lathe. Gunsmiths also would find such a unit valuable.

Materials. Small pin vise with chuck taking a $\frac{1}{8}$ -in. drill (maximum); 2 ft. of $\frac{1}{4}$ -in. flexible metal conduit; $\frac{3}{32}$ -in. flexible core from an auto speedometer shaft; brass rod.

Vise. Cut handle to desired length and ream out burr. Insert short length of steel rod in the chuck, tighten chuck, and center piece in lathe. Hold the hollow stub of the handle with the tail-stock center. Turn down shank and polish to turn in brass bearing at end of flexible conduit. Fit one end of cable snugly into hollow stub handle and "sweat" with solder.

If a ball-bearing unit is desired, obtain a used "hand piece" from a dental supply house and substitute it for the remodeled pin-vise assembly.


Fittings. Turn from round brass stock



The remodeled pin vise, the brass bearing, and brass collars for use at the motor end

a fitting to serve as a bearing for the finished chuck. Make outside any convenient size and shape to hold in your hand. Drill and ream one end to receive the chuck unit; drill the other end to receive about 1 in. of the conduit. Fit this brass piece over the conduit and solder.

Make brass collar for other end of conduit. Note that a short length of steel shaft is sweated to the tail end of the cable. This rod must not be too large to go through the chuck bearing, as the unit is assembled by feeding the




Chuck and cable before being inserted in housing. In center are some of the tools

cable in through the chuck end. Also make brass collar to fit over motor shaft and receive the projecting end of the steel rod.

Assembling. Rub the cable with graphite paste and assemble as shown. The motor used in the original is a $\frac{1}{10}$ -h.p. variable-speed motor with a maximum speed of 6,000 r.p.m., which was purchased secondhand for \$1.50. An alternative method is to chuck the driven end of the cable in your lathe. High speed is best for grinding operations.—C. K. FANKHAUSER.


Rubber Vacuum Cups Keep Pastry Board in Place



PASTRY boards and other articles that are to be used on smooth surfaces may be prevented from slipping by providing them with vacuum-cup feet, as shown. Each foot consists of three disks of rubber cut from an old inner tube and screwed to the board.


New Fisherman's Boat

(Continued from page 61)



Cross Section at Transom

Above is a diagram showing the relation of all parts at stern. The dotted lines indicate parts on the outside. Right, an inside view of side at the rowing seat




Side at Stations 5 and 6

seat may be made removable by notching the seat frames over a cleat screwed to the side frames.

The entire hull should be well sanded before the priming coat is put on and, after the priming coat is dry, all screw holes covered with putty. The hull should have at least two coats of marine enamel, or else flat paint covered with a coat of spar varnish. The deck, seats, and trim, including the sheer and fender molding, can be given a natural finish with two or more coats of spar varnish. To mark the water line, set the boat level on an even floor and mark around the hull 5 in. up from the floor.

The sheer and fender molding should be 3/4-in. hardwood screwed to the frames and battens with 1 1/4-in. No. 7 oval-head brass screws. A strip of 1/2-in. brass or aluminum should be used to protect the stem.

A fin about 3 in. deep by 6 in. long will be necessary to prevent skidding on turns if a motor of over 6 h.p. is to be used. The fin should be bolted to the keel between frames Nos. 4 and 5.



Assembly view looking down on hull at stern



Velvet

—the **MILDNESS**
of fine old
Kentucky Burley
aged in wood

—the **FLAVOR**
of pure maple
sugar for extra
good taste

Velvet packs easy in a pipe
Rolls smooth in a cigarette
Draws right in both

Better
Smoking
Tobacco

Copyright 1938, LIGGETT & MYERS TOBACCO CO.

**I'M TOPS IN
COMFORT!**



Keener, longer-lasting,
kind to the skin, Treet
Single-edge Blades are
uniformly good! 4
superb blades for 10c.

**4
FOR
10c**

**Treet
BLADES**

FIT GEM AND EVER-READY RAZORS

**New Catalog of
TRAILER
PARTS**

Axles, straight \$4 Drop center axle, \$7.50. Drop
center axle undercarriage, \$19.50, complete less tires.
Cable-controlled brakes, on axle, \$15 extra. Electric
brakes—prices on request. Send for FREE Catalog today.
SHAMROCK TRAILER PARTS
12317 Turner Detroit, Mich.

Print Your Own

CARDS, STATIONERY, ADVERTISING CARDS, CIRCULARS, FOLIOS ETC.
SAVE MONEY AND TIME! SOLD DIRECT FROM FACTORY ONLY.
JUNIOR OUTLET 50c. SENIOR OUTLET 75c. AND UP TO 90c. POPULAR
RAISED PRINTING. LIKE LITHOGRAPH, BUT FOR 1/10th the cost. A SHORT
TIME. EASY RULES. SENT FREE FOR FREE CATALOG.
OF OUTLETS AND ALL DETAILS...
KELSEY PRESSES 433 MI. HIDDEN CONN. CT.

**PROFIT
PRINTING** **EXCELSIOR**

When Writing Advertisers

Please Mention **POPULAR SCIENCE**

CHEMICALS


5c **C. P. Grade—** **5c**
Generous Quantities

... and in glass containers—unconditionally guaranteed!
big fully illustrated valuable
FREE catalog—a real 25c handbook
Equip a complete home or pro-
fessional laboratory with chemicals, apparatus, mi-
croscopes and instruments at real bargain prices. Save
money! Send 3c for postage. Get your copy NOW!
KEMKIT SCIENTIFIC CORP.
397-A Bridge St. Brooklyn, New York

MINIATURE GAS ENGINES

SYNCR O ACE

The time-tested, efficient,
stream-lined power plant
for model airplanes. Im-
mediate deliveries, with
all 1938 im-
provements.
Now only
\$13.75, at
your dealers.



The New SYNCR O BEE

This tiny gasoline engine
is now ready. Only 4 1/2" bore, 3/4" stroke. Weighs
approximately 4 oz. Only \$12.50 at your dealer's.
ELECTRIC JIG SAWS
7200 strokes per minute. No motor required. Ideal
for all model builders. Sold by dealers everywhere.
Write for literature.

SYNCR O DEVICES, Inc. 513 Boyden Bldg. Detroit, Michigan

Learn to Sail on Your Dining Table

(Continued from page 38)

the wind. To prevent the possibility of an accidental jibe, good sailors generally steer their boats before the wind so that the breeze comes over the stern slightly on the opposite side to that on which the mainsail is riding.

JIBING, coming about, and all the other maneuvers of your model boat on the table have been done by hand, by actually taking hold of the boat and moving it from one position to another. In an actual sailboat, of course, the rudder does this steering job. Study how your model rudder acts as you twist the tiller back and forth and you will note that it works just opposite to the manner of an automobile steering wheel.

If you want to turn a boat to port, the left side looking toward the front end or bow, you swing the tiller to starboard, the right side, and vice versa. It is well to remember, however, that if a boat is drifting backward, the action of the rudder is just the reverse. And if you ever sail a real boat and become confused about the steering or setting of the sails, simply turn the tiller toward the sail. This will always swing the boat into the wind and bring it to a standstill.

One vital difference between table-top and actual sailing is in knowing the exact direction of the wind. At

home, you can have the wind blow from any direction merely by moving the fan, but under actual sailing conditions, you will have to adapt the boat and its sails to the prevailing wind. Thus it is extremely important to know from just what direction the wind is blowing, and to keep on the lookout for sudden changes.

SAILORS sometimes fasten a pennant to the truck, or topmast part of the mast, or attach bits of yarn to the shrouds at the side of the mast, to show wind direction. But old salts just face in the general direction of the wind and turn their heads from side to side until the hum of the air passing both ears is of equal intensity. Then they know they are facing directly into the breeze. Try this in front of your electric fan. If the noise of the motor is not too loud, you should soon get the hang of this trick.

By the time you have become proficient in maneuvering your model boat on its miniature sea, you will have learned most of the fundamentals of sailing. The practice indoors enables you to visualize exactly what is happening in each maneuver you make when you begin handling a full-size craft on real water. By becoming a table-top mariner first, you will save time, and avoid dangerous mistakes.

Cleaner Air To Breathe

(Continued from page 77)

soda water sparkle and fizz. Your exhaled breath contains about four or five percent of it. In the small proportions ordinarily encountered, in fact, carbon dioxide is entirely harmless. When people are breathing in a closed chamber like a submarine or a stratosphere-balloon gondola, however, containers of soda lime (a mixture of caustic soda and quicklime) must be provided to absorb it, or it would rise to such a percentage as to endanger life. This is because a high concentration of carbon dioxide in the atmosphere interferes with the elimination of the same gas as a waste product of our bodies.

AIR that you exhale is about 140 times as rich in carbon dioxide gas as the atmosphere is, and a simply constructed bit of apparatus will demonstrate the difference in a striking way. Obtain a pair of similar flasks and place in each one an equal quantity of clear limewater. This is prepared by shaking several grams of lime with about 100 cubic centimeters of water and filtering the resulting solution. Fit the flasks with two-hole stoppers, and join them with tubing providing a T connection at the center. Attach a piece of rubber tubing to this T connection to serve as a mouthpiece. Fit one of the flasks with a piece of glass

tubing that dips below the surface of the limewater, and the other with a rubber-tubing outlet closed with a small cork and slit along the side with a razor, to form a one-way valve.

Now, when you suck through the mouthpiece, outside air will bubble through the limewater in the first flask. When you exhale through the mouthpiece, your breath will bubble through the limewater in the second flask. Without further manipulation, the operation of the apparatus is entirely automatic in directing the air streams through the proper vessels.

TRY breathing continuously, in and out, through the rubber-tubing mouthpiece. Soon you will notice that the limewater in both flasks is turning milky. This is due to the precipitation of calcium carbonate (precipitated chalk) by the reaction of the carbon dioxide with the limewater. The liquid in the second flask will be much the milkier of the two, plainly demonstrating that there is a far higher percentage of carbon dioxide in your exhaled breath than in the surrounding atmosphere.


An easy way to obtain carbon dioxide for chemistry experiments is to put a chunk of dry ice (frozen carbon dioxide) in a bottle and let it "melt."

Wind-Driven Generator Supplies Current for Summer Home

(Continued from page 63)

completed armature with several coats of insulating varnish, allowing each to dry thoroughly.

Mark the field pole pieces so they can be replaced in their original positions; then remove them and the field coils. Make a wooden winding form, the center of which is the same size as the opening in the original field coils. Wind two new field coils in same direction as the old ones, each consisting of 220 turns of No. 20 celenamel wire (approximately 1½ lb. will be needed altogether). Connect exactly like the original field coils. Wrap coils with cotton tape and cover with insulating varnish or shellac. Replace the pole pieces and new coils, and connect ends to same brush and ground terminals as before.



The housing raised to show the bearings

Shape the end of a 1-in. pipe (long enough to extend below the larger supporting pipe) as in Fig. 10 and mount

the generator as shown at Fig. 5. Drive a short piece of 1¼-in. pipe over the 1-in. pipe and solder a metal bearing cover to it. A set of ball bearings and raceway to fit the 1-in. pipe may be picked up in an automobile wrecking yard.


Note that the pipe sizes are trade sizes, not the actual sizes in inches. The outside diameters of pipes may vary somewhat, so it is advisable to select pieces that will make a fairly snug fit when one is placed inside the other.

The collecting rings and brushes are shown at Figs. 10 and 11. The generator should be placed as high as possible, clear of surrounding objects. The mounting tower may be either wood or angle iron.

An adjustable vane is provided (Figs. 3 and 5), so the generator will not be injured by strong winds. The tension on the vane may be set so the generator speed will be nearly constant in varying wind speeds, because as the wind increases, the vane tends to fold at right angles to the propeller, and this moves the propeller away from the wind.

To stop the generator, the vane is pulled around by a flexible metal cable so it is at right angles to the propeller. The lower mounting bracket for the vane is shown in Figs. 6 and 7.

The propeller is cut from 20-gauge galvanized steel 3 ft. square (Fig. 8).



Collecting rings and brushes at bottom of pipe support. Connections are No. 10 wire

It is bolted to the generator pulley. The wire reinforcing ring is threaded through the holes, and the ends are bolted or brazed together. Bend the blades to slant about 30 deg.

Two No. 10 wires are brought out from the brushes on the tower to the cut-out coil and connected as in Fig. 12. The lower brush is connected to the generator terminal, which is the positive pole. At Fig. 5 it will be seen that the generator terminal passing through the vane-support bracket is thoroughly insulated with fiber washers from the surrounding metal.

It is advisable to include an ammeter in the circuit (Fig. 12); this may also be obtained from a wrecking yard.

No Extra Cost FOR GREATEST SKID PROTECTION YOU'VE EVER SEEN!

IMPARTIAL TESTS PROVE THAT THIS NEW KIND OF TIRE GIVES YOU QUICKER NON-SKID STOPS THAN TIRES PRICED UP TO 70% MORE!



HERE'S a new kind of tire that changes the rain-drenched road under your car from a "skid trap" to a dry track! It's the new Goodrich Silvertown Tire with the Life-Saver Tread!

This amazing tread acts like a whole battery of windshield wipers. It sweeps the water right and left—forces it out through the deep drainage grooves—makes a DRY TRACK for the rubber to grip—giving you the *quickest* non-skid stops you've ever seen!

And when you can get this real life-saving skid protection, *plus* Golden Ply protection against high-speed blow-outs AT NO EXTRA COST why gamble on tires? See your Goodrich dealer or Goodrich Silvertown Store about a free demonstration.



Here's Proof from America's Largest Independent Testing Laboratory

BOTH regular, and also the premium-priced tires of America's six largest tire manufacturers were submitted to a series of exhaustive road tests made over a three months period by us, to determine their resistance to skidding and wear, with the following results:

"NON-SKID—The new Goodrich Silvertown with the Life-Saver Tread gave greater skid resistance than any other tire tested, including those tires listed at from 40% to 70% higher in price."



PITTSBURGH TESTING LABORATORY



The new Goodrich SAFETY Silvertown

SKID PROTECTION OF LIFE-SAVER TREAD • GOLDEN PLY BLOW-OUT PROTECTION

YOUR WORK WILL SHOW THE DIFFERENCE

How good a job a man intends to do is often reflected in his choice of a saw. For a sloppy job any saw will do. But for your guidance to clean-cut results, remember that Atkins Silver Steel Saws (hand, hack, circular, etc.) have held the respect of carpenters, cabinet makers and metal workers since 1856. Their true set teeth, taper grinding and famous tempered "silver steel" help craftsmen to do their best work—and save a great deal of energy.

E. C. ATKINS AND COMPANY
428 S. Illinois St., Indianapolis, Ind.

SEND FOR 40-page Home Workshop Book, "HOW TO DO IT." Send only 10c to cover handling.

ATKINS

SILVER STEEL SAWS

60 POWER TELESCOPE \$2.19

VARIABLE EYEPIECE 30X-40X-60X

NEW! Three telescopes in one, 8 different magnifications. 20 power for ultra-bright images with 40 & 60 power for extra long range. Guaranteed to bring distant objects, people, sports events, ships, moon, stars, etc., 60 times as close.

Most powerful made for anywhere near the money. Closes in less than a foot in length. Multiple lens system. 30 mm. objective lens. 6 sections. Directions included for using as a compound lens microscope. American made. We pay the postage. Only \$2.19. Address Dept. 63.

BROWNSCOPE CO., 5 W. 27th ST., NEW YORK

CHEMICALS

Laboratory
Apparatus and Glassware
Send 5¢ for Catalog CP1
Dept. 1111

BIOLOGICAL SUPPLY COMPANY
1176 Mt. Hope Ave. Rochester, N. Y.

EARN BIG PROFITS

with new RANGER SCOOTER

Earn big profits selling or renting marvelous, improved RANGER SCOOTER. 120 miles per gallon—80 m. p. h. Safe. Sturdy. Good territory still open. Get your share of the big profits possible! **EASY TERMS FINANCED.** Write for Free folder. Special Low Agents' Prices. Hurry!

MEAD CYCLE CO.
Dept. FE-249, CHICAGO, U. S. A.

When answering advertisements,
please write your name and
address plainly.

FREE! LABORATORY APPARATUS
BIOLOGICAL SUPPLIES
MICROSCOPES
TELESCOPES
CHEMICALS

New complete 32-page catalog lists hundreds of items of interest to amateur and professional experimenters. Save Money—Buy Direct. Send now! It's FREE and full of bargains and valuable information.

J. H. WINN MFG. CO., Dept. 108, 124 W. 23 St., New York

DIESELECTRIC PLANTS

Electric Starting—Remote Control

Make electricity the Diesel way for less than one cent per kilowatt. 110 volt A. C. or D. C. for direct lighting or 88 volt for battery charging. Saves 75%. Easily installed—occupies small space. Larger plants available.

WITTE ENGINE WORKS
222-C Oakland Ave., KANSAS CITY, MO.



Small Machine Belts Laced with Copper Wire



THE efficient operation of home workshop machines depends to a greater extent than generally realized upon the belts. While endless belts are excellent, they soon stretch so that proper speed cannot be maintained unless some arrangements are made to tighten them. Laced belts are the alternative, but many amateur mechanics seem to find it difficult to do the lacing. It is really a simple process, especially if No. 22 plain copper wire is used. This wire, which can be purchased in spools at any hardware store, is quite satisfactory for small belts.

Put the belt over the two pulleys where it is to be used and pull moderately tight. Mark with a try-square where the joint comes, and cut off the belt. Then file off the point of a 2½-in. (eightpenny) finishing nail to form a punch for making the holes. A belt punch will do this work, but it is difficult to obtain one that will make a small enough hole.


The two outside holes should be about ¼ in. in from the edge of the belt; the remaining holes are spaced about ⅜ in. apart. When they have been punched, run a groove from each hole to the end

of the belt on the pulley side. This groove is for the wire to lie in so that it will not come in contact with the pulley.


Cut off a piece of the copper wire about five times as long as the width of the belt and run it halfway through hole 3. Then run the end marked A up through hole 8, down through 4, up through 9, down through 4, up through 9 again, down through 5, up through 10, down through 5, and up through 10, and loop the end C around the cross wire between holes 5 and 9. Lace end B down through 8, up through 3, and then through the remaining holes in the same way.

Make sure that the wires lie side by side on the inside. If you allow them to cross over one another, the pulley will wear them out. After the ends have been curled under as at C, lay the belt, underside down, on an iron block and tap the joint lightly with a hammer. A belt laced in this manner runs without bumping and will last longer.

Bear in mind that the hair side of leather belting should be run against the pulley.—R. A. HILL.



STARTING AT HOLE NO. 3, LACE WIRE END A AS SHOWN, AND SECURE END AT C. THEN LACE WIRE END B (TO THE LEFT) IN THE SAME MANNER



Lacing the belt is a simple operation if the diagrams above are followed carefully

A Quick Way of Making Good Ground Glass

WHEN a sheet of ground glass is needed, first obtain a piece of 2-in. plank a little wider and longer than the glass to be ground. One surface must be planed perfectly smooth. Set the glass (old glass photographic plates with the emulsion washed off are good for this purpose) on the plank and inclose with strips of wood slightly thinner than the glass.

Take a piece of the same plank as large as the first piece and cement sheet rubber (an old inner tube will serve) to the smooth surface; then provide an edging of wooden strips, put on so that it extends just a little beyond the rubber face, and attach a wooden handle to the center of the back. Dust a little emery powder on the glass and sprinkle

with a few drops of water. Dampen the rubber face of the upper block and place another sheet of glass upon it. The moistened rubber will hold this glass in place and permit it to be rubbed with a constantly changing motion over the lower sheet.

After about ten minutes grinding, wash off the emery and observe the results. Where an unground patch is seen on either plate, tear off a piece of thick paper, place behind the glass so as to force it forward, and continue grinding.—W. W.

Subscribers are requested to notify us of change of address four weeks in advance of the next publication date. Please give both old and new address.

BLUEPRINTS

for Building a Fisherman's Boat

DESIGNED for fishing and all-around use, our new outboard boat should suit every member of the family. It is light, handles well with oars, and is perfectly adapted for small motors, while with a larger motor it becomes a fast runabout of excellent riding qualities. The boat can be built either 9 ft. 3 in. or 11 ft. 6 in. in length. Total cost should be less than \$25, but will vary in different localities. The blueprints (Nos. 344-345) cost only 50 cents, and full-size patterns will be drawn to order for \$1.50 extra.

A few of our many blueprint projects are given below. Our latest complete list will be sent free upon receipt of a stamped, self-addressed envelope.



BOATS

All-Purpose Boat, 11 ft. 5 in. long, for sails, outboard motor, or rowing, 331-R.....	.75
Camper's Utility Boat, 11 ft. 2 in. long, canvas-covered, for outboard motor or rowing, 281-R.....	.50
Canoe, 16-ft. canvas-covered kayak, with sail, 192-193-194-R.....	1.00
Canvas-Covered Duck Boat, 13 ft. 6 in. long, 279-R.....	.50
Fisherman's Outboard Boat, 9 ft. 3 in. or 11 ft. 6 in. long, for motors from 3 to 15 h.p.; can also be rowed, 344-345.....	.50
Folding Duck Boat, 13 ft. long, 170-R.....	.50
High-Speed Boat for Small Outboard Motors (7 ft. 11 in. long), 257-R.....	.50



Instructions and blueprints for a midget boat 9 ft. long (No. 339-R) cost 50 cents

Midget Boat or Pram, 9 ft. long, for oars, sail, or outboard motor, 339-R.....	.50
Motorboat-Rowboat, 16 ft. long, decked hull, for use with outboard or inboard drives or oars, 149-R.....	.50
Racing Runabout (13 ft. long, for outboard motor), 261-262-R.....	.75
Racing Sailboat Blackcat (13 ft. 4 in. long, 5 ft. beam, weighs 250 lb., Marconi rigged), 321-322-323-R.....	1.00
Runabout, 15½ ft. long, detachable top, seats that fold into bunks; for use with outboard or inboard drives, 175-176-177-R.....	1.00
Sectional Rowboat, 9 ft. 8 in. long, can be used with small outboard motor; all wood construction, 340-341-R.....	.75
Sport Runabout (9 ft. 8 in. long, 43-in. beam, for small outboard motors), 309-310-R.....	.75
Utility Rowboat, 13-ft., (can also be sailed or driven by outboard motor), 224-R.....	.50



MODELS

Aircraft Carrier Saratoga (18 in.) and a Flush-Deck Destroyer (6½ in.), 226-227-R.....	.75
Alabama, famous Confederate bark-rigged steam sloop, 21½-in. hull, 335-336-337.....	1.00
Barbary Pirate Galley or Felucca (20 in.), 44-45-R.....	.75
Barneget Lighthouse, 10½ in. high, 298A.....	.25
Bluenose, the famous fishing schooner, 17½-in. hull, 110-111-112-R.....	1.00
Brig Malek Adhel (20-in. hull; frame-and-plank construction), 304-305-306-R.....	1.25
Clipper Ship Sea Witch (9½-in. hull), 219.....	.25



You will have no difficulty in constructing this boat from Blueprint Nos. 344-345

Cody Coach, 13 in. long, with plans for horses, 144-145-146-R.....	1.00
Constitution ("Old Ironsides"), 21-in. hull, 57-58-59-R.....	1.00
Cruiser U.S.S. Indianapolis (12-in.), 216.....	.25
Experimenter No. 3, flying airplane, 20½-in. wing spread, 20 in. long, 348A.....	.50
Freighter, Ocean (14-in.), 271.....	.25
H. M. S. Bounty (8½-in. hull), 254.....	.25
Liner President Lincoln (14¾ in.), 325.....	.25
Mayflower (24 in.), 83-84-85-R.....	1.00
New Bedford Whaleboat (14-in.), 326-R.....	.50
Privateer Swallow, Baltimore clipper, (13-in. hull), 228-229-230-R.....	1.00
Racing Yacht Seascout (42-in.), 106-107-R.....	.75
Sovereign of the Seas, clipper ship (20¾-in. hull), 51-52-53-R.....	1.00
Spanish Treasure Galleon (24 in.), 46-47.....	.50
Trading Schooner (17½-in. hull), 252-253.....	.50
U. S. Battleship Texas (3-ft. hull), 197-198-199-200.....	1.00

(Construction kits are available for some of these models. See page 11.)



FURNITURE

Bed and Armchair Table, 339A.....	.25
Bookcase, modernistic, 88.....	.25
Double-Decker Bed, 277A.....	.25
Four-Leaf Card Table, 239A.....	.25
Gate-Leg Table with Round Top, 24.....	.25
Hanging Wall Cabinet, 280A.....	.25
Modernistic Lamps (three designs), 93.....	.25
Reading Tables, Two, 88.....	.25
Sewing Table, 1.....	.25
Silverware Chest on Stand, 256A.....	.25
Smoking Stand, Modern, 238A.....	.25
Tea Wagon (turning), 13.....	.25
Telephone Table and Stool, 18.....	.25
Tilt-Top Table (turning), 140.....	.25



RADIO SETS

All-Wave Portable Receiver (two tubes, operated by battery), 217-R.....	.50
Amateur Short Wave Receiver, 155.....	.25
Amateur Radio Transmitter, 183-184.....	.50
Five-Tube Short Wave (A.C. or D.C.), 223.....	.25
Full Electric Headphone Set, 130.....	.25
One Tube (battery operated), 103.....	.25
Screen-Grid Set, 109.....	.25
Short-Wave Converter Unit, 137.....	.25



MISCELLANEOUS and TOYS

Arbor with Two Seats and Garden Gate, 9.....	.25
Baby's Crib and Play Pen, 26.....	.25
Garden Trellises, 34.....	.25
Naval Gun Model (3-in.), Boy's Coat Rack of Indian Design, and Costume Brooch of Sheet Copper, 345A.....	.25
Portable Microscope Kit, 220.....	.25
Rowboat Back Rest, Band-Iron Electric Wall or Table Lamp, and Jig-Sawed Garden Figures, 347A.....	.25
Rustic Settee, 156A.....	.25
Toy Electric Motor, Softwood Coffee Table, and Scottie Pins, 332A.....	.25
Turned Costume Jewelry, 275A.....	.25
Wood-Mosaic Serving Tray and Novelty Wooden Book Ends, 297A.....	.25

Popular Science Monthly
353 Fourth Avenue, New York

Send me the blueprint, or blueprints, numbered as follows:

I am enclosing.....dollars.....cents

Name.....

Street.....

City and State.....

Please print your name and address clearly.

"THIS IS THE LIFE!"



BUILD

YOUR OWN MASONITE GARDEN TABLE AND DIVAN

All the comforts of home—in the garden! The table is made of a carriage wheel, with a durable, weather-resistant MASONITE TEMPERED PRESWOOD top. You can leave it outside all year round.

The luxurious lawn-barrow divan is just the thing for long, lazy days in the sunshine. A natural companion for the carriage-wheel table. Sturdy. As easy to move as a wheelbarrow. Sunshade and seat are MASONITE TEMPERED PRESWOOD. Backrest is MASONITE QUARTERBOARD.

Mail the coupon today for FREE working drawings and assembly instructions for these two new MASONITE masterpieces. Start building them at once with Genuine MASONITE!



MASONITE

THE WONDER WOOD OF A THOUSAND USES

A MISSISSIPPI PRODUCT

SOLD BY LUMBER DEALERS EVERYWHERE

Copyright 1938, Masonite Corporation

FREE!

MASONITE CORPORATION

Dept. PS-8

111 W. Washington St., Chicago, Ill.

Please send me FREE working drawings and assembly instructions for the MASONITE garden table and divan.

Name.....

Address.....

City.....State.....

NEW FREE CAMERA CATALOG

Whole new volume devoted exclusively to cameras and camera equipment. Sensational values! See how much you can save... see the wide selection of famous-make cameras and supplies, the completeness of stocks. See what you're missing if you don't make this book your camera buying guide! Don't wait. Send for it today. It's yours. It's FREE!

WHOLESALE RADIO SERVICE CO. INC.
NEW YORK, N.Y. • CHICAGO, ILL. • ATLANTA, GA.
100 SIXTH AVENUE • 101 W. JACKSON BLVD. • 555 PEACHTREE STREET
BOSTON, MASS. • BRONX, N.Y. • NEWARK, N.J. • JAMAICA, L.I.

WHOLESALE RADIO SERVICE CO., INC.
100 SIXTH AVENUE, NEW YORK, N. Y.

Rush FREE Camera Catalog No. 72-9H8

Name.....

Address.....

City..... State.....

PASTE COUPON ON PENNY POSTCARD

Print Your Own
Cards, Stationery, Advertising, labels, paper, circulars, tags, etc. Save money and time. Sold direct from factory only. Junior Outfit \$9.00, Senior Outfit \$17 and up. Do popular raised printing like engraving with any of our presses. Print for Others, Big Profits. Pays for itself in a short time. Easy rules sent. Write for free catalog of outfits and all details. Kelby Presses, E-33, Meriden, Conn.

PHOTO ENLARGEMENTS
Is Photography your hobby? Do you want a profitable easy business at home? Make PHOTO ENLARGEMENTS for yourself and others. Your cost 3c each and less. The Ideal Photo Enlarger is AUTOMATIC. No experience required. Also COPIES any picture \$8.94 COM-PLITE. Interesting circular FREE
IDEAL-X, 127 East 25th Street, NEW YORK

SHIP MODEL KITS
\$1.50 and up
Also Blueprints—Woods—Tools—And hundreds of Scale fittings in White Metal, Brass and Boxwood.
Send 18 cents (will be refunded) for this Catalogue to
GENE'S 510 EAST 11 STREET
Dept. P. S., New York City

Explore NEW ROADS
You can get a thrill out of driving again. Try the less frequented highways. Let the Hail Auto Compass direct you along any unfamiliar road any time, in any weather. No worry, no delays. Only \$2.95 at your dealer. Two-piece model \$1.95. Write for circular.
Hull Mfg. Co., P. O. Box 246-E4, Warren, Ohio

Earn Wood-working \$\$ IN YOUR SPARE TIME!

Learn how you can build up a profitable spare or full-time business in your own home. This new book "How to Make Money in Woodworking" is crammed with practical tested ideas, plans, and suggestions. Tells you exactly what to make, how to make it and how to sell it. Describes plans that have worked for others. Woodworking, the new way is light, pleasant and profitable. Send only 10c and complete book will be mailed postpaid. Satisfaction guaranteed or money refunded. Write to Dept. BS38.

Delta Mfg Co. 600 E. VIENNA AVE. MILWAUKEE, WIS.

Decorative Baskets of Thin Wood

(Continued from page 70)

groove. The weaving strips are 3/16 in. wide and 1/16 in. or less in thickness. These strips cannot be cut in the usual manner of passing the strip between the saw and the ripping fence, because with such small work this process is very dangerous. The following method is safer: The material is first passed through the saw to make both sides parallel. A block of wood is fastened onto the miter gauge so that its end is the required thickness of the strip away from the saw blade. The ripping fence is adjusted so that the material for the strips presses lightly against this block, as illustrated. The miter gauge is then removed, and the material is passed through the saw. As the ripping fence must be adjusted for each strip, it will speed up the process if several pieces of material of the same width are passed through the saw in succession.

The strips are sanded and fastened in place in the groove of the bottom piece with a good grade of glue. There



Gluing the strips into the upper ring. At right is the form used in the construction

around the top of the form, place the remaining part of the strip alternately on the outside of one upright and on the inside of the next. When the basket has been completely circled, the remaining end of the strip is placed on the inside of the same upright as the other end. The strip is then pressed towards the bottom of the basket. Because of the decrease in size, it will be necessary to pull on the ends of the strip as it is moved downwards. The ends are cut where they overlap on the inside of the upright, forming a continuous strip.


The following strips are placed on alternate sides of the uprights with their joints on the inner side. When the weaving is complete, the upper ring is glued in place. The top is woven in a similar manner. One end of each of the crosspieces is fastened with small nails or staples, and the weaving strips are slipped over the other end. It is best to leave off the outer crosspieces till the weaving is complete. They are slipped in place, and all of the strips are securely fastened. The surplus ends of the weaving strips are removed with shears.

The type of finish is left to the worker. The basket shown is made completely from white pine, but the rings, bottom, and uprights are stained. Two coats of shellac produce a pleasing finish.


How to Plane Woods with Twisted Grain

UNLESS a special low-angle cabinet-maker's block plane is available, it is often difficult to plane hardwoods which have a highly figured, twisted grain. To use an ordinary smooth plane, sharpen the cutter carefully, making the angle a little less than usual. Then grind the edge of the cap iron, or shaving splitter as it is sometimes called, until it is about 1/32 in. thick. Place this edge very close to the cutting edge of the cutter, and assemble the two parts by tightening the screw hard. Use plenty of pressure in clamping the cutter, and adjust for a shallow cut.

Use an even pressure in planing, because planes fitted in this way have a tendency to chatter. You will be surprised at the almost polished surface the plane will produce.—GEORGE MAGEE.



Weaving the top. One end of each cross strip is left unfastened for this purpose



Cutting surplus ends from weaving strips

should be an even number of these strips. The space between each strip at the bottom should be between 1/4 and 3/8 in.

To retain the correct shape of the basket while it is being woven, it is best to use a form. This consists of two disks of wood turned to fit the inside of the basket and separated by a spindle. These disks are turned slightly small to allow for the weaving strips.


The weaving strips are soaked overnight in water. With the form in place, one end of the first strip is placed on the inside of one of the uprights. Working

Sails for the 'Alabama' Model

(Continued from page 69)

sheets are fastened to the clews and drawn down tight to the sheet bitts. The leech lines are hitched to the leeches, and the buntlines to the foot; these lines are then rove through the blocks on the yard and through others tied to the eyes of the rigging abaft the masts, and to the deck through the lubber hole. These should hang slack on the fore side of the sails.

The halyards are small chain for the length of the topmast, then cord, finishing with a two double-block tackle to port at the fore and to starboard at the main. The lifts are as shown in the



A simplified diagram to make clear the rigging of spanker, gaff topsail, and try sails

rigging plan, but hanging down abaft the yards.

Topgallant sails are similarly fixed. The sheets are cord leading down to the fife rail. The halyards are also cord, with a double and single-block tackles on the side opposite to the topsail halyards.

Royals are the same with two single-block halyard tackles, reversing sides again.

Braces were clearly shown on the rigging plan. Although they appear as if only on one side; the other side is, of course, the same. The fore lower and topsail braces go through blocks hooked to bolts in the mainmast cheeks. Fore topgallant and royal braces reeve through double blocks seized to the stay and through others hung from the crosstrees, abaft. Main and topsail braces go to the bumpkins and finally to blocks hooked to bolts in the covering board about $\frac{1}{4}$ in. abaft the bumpkins.

One may have the yards set straight across or at any angle. I have mine at half a right angle, as if the wind (if any) were on the quarter. This looks well and allows the rigging detail to be seen. When you have the yards at the desired angle, adjust the lower ones horizontally with the topping lifts, and the others with the sail sheets.

Stunsails are made to the patterns shown, just like the other square sails. A stunsail boom is half the length of its respective yard and one third the thickness. Two thirds of the boom extends beyond the iron, and the inner

end is lashed to the yard. The stunsail yard is half the length of its boom. The halyard hitches to it one third from the inner end, goes through a block tied to the boom irons or eyes and continues up to the masthead and down to the deck or the top. The tack goes through a block at the boom end and then aft to act as a brace. The double sheet ties to the yard abaft the standing sail to the windward side. On the other side, to the leeward, however, the sheet ties to the yard before the standing sail. I belayed the fore stunsail braces to the main fife rail, and the main to the poop handrail.

The *Alabama* carried five boats. I have placed a cutter and a launch amidships, open to show the thwarts and oars, and two lifeboats with their covers on abaft. There is an open gig over the stern. These boats should be black outside and white inside. They hang with two double-block tackles. As our ship appears as if under way, I swung them inboard.

Two anchors are needed. These should be not less than $1\frac{1}{2}$ or more than 2 in. long. The original anchors probably were of the iron-stock pattern. On my model the chain cables are unbent, but they may be shown if desired.

According to Captain Semmes, the *Alabama* flew the long pennant at the main, the red cross of St. George at the fore, and the white ensign with blue, starry cross at the peak.

Almost any kind of base or cradle may be used, but as the model has sails set, the so-called "graving-dock" type would not be appropriate.

That would appear to be all, and I think you will agree that you have by now a very good-looking and interesting model ship.

This concludes not only the Alabama article, but the entire great series of model articles prepared for POPULAR SCIENCE MONTHLY by Captain McCann (see P.S.M., Feb. '38, p. 78). The lines above were written by him only a few days before his death. They were the last to come from his pen.

Molding Sand Improved by Adding Paste

BY ADDING wall-paper paste to molding sand, I have found it possible to get sharper and better-detailed castings of small, intricate parts. About two heaping tablespoons of the dry paste are mixed thoroughly with one pint of fine, dry sand. This is sprinkled with water and mixed until the sand is wet enough to mold. If it holds together without leaving the hand wet, it is just right. Let the mold dry before pouring the metal; it will become quite hard and hold its shape much better than plain sand. Any that is left over will harden, but it can be used again by adding a little water.—EARLE S. COLLINS.

Making these repairs with SMOOTH-ON No. 1 is like finding money!

Stopping leaks at screw threads, gaskets, press-fit joints, seams, connections, cracks, etc., in water, steam, gas, air or smoke pipes, boilers, furnaces, fire pots, heaters, tanks, radiators, sinks, troughs, etc.

Tightening loose wood screws, bolts, nuts, handles, drawer pulls, hinges, locks, hooks, casters, stems, bases, etc.

SMOOTH-ON No. 1 has enabled thousands of householders and home mechanics to make the above and similar repairs at absurdly low cost—to restore full usefulness to many impaired household appliances that otherwise would have required expensive replacement.

Smooth-On No. 1 hardens and its adhesion and expansion in doing so effect a tightness of parts or a seal against leakage that withstands pressure, heat, cold, vibration, moisture and chemical action. The Smooth-On restores original efficiency quicker, with less effort and at less expense than by any other practical repair procedure. Try Smooth-On (no heat, special tools or previous experience required). Your worst repair becomes simple and you can make annual savings that amount to a substantial figure.

Many Smooth-On repairs can be made in various ways. The one which produces the best results most economically is easily determined from the instructions and diagrams in the free Smooth-On Home and Auto Repair Booklet.

Mail the coupon for your copy and get Smooth-On No. 1 in 7-oz. or 1 or 5-lb. can from your hardware store.

SMOOTH-ON MFG. CO.
Dept. 58,
574 Communipaw Ave.
Jersey City, N. J.

Please send the free Smooth-On Repair Book.



Write for
FREE BOOK



Do it with SMOOTH-ON

SHOOT BENJAMIN GENUINE COMPRESSED AIR PISTOLS WITH SAFETY

For Target & Small Game—Economical—Accurate—Practical—Adjustable Force—Amazing Maximum Velocity—Safe—Single Shot with Bolt Action—Hammer Fire—Hair Trigger Safety—No. 1 or 2 or BB Price \$7.50—Repeater \$12.00—No. 177 and 22 Single Shot Air Rifles \$4.95—Single Shot BB Air Rifle \$6.00—22 Shot BB Repeater Air Rifle \$7.50—at Dealer or Direct—No license required—SAFE. The Only Genuine Compressed Air Pistols & Rifles for Shooting BB on the Market. Full Details—Targets—Free—Write Today for Introductory Offer.
BENJAMIN AIR RIFLE CO., 553 Marion St., St. Louis, Mo., U. S. A.



WORLD'S GREATEST all around ELECTRIC TOOL

DRILLS
GRINDS
SANDS
SAWS
POLISHES
SHARPENS

The new WHIZ ELECTRIC TOOL is the handiest, most useful power tool ever made. Not a delicate instrument but a real rugged tool, equally effective for both power and precision work. Drills through 1/2 inch iron plate in 42 seconds or engraves intricate designs on jewelry. Handles any material: Metals - Woods - Alloys - Plastics - Glass - Steel - etc. Saves time. Eliminates tedious labor. Plug into any socket AC or DC, 110 volts. Chuck 1/2 inch capacity. Ball bearing thrust. Powerful triple-gear motor. Worth its weight in gold. "A" to a mechanic or handy man. STANDARD MODEL with normal speed (uses 50 different accessories). Instantly interchangeable. Special introductory price for limited time, only \$6.95. Accessory outfit (Value \$2) includes set of drills, mounted 1 1/2 inch grinder, sanding discs, cutting wheels, mounted brush polishing wheel, carving bur, etc. FREE with each outfit ordered NOW! We pay postage on all shipments. Will send C O D if desired.

ONLY
6.95
POSTPAID

10-DAY TRIAL—MONEY BACK GUARANTEE

Special "2-SPEED" MODEL combines Normal Speed and High speed in one outfit (uses 200 accessories) only \$8.95 complete, with same accessory outfit value \$2. FREE.

PARAMOUNT PRODUCTS CO.
Dept. 80 48 West 48th St. New York, N. Y.

BUILD THE CUTTY SARK

2 R. MODEL OF THE FAMOUS CLIPPER SHIP

Everything including CARVED WOOD HULLS, Painted Sides, Decks, Cast-Metal Life-boats, Anchors, Rigs, Sailing Wheel, Chimes, Mast, Spars, Rigging, Cement, Colored Lacquer - Full-Size Plans and Instructions.

Send for Catalog and all the new models. 10¢. **WILL ADAMS & SONS COMPANY, INC.** 28 West 19th Street, New York

Complete kit material perfect building easy.
2.50
plus 10¢ postage

NOW ONLY \$5.00

Over 7,000 GHQ Gas Engine Kits have been sold at \$8.50. Now is your chance to buy the *New Improved* kit for \$5.00. Absolutely complete with coil, plug, etc. Send only \$1. — Shipped Exp. Coll. for balance same day. Catalog 3c.

A screwdriver is the only tool needed. Average assembly time 30 minutes.

GHQ MOTORS, 854S East 149 St., New York, N. Y.

PHOTOGRAPHIC ALMANAC

Free!

Free 1938 Almanac includes:
(1) Special month-by-month Photographic Calendar. (2) Authoritative photographic article. (3) Handy Exposure Table, Exposure Guide. (4) 100 pages of still & movie cameras, film, lenses, enlargers, chemicals—everything photographic—made at low prices. **ALL GUARANTEED** on 10 Day Money Back Trial. Used or unused accepted in trade. Write for Free copy. Central Camera Co., (Est. 1888) 236 S. Wabash, Dept. 9-2, Chicago

Only \$18.90 at Bass

Dollina O

Special camera with 4.5 mm. Vario lens. Anamorphic F 4.5 mm. Vario shutter speeds: 1/25, 1/50, 1/100, 1/200, 1/400, 1/800, 1/1600, 1/3200, 1/6400, 1/12800, 1/25600, 1/51200, 1/102400, 1/204800, 1/409600, 1/819200, 1/1638400, 1/3276800, 1/6553600, 1/13107200, 1/26214400, 1/52428800, 1/104857600, 1/209715200, 1/419430400, 1/838860800, 1/1677721600, 1/3355443200, 1/6710886400, 1/13421772800, 1/26843545600, 1/53687091200, 1/107374182400, 1/214748364800, 1/429496729600, 1/858993459200, 1/1717986918400, 1/3435973836800, 1/6871947673600, 1/13743895347200, 1/27487790694400, 1/54975581388800, 1/109951162777600, 1/219902325555200, 1/439804651110400, 1/879609302220800, 1/1759218604441600, 1/3518437208883200, 1/7036874417766400, 1/14073748835532800, 1/28147497671065600, 1/56294995342131200, 1/112589990684262400, 1/225179981368524800, 1/450359962737049600, 1/900719925474099200, 1/1801439850948198400, 1/3602879701896396800, 1/7205759403792793600, 1/14411518807585587200, 1/28823037615171174400, 1/57646075230342348800, 1/115292150460684697600, 1/230584300921369395200, 1/461168601842738790400, 1/922337203685477580800, 1/1844674407370955161600, 1/3689348814741910323200, 1/7378697629483820646400, 1/14757395258967641292800, 1/29514790517935282585600, 1/59029581035870565171200, 1/118059162071741130342400, 1/236118324143482260684800, 1/472236648286964521369600, 1/944473296573929042739200, 1/1888946593147858085478400, 1/3777893186295716170956800, 1/7555786372591432341913600, 1/15111572745182864683827200, 1/30223145490365729367654400, 1/60446290980731458735308800, 1/120892581961462917470617600, 1/241785163922925834941235200, 1/483570327845851669882470400, 1/967140655691703339764940800, 1/1934281311383406679529881600, 1/3868562622766813359059763200, 1/7737125245533626718119526400, 1/15474250491067253436239052800, 1/30948500982134506872478105600, 1/61897001964269013744956211200, 1/123794003928538027489912422400, 1/247588007857076054979824844800, 1/495176015714152109959649689600, 1/990352031428304219919299379200, 1/1980704062856608439838598758400, 1/3961408125713216879677197516800, 1/7922816251426433759354395033600, 1/15845632502852867518708790067200, 1/31691265005705735037417580134400, 1/63382530011411470074835160268800, 1/126765060022822940149670320537600, 1/253530120045645880299340641075200, 1/507060240091291760598681282150400, 1/1014120480182583521197362564300800, 1/2028240960365167042394725128601600, 1/4056481920730334084789450257203200, 1/8112963841460668169578900514406400, 1/16225927682921336339157801028812800, 1/32451855365842672678315602057625600, 1/64903710731685345356631204115251200, 1/129807421463370690713262408230502400, 1/259614842926741381426524816461004800, 1/519229685853482762853049632922009600, 1/1038459371706965525706099265844019200, 1/2076918743413931051412198531688038400, 1/4153837486827862102824397063376076800, 1/8307674973655724205648794126752153600, 1/16615349947311448411297588253504307200, 1/33230699894622896822595176507008614400, 1/66461399789245793645190353014017228800, 1/132922799578491587290380706028034457600, 1/265845599156983174580761412056068915200, 1/531691198313966349161522824112137830400, 1/1063382396627932698323045648224275660800, 1/2126764793255865396646091296448551321600, 1/4253529586511730793292182592897102643200, 1/8507059173023461586584365185794205286400, 1/17014118346046923173168730371588410572800, 1/34028236692093846346337460743176821145600, 1/68056473384187692692674921486353642291200, 1/136112946768375385385349842972707284582400, 1/272225893536750770770699685945414569164800, 1/544451787073501541541399371890829138329600, 1/1088903574147003083082798743781658276659200, 1/2177807148294006166165597487563316553318400, 1/4355614296588012332331194975126633106636800, 1/8711228593176024664662389950253266213273600, 1/17422457186352049329324779900506532426547200, 1/34844914372704098658649559801013064853094400, 1/69689828745408197317299119602026129706188800, 1/139379657490816394634598239204052259412377600, 1/278759314981632789269196478408104518824755200, 1/557518629963265578538392956816209037649510400, 1/1115037259926531157076785913632418075299020800, 1/2230074519853062314153571827264836150598041600, 1/4460149039706124628307143654529672301196083200, 1/8920298079412249256614287309059344602392166400, 1/17840596158824498513228574618118689204784332800, 1/35681192317648997026457149236237378409568665600, 1/71362384635297994052914298472474756819137331200, 1/142724769270595988105828596944949513638274662400, 1/285449538541191976211657193889899027276549324800, 1/570899077082383952423314387779798054553098649600, 1/1141798154164767904846628775559596109106197299200, 1/2283596308329535809693257551119192218212394598400, 1/4567192616659071619386515102238384436424789196800, 1/9134385233318143238773030204476768872849578393600, 1/18268770466636286477546060408953537745699156787200, 1/36537540933272572955092120817907075491398313574400, 1/73075081866545145910184241635814150982796627148800, 1/146150163733090291820368483271628301965593254297600, 1/292300327466180583640736966543256603931186508595200, 1/584600654932361167281473933086513207862373017190400, 1/1169201309864722334562947866173026415724746034380800, 1/2338402619729444669125895732346052831449492068761600, 1/4676805239458889338251791464692105662898984137523200, 1/9353610478917778676503582929384211325797968275046400, 1/18707220957835557353007165858768422651595936550092800, 1/37414441915671114706014331717536845303191873100185600, 1/74828883831342229412028663435073690606383746200371200, 1/149657767662684458824057326870147381212767492400742400, 1/299315535325368917648114653740294762425534984801484800, 1/598631070650737835296229307480589524851069969602969600, 1/1197262141301475670592458614961179049702139939205939200, 1/2394524282602951341184917229922358099404279878411878400, 1/4789048565205902682369834459844716198808559756823756800, 1/9578097130411805364739668919689432397617119513647513600, 1/19156194260823610729479337839378864795234239027295027200, 1/38312388521647221458958675678757729590468478054590054400, 1/76624777043294442917917351357515459180936956109180108800, 1/153249554086588885835834702715030918361873912218360217600, 1/306499108173177771671669405430061836723747824436720435200, 1/612998216346355543343338810860123673447495648873440870400, 1/1225996432692711086686677621720247346894991297746881740800, 1/2451992865385422173373355243440494693789982595493763481600, 1/4903985730770844346746710486880989387579965190987526963200, 1/9807971461541688693493420973761978775159930381975053926400, 1/19615942923083377386986841947523957550319860763950107852800, 1/39231885846166754773973683895047915100639721527900215705600, 1/78463771692333509547947367790095830201279443055800431411200, 1/156927543384667019095894735580191660402558886111600862822400, 1/313855086769334038191789471160383320805117772223201725444800, 1/627710173538668076383578942320766641610235544446403450889600, 1/1255420347077336152767157884641533283220471088892806901779200, 1/2510840694154672305534315769283066566440942177785613803558400, 1/5021681388309344611068631538566133132881884355571227607116800, 1/10043362776618689222137263077132266265763768711142455214233600, 1/20086725553237378444274526154264532531527537422284910428467200, 1/40173451106474756888549052308529065063055074844569820856934400, 1/80346902212949513777098104617058130126110149689139641713868800, 1/160693804425899027554196209234116260252220299378279283427737600, 1/321387608851798055108392418468232520504440598756558566855475200, 1/642775217703596110216784836936465041008881197513117133710950400, 1/1285550435407192220433569673872930082017762395026234267421900800, 1/2571100870814384440867139347745860164035524790052468534843801600, 1/5142201741628768881734278695491720328071049580104937069687603200, 1/10284403483257537763468557390983440656142099160209874139375206400, 1/20568806966515075526937114781966881312284198320419748278750412800, 1/41137613933030151053874229563933762624568396640839496557500825600, 1/82275227866060302107748459127867525249136793281678993115001651200, 1/164550455732120604215496918255735050498273586563357986230003302400, 1/329100911464241208430993836511470100996547173126715972460006604800, 1/658201822928482416861987673022940201993094346253431944920013209600, 1/1316403645856964833723975346045880403986188692506863889840026419200, 1/2632807291713929667447950692091760807972377385013727779680052838400, 1/5265614583427859334895901384183521615944754770027455559360105676800, 1/10531229166855718669791802768367043231889509540054911118720211353600, 1/21062458333711437339583605536734086463779019080109822237440422707200, 1/42124916667422874679167211073468172927558038160219644474880845414400, 1/84249833334845749358334422146936345855116076320439288949761690828800, 1/168499666689691498716668844293872691710232152640878577899523381657600, 1/336999333379382997433337688587745383420464305281757155799046763315200, 1/673998666758765994866675377175490766840928610563514311598093526630400, 1/1347997333517531989733350754350981533681857221127028623196187053260800, 1/2695994667035063979466701508701963067363714442254057246392374106521600, 1/5391989334070127958933403017403926134727428884508114492784748213043200, 1/10783978668140255917866806034807852269454857769016228985569496426086400, 1/21567957336280511835733612069615704538909715538032457971138992852172800, 1/43135914672561023671467224139231409077819431076064915942277985704345600, 1/86271829345122047342934448278462818155638862152129831884555971408691200, 1/172543658690244094685868896556925636311277724304259663769111942817382400, 1/345087317380488189371737793113851272622555448608519327538223885634764800, 1/690174634760976378743475586227702545245110897217038655076447771269529600, 1/1380349269521952757486951172455405090490221794434077310152895542539059200, 1/2760698539043905514973902344910810180980443588868154620305791085078118400, 1/5521397078087811029947804689821620361960887177736309240611582170156236800, 1/11042794156175622059895609379643240723921774355472618481223164340312473600, 1/22085588312351244119791218759286481447843548710945236962446328680624947200, 1/44171176624702488239582437518572962895687097421890473924892657361249894400, 1/88342353249404976479164875037145925791374194843780947849785314722499788800, 1/176684706498809952958329750074291851582748389687561895699570629444999577600, 1/353369412997619905916659500148583703165496779375123791399141258889999155200, 1/706738825995239811833319000297167406330993558750247582798282517779998310400, 1/1413477651990479623666638000594334812661987117500495165596565035559996620800, 1/2826955303980959247333276001188669625323974235000990331193130071119993241600, 1/5653910607961918494666552002377339250647948470001980662386260142239986483200, 1/11307821215923836989333104004754678501295896940003961324772520284479972966400, 1/22615642431847673978666208009509357002591793880007922649545040568959945932800, 1/45231284863695347957332416019018714005183587760015845299090081137919891865600, 1/90462569727390695914664832038037428010367175520031690598180162275839783731200, 1/180925139454781391829329664076

Twenty-One-Mile Parachute Leap

(Continued from page 43)

and float back to earth under umbrellas of silk. A few weeks before his fourteenth birthday, he got permission from one of the balloonists to go up and parachute back.

That first leap was the beginning of a lifetime of thrilling activity. It wasn't long until young Dunkel was building his own hot-air balloons and parachutes. His mother helped him cut out and sew his first outfit. Although Dunkel began using parachutes about 1913, he never bought one ready-made until 1926.

THOSE early parachutes used with the hot-air balloons were of the attached type. They opened at the instant the balloonist abandoned his craft. After Dunkel graduated from balloons to airplanes, he still used the attached 'chute.

Along about 1919, Dunkel got the idea that he could jump from a plane, fall through space for a while, then open his parachute. So he went to work and constructed a crude pack. He tied the folded 'chute with grocery string, went aloft, and jumped out. He broke the string with his hands, and pushed the parachute out until the wind caught it, and it opened. He made about twenty such jumps, until one day the silken folds refused to open as they should. By frantic effort and considerable luck, he got the 'chute open just before he reached the ground. Thereupon he abandoned the grocery-string pack, and waited for something more reliable to come along.

At that time, various parachute makers, jumpers, and inventors were experimenting with free types of packs, which could be released at any time after jumping. Dunkel remembers the device originated by a Japanese, which was a modified jack-in-the-box. The parachute was literally shot out of a wooden container by powerful steel springs. Another man had an arrangement of steel wires and canvas that could be set, somewhat like a trap, to shoot the parachute into the air. This worked all right until the jumper's body got in the way of the catapulted 'chute. Finally, Floyd Smith and Leslie Irving, working for the Government, developed a successful pack-type parachute. At first this was produced only for military use, and it was not until 1926 that Dunkel could get one.

FOR a number of years, Dunkel worked with designers and manufacturers in an effort to perfect parachutes. He was, and still is, a parachute salesman. During his most active period, he made as many as ten leaps in an afternoon, to show prospective purchasers how his wares worked. In St. Louis, he demonstrated the quick-opening features of a certain parachute by leaping from a plane only 250 feet above the ground. As the ship was in a power dive at the time, he left it at

a speed of more than 200 miles an hour, sufficient to snap the parachute open instantly. Such a stunt would have been foolhardy with one of his early balloon-type models, Dunkel says. These were made of pure Japanese silk, and were inclined to split easily.

During all of his twenty-eight years of plunging through space, Dunkel has never been seriously injured. He has lost a few square inches of skin, but he has never broken a bone. He is proud of that record. But he is even more proud of the fact that, as a parachute instructor, he has dropped more than 1,000 novices into space without a single fatality.

DURING the 1932 National Air Races at Cleveland, Dunkel and a pilot took Marie McMillen to a height of 24,800 feet and Dunkel helped her get out of the plane, to drop to earth and establish a world's altitude record for women jumpers. He helped Miss McMillen train for this and other spectacular leaps.

His job as Chief of Parachute Participation at the National Air Races makes it necessary for him to supervise preparations for as many as sixty jumps a day. All the equipment used by the various jumpers must go through his hands and receive his approval before it can be used.

For many years, Dunkel has been collecting parachutes as a hobby. Stored away in his Cleveland home, he has fifty-six different kinds, representing virtually every type that has been used in America. Study of these parachutes, plus his years of jumping from the sky, has provided the groundwork for Dunkel's sensational proposal for a plunge from the stratosphere.

POPULAR SCIENCE Question Bee

To SEE how you fared in the Question Bee on page 50, compare your answers with the correct list below. For every one that you got right, give yourself four points. A total score of 80 to 88 is good; 92 to 100 is excellent.

QUESTIONS

- | | | | | |
|------|-------|-------|-------|-------|
| 1. d | 6. b | 11. b | 16. b | 21. d |
| 2. b | 7. b | 12. c | 17. b | 22. d |
| 3. d | 8. c | 13. c | 18. a | 23. a |
| 4. b | 9. d | 14. d | 19. b | 24. c |
| 5. c | 10. b | 15. b | 20. c | 25. b |

PICTURES

- | | |
|----------------|-------------------|
| 1. dead center | 6. headstock |
| 2. cone pulley | 7. bed |
| 3. faceplate | 8. tail spindle |
| 4. tool rest | 9. tailstock |
| 5. live center | 10. spindle clamp |

Alkalize with Alka-Seltzer AT ALL DRUG STORES

GOOD BYE TO WORRY AND VACATION TIME IS HERE

GOOD BYE TO UPSET STOMACHS AND HEAD-ACHES TOO, MY DEAR

GOOD BYE TO MORNING MISERY, GOOD BYE TO DAILY GRIND

WITH ALKA-SELTZER IN OUR GRIP, WE LEAVE DULL CARE BEHIND.

Beware - Alkalize

An Alka-Seltzer Tablet in a glass of water makes a sparkling pleasant-tasting solution. Drink it and it gives quick relief from Head-aches, Sour Stomach, Distress after meals and other common ailments. It also helps overcome excess acid condition so often associated with these troubles.

30¢ & 50¢ PER DOZ. AT THE GLASS OR AT DRUG STORE

TUNE IN THE NATIONAL BARN DANCE SATURDAY NIGHT NBC NETWORK

SHIP MODEL FITTINGS

Build the 4-mast Barque, California

Accurate, detailed blue prints of this handsome, steel barque. Complete fittings and construction sets for steam trawler and other popular models including the "Hartford." Send 20c (coin) for new illustrated catalog. Illustrates hundreds of items, fittings and complete kits.

A. J. FISHER
1002-2 Elsworth Ave. Royal Oak, Mich.

FREE Sensational OFFER

2 FENCING SWORDS FREE

FENCING
WORLD'S FINEST SPORT
HARMLESS-EXCITING FUN

Develops strong body and alert mind. HARMLESS. The spring-steel 3-foot-long foils (swords) are equipped with rubber buttons. Aluminum cup-shaped hand guards. Our De Luxe foils are built for hard usage. Complete set of two foils (swords) and free instruction booklet, only \$1.50 postpaid. Two additional fencing swords FREE for limited time. (Regular price of these two sets of foils \$3.95.) ORDER NOW.

ALL-AMERICAN FENCERS GUILD
Dept. B5P 45 West 40th St., New York, N. Y.

Earn BIG MONEY MAKING ELECTRIC RAZORS at home!

BUY ALL PARTS READY FOR INSTANT ASSEMBLY NO TOOLS NEEDED

Make \$5 or more on Every Razor You Sell

Just think, a complete \$15 type razor for \$1.95 or less. You can make \$5 or more for fifteen minutes of your spare time. Start AT ONCE, big or small—with one unit or 100—make your own electric razor or sell to others—you can profit both ways!

Costs \$1.95 (In lots of three in quantities less)

Just like the highest priced ones. Earn money assembling electric razors. In spare time or full time. Buy parts from us complete matched units ready to be put together to make one of the most popular standard high quality Electric Razors. The same selling quality parts now used in Shavers selling in the higher price brackets. Write for information or order your first unit at once and prove the money making possibilities to your own satisfaction.

SIMMONS MFG. CO.
126 W. North Ave., Chicago, Ill.

FREE
Screwdriver and in the case with order for set in it. You need no other tool or equipment.

SIMMONS MFG. CO.
126 W. North Ave., Chicago, Ill.

- ☐ Enclosed \$2.25 for samples.
☐ Ship C.O.D., \$2.25, I will pay small postage charge.

Name

Address

HANDEE
TOOL OF 1001 USES

ACTUALLY A WHOLE SHOP FULL OF TOOLS IN ONE

Uses 200 different accessories, instantly interchangeable in easy-working chuck. For faster, better work on all materials, at home, in shop or take to job. Plugs in any AC or DC socket, 110 volts.

STANDARD, 18,000 s.p.m. \$10.75 postpaid, 2 Accessories Free.

DELUXE (Illustrated), 25,000 s.p.m. \$18.50 postpaid, 6 Accessories Free.

GET A DEMONSTRATION at Hardware, Tool Dept. Stores or order on 10 Days Money-back Trial Catalog Free.

CHICAGO WHEEL & MFG. CO.
1101 W. Monroe St., Dept. S, Chicago, Ill.

Grinds
Drills
Polishes
Engraves
Sharpens
Cuts
Cleans
Sands
Cuts
Saws

HANDEE Project Book Easy to use. Explains in many interesting objects. 25c

HOT WATER from SUNSHINE

Complete drawings and specifications for building a Solar heater. Thousands in constant use. Factory information never before available for one dollar.

EARL A. BROWN & SONS
8440 N. E. 1st Ave., Miami, Florida

BIG MONEY Assembling NEW BOAT!

GIVEN \$5

Double-Blade paddle now given with your "KAY" Kayak—*if you hurry!*

MEAD GLIDERS Dept. D-55, CHICAGO, U. S. A.

Make big money on each 20 lb. Mead KAYAK you easily assemble at home in a few days from complete "kit to go." Kit at amazing LOW PRICE! Sea-worthy, Fast! Snap-put together! Complete Sailing Rig, a few dollars extra. A so 2 other portable paddles and models AND 2 portable outboard motor, sail, oar models. Rush 10c for illustrated folder and \$5 Paddle Gift Offer!

25 So. Market St.
Dept. D-55, CHICAGO, U. S. A.

WIRELESS Pocket TUBELESS BATTERYLESS Radio

WORLD'S SMALLEST REAL PERFORMING

Small as a matchbox, it performs like a big radio. With a single "push" button, it gives you clear, crisp, natural tone. NO CRYSTALS to adjust—NO UPKEEP—only one moving part. Self-contained "breakphone" unit gives superior performance. IS NOT A TOY! THOUSANDS OF SATISFIED OWNERS—Many report amazing reception and distance. Sent complete with instructions for use in homes, offices, hotels, boats, in bed, etc. TAKES ONLY A SECOND TO CONNECT. No hook-ups to any current. Six colors available.

SEND NO MONEY! Pay postman only \$2.99 plus postage on arrival or send \$2.99 (Check, M. O., Cash) and yours will be sent postpaid. **GUARANTEED** A most unusual value. **ORDER NOW!**

TINYTONE RADIO CORP., Dept. P-2, KEARNEY, NEBRASKA

Photographs Under the Microscope

(Continued from page 75)

surface of a camera lens to determine its cleanliness, or the extent of scratches or other damage. If you cannot place the lens on the microscope stage, try holding it directly beneath the stage and focusing the microscope on it through the stage hole. Incidentally, this is also a good way to examine a microscope objective lens.

EVERY photograph reproduced in a magazine or newspaper is the result of a complicated series of photographic steps whereby the image is broken up into a series of dots of varying sizes which collect ink from the printing-press rollers and transfer it to the paper. By examining the half-tone reproductions in this magazine with your microscope, you can see these tiny dots, and observe how they vary in different parts of the pictures. Engravers who make half-tone plates for reproducing pictures, often employ a compound microscope to examine the condition of the dots and the progress of etching a zinc or other metallic plate with acid, and to make delicate corrections with sharp instruments, by altering the shapes of the dots.

Another possible use of the microscope in the amateur darkroom is as an aid in the retouching of miniature negatives. Usually, 1 by 1½-in. negatives, or those of similar small size, are never retouched to correct such faults as pinholes—tiny clear spots resulting from dust on the film. However, with the lower powers of a compound microscope, sufficiently fine tools, and a steady hand, it is possible to perform certain alterations on a small negative. In watching the movement of the brush or other instrument through a compound microscope, remember that the image is reversed, so that you have to move your hand to the right to make the brush move apparently to the left.

MANY of the chemicals used in photography, such as pyrogallol acid and hydroquinone, produce crystals that make interesting objects for study. To prepare a specimen, dissolve some of the chemical in water, place a few drops in the center of a clean glass slide, and let it stand until the water has evaporated.

By removing the regular lens from a photographic enlarger and substituting a compound microscope, mistituting a compound microscope, microphotographs, which are extremely small photographs, can be made. Positive motion-picture film or lantern-slide plates are best for this, because of their fine grain. Suppose you are going to employ a 3¼ by 4-in. lantern-slide plate. With a glass cutter, reduce it to strips from ½ to ¾ in. wide. Use one of these as a focusing screen by placing it, coated side up, on the microscope stage. Place a negative in the enlarger in the usual manner, and focus

the microscope until a clear but greatly reduced image of it is formed on the strip of lantern-slide plate. A magnifying glass is useful for telling when the image is sharpest.

Now turn out the enlarger lamp, and replace the lantern-slide strip with a fresh, unexposed strip. Starting at one end, make a series of exposures, giving each a different time. Develop, fix, and wash the strip in the usual manner. After it is dry, examine the images with your microscope, and select the best for permanent preservation. If the negative was placed in the enlarger in the proper position, the tiny microphotograph on the lantern-slide plate will be right-side-to when placed with the emulsion side down and examined through the microscope. With a glass cutter, separate the best pictures from the others, place a little balsam on the emulsion side, and mount them in the centers of standard 1 by 1½-in. slides.

YOU'LL always draw a laugh if you include one of these tiny photographs when you are showing your slide collection to a friend, particularly if the picture happens to be a likeness of the friend. Usually, observation of such pictures through the microscope should be made at the same power or a power lower than that used in projecting the image with the enlarger. Usually, also, the picture will show quite a bit of grain, in spite of the relative fineness of grain in lantern-slide plates or positive film. When observed at low or moderate powers, however, the grain will not be objectionable. This stunt, incidentally, should clear up a common bit of fog in connection with microscopy. Many people do not know the difference between a photomicrograph and a microphotograph. When you take a highly enlarged picture of a tiny object through a microscope, you are making a photomicrograph. When you reduce a photographic image, in the manner described, to produce a tiny positive print, you are making a microphotograph. When the microscope works in reverse, the words have to be reversed, too!

Novel Electric Motor Has Two Rotors

ELECTRIC motors of radical new type have been produced in Germany to drive an experimental locomotive. Between the rotating armature and the stationary field it has an additional rotor—a thin set of windings shaped like a hollow cylinder, turning concentrically with the armature but on independent bearings. The scheme is declared to solve the problem of operating electric locomotives on alternating current of the "single-phase" type, with only one overhead power wire.

This One



H2NH-RFC-CFPC

Gus Gives Tips on Outboard Motors

(Continued from page 54)

and Harry a chance to laugh—and they took it.

"My guess, Professor," Gus remarked as he lifted the engine up on his bench, "is that your trouble was caused by pre-ignition. Let's see, now." He disconnected the spark-plug wires, took out a plug, glanced at it, and held it up for Clapp's inspection. What little of the porcelain insulator hadn't been burned away was covered deeply with gummy black carbon.

"THERE'S the cause of your troubles," he explained. "With burned-up plugs like this, your motor may start a little hard, but once you get it going it will run well enough until the plugs get hot. Then pre-ignition will start, and your engine will slow down, and vibrate, and act as if it were starving for gas. But when the engine slows down, the spark plugs cool off, and then the engine runs normally again—until the plugs' temperature goes back up. After a while, when the plugs and the engine are real good and hot, cutting the ignition off doesn't have any effect—she goes right on firing. That's what happened to you. I'll put in new plugs, and we'll try her out. Fill a barrel with water, will you, Harry?"

Harry filled the barrel, and Gus clamped the motor to a block in the vise so that its propeller was in the water. Then he mixed some gasoline and oil, poured it into the fuel tank, and pulled the starting cord. The engine took off easily enough, and the water in the barrel started to churn. Gus, with his head cocked to one side, listened for perhaps a minute, and then shut it off.

"That's a good engine, Professor," he said, "but it's had darned bad treatment. Better leave it here for a day or two, and let me go over it for you."

"Nonsense!" snapped Professor Clapp. "So long as it runs—"

"That will be fine, Mr. Wilson," Beverly interrupted sweetly. "I'll stop for it tomorrow, and take it out to the lake with me. Oh, I forgot to tell you, Dad, I'm staying with Aunt Molly tonight. Seems like a year since I saw a really good movie. Mother's alone, so I asked Mr. Jones to take you out with him—that must be he honking the horn outside now. I'll drive out tomorrow afternoon."

CONSIDERABLY to Gus Wilson's surprise, Harry had the shop open when he drove up at a quarter to eight the next morning, and the outboard was out on the workbench.

"Hey, what's the meaning of all this industry?" Gus demanded.

"Bev's coming in to see you about that outboard early this morning," Harry explained. "I thought you'd like to give it the once-over before you talked to her about it."

"Bev, hey!" Gus said. "You're get-

(Continued on page 102)

ting sort of familiar with the customers' daughters, aren't you?"

"Shucks, I've known her all my life!" Harry told him. "Say, Gus, do you know why she talked her father into buying this outboard? Because she's going in the girls' race up there at the lake Saturday—that six-mile race they have every year."

"Well, she won't get anything out of it," Gus said. "Not in the professor's old rowboat. She'll be up against a lot of those little doodlebug hydroplanes that can do twenty-five easy."

HARRY grinned. "She's got a hydroplane—only her father doesn't know it yet," he explained. "That old one of Bill Hazzard's—the one he ripped the bottom out of in the marathon last year. He gave it to her, and she's had it fixed up so it's as likely as not to hold together for six miles. So now it's up to us to fix up this engine. She's not going in that race to lose."

"And that's the honest truth," said Beverly, from the doorway. "How about it, Mr. Wilson—you're with me, aren't you?"

"Well," Gus said, "I'll see what I can do."

With Harry helping, and the girl keeping up a rapid fire of not-so-dumb questions, Gus took out the fuel line and blew it clear. Then, picking up the gasoline strainer, he showed Beverly the dirt caked in the mesh. "This thing's put in to keep the dirt out of the carburetor," he said, "but hardly anybody ever thinks of cleaning it off occasionally."

"Here now, watch how I take this flywheel off. You can't pry it." Removing the nut, he struck the shaft end on top with a hammer. The flywheel came off easily, exposing the magneto.

"In the magneto, trouble usually comes from the contact points," the veteran mechanic went on. "Clean them off with 00 sandpaper, like this, and if they're worn or pitted put in new ones. And be sure to check up on the width of the gap from time to time."

BEVERLY put in a question. "Is vibration, like Father noticed, always caused by—what do you call it?—pre-ignition?"

"Oh, no," Gus replied. "It could have been a loose bearing on the steering pivot, a bent propeller, loose mounting on the boat, or poor compression in one cylinder."

By this time, Harry had the carburetor taken apart. "This is just a simplified version of the carburetor on your car," Gus pointed out. "It needs an occasional cleaning of this needle valve that regulates the gas flow. And use your head when you prime it. The only time you need to do this is when the motor is cold. More outboards are kept from starting by priming them when they're hot than by almost any

FACTORY-TO-YOU SAVES YOU 50%

also **\$30.00** FOR YOUR **AND UP** OLD RADIO **AS A SPECIAL TRADE-IN ALLOWANCE!**

SENSATIONAL NEW 1939

17 TUBE WORLD-WIDE

MIDWEST

30 DAYS FREE TRIAL

Today's sensational new radio headliner! Bigger, better, more powerful, more luxurious. Delight in high-priced, 17-tube performance at ordinary 8-tube set cost. Glorious reception, richer tone... all-wave, world-wide entertainment... 10,000 mile range.

Buy At Wholesaler's Price

Secure \$30.00 or more trade-in allowance on your old radio. Save 50% at amazingly low factory-to-you price. Get 30 days FREE Home Trial. Easy payments. Money Back Guarantee.

Send for FREE 1939 Catalog

MIDWEST RADIO CORPORATION
Dept. 59AA, Cincinnati, Ohio

PASTE COUPON ON 1c POSTCARD... OR WRITE TODAY!

MIDWEST RADIO CORPORATION Dept. 59AA Cincinnati, Ohio	Name.....
Send me your new FREE catalog and complete details of your liberal 30-day FREE trial offer and factory-to-you wholesale prices.	Address.....
	Town..... State.....
	User-Agents Make Easy Extra Money. Check Here <input type="checkbox"/> for details.

When answering advertisements, please write your name and address plainly.

WOOD-WORKING SUPPLIES!



New 100 page book contains most complete list of woodworking supplies in the world—Standard American woods cut-in-slabs at bargain prices, rare imported woods, Veneers, ply-woods, inlays, overlays, carved legs, mouldings, decorations, ornamental hardware, scroll saw patterns, wood-finishing instructions—How to make Venetian Blinds at 1/4 store prices. Send only 10c for Catalog No. 10 to—
Craftsman's Wood Service Co.
2722 S. Mary Street Chicago, Ill.

WHAT STRANGE POWERS
Did The Ancients Possess?

WHERE was the source of knowledge that made it possible for the ancients to perform miracles? These wise men of the past knew the mysteries of life and personal power. This wisdom is not lost—it is withheld from the masses. It is offered freely TO YOU, if you have an open mind. Write for free sealed book. Address: Scribe YZG

The ROSICRUCIANS
San Jose (AMORC) California

GOING!...GOING!...GONE!



TALK ABOUT ANTIQUES! Get a whiff of that rancid old tobacco the duck in the derby is smoking! Even the auctioneer is groggy, so it must be pretty strong stuff!



"GOSH ALL HEMLOCK!" protested Mr. Felt Hat. "Why not give folks around you a break? Here—clean the goo out of your pipe and then switch from that stinko brand to



"A Milder Tobacco!" Have you tried Sir Walter Raleigh? Not ever? Well, have some of mine right now! It's a very, very mild burley blend, and just as fragrant as it can be!"



GOING AT 15¢ for two heaping ounces! Sold! Sold to a million and more men who want a mild brand of tobacco that smells good to the man smoking, and to his friends, too!

Switch to the brand of grand aroma



FREE BOOKLET tells how to make your old pipe taste better, sweeter; how to break in a new pipe. Write for your copy today. Brown & Williamson Tobacco Corporation, Louisville, Kentucky. Dept. Y-88.

HOW TO TAKE CARE OF YOUR PIPE

TUNE IN Tommy Dorsey and his orchestra. Every Wednesday, coast-to-coast NBC Red Network.

Gus Gives Some Tips on Outboard Motors

(Continued from page 101)

other cause. Then there's overheating—"

"And what makes an outboard overheat?" Beverly wanted to know.

"Same as in a car—running out of oil or water."

Harry chuckled. "Imagine a boat running out of water!"

By way of reply, Gus dug into the motor's cooling system. "Easiest thing you know," he said. "If the water pump isn't clean, and the feed pipe and connections aren't tight, it's a case of 'water, water everywhere' and not a drop for the cylinder jacket where it's needed. Just look at the dirt and hunks of string in this feed pipe!"

WITH deft, sure motions, he removed the cylinders to inspect the pistons and rings. "You're lucky," he commented. "The rings seat well, and the cylinder walls gleam all over, showing that they're not scored. Now let's take a peek at the gear box." Removing the cover, he washed out the box with kerosene and inspected the gears closely. "Everything's O.K. here," he reported. "No pitting, no chipping."

Packing the gear box with grease and oiling the cylinder walls and bearings, Gus reassembled the motor. He signaled Harry to put the motor back in the barrel, put in fuel, and started it.

Gus listened to the motor for a couple of minutes, and then nodded his satisfaction. "She'll do," he said. "Maybe she'll kick that patched-up hull along too fast for it to hold together. Know how to swim, Bev?"

"Of course," said Beverly, "but this is a boat race. Oh, and Mr. Wilson, I'll need Harry to help me get the motor adjusted on the boat. Saturday morning—early—would do."

"That's a busy day around here, Bev. Well, all right. But he's got to be back Saturday evening—sure!"

IT WAS a little after four o'clock Saturday afternoon when the telephone rang. Gus went into the office and took up the receiver.

"That you, Mr. Wilson?" said the voice at the other end of the wire. "Well, I won! The old boat just held together long enough. You certainly put-put that outboard right! Next time you come up this way, I'm going to mix you something nice in the silver bowl they gave me."

"That's fine!" Gus said. "I'm glad you won—mighty glad, Bev! And now do me a favor, and start Harry home."

"Oh, Harry," Beverly said. "It would be a shame to make him start home now, Mr. Wilson. He's got that power lawn mower we bought three years ago going! No one ever has been able to start it, so now Dad thinks he's just grand. Couldn't you get along without him until Monday morning, please?"

"What's the use?" asked Gus, and hung up.

Free TO MOTORISTS WITH OIL EATING CARS



If Your Motor Wastes Oil and Gas—if It Has Lost That "New Car" Power Speed and Quiet, Send Coupon Below For FREE Sample of Miner's Amazing Mineral Discovery

SAVES OIL SAVES GAS

Nearly a half-million motorists have used this revolutionary method of cutting oil and gas waste caused by worn rings and cylinders. Savings up to 50% reported. Give your car new power, pep, speed and quiet with this amazing mineral discovered in the Rocky Mountains. Awarded A. T. L. Seal of Approval.

Why Pay Up to \$151.37 for New Rings and Reboring?

If worn rings and cylinders cause your car to be an oil and gas eater—before you spend a lot of money, try Ovrhaul. Give it an opportunity to do for you what it has done for thousands of others. Here are costs of new rings and rebore on a few 1935 models; Chevrolet \$50.00; DeSoto, \$62.50; Dodge, \$59.20; Ford, \$50.00 to \$55.00; Cadillac, \$151.37; Packard, \$112.50.

ENDORSED

By Member of
Society Automotive Engineers
National Aeronautical Assn.
Detroit Soc. of Engineering
Pentiac Engineers Club

Let us send you L. H. Smith's complete report which shows that the compression of a badly worn 6-cylinder motor was increased 32.4% and brought back to within .09 points of its original new car efficiency. Such tests conclusively prove the sensational merits of Ovrhaul.

TAKES PLACE OF NEW RINGS AND REBORE!

Quickly placed through spark plug openings and at a fraction of the cost of new rings and rebore, this amazing mineral fills in and plates worn rings and cylinder walls. Ovrhaul gives your motor increased compression. Cuts oil consumption, increases gas mileage, adds new power and speed, with other substantial benefits of new rings and rebore. Ovrhaul has been thoroughly tested and proved by impartial laboratories and great Universities in the United States and abroad. Proved harmless to finest motors.

INSTALLED IN 30 MINUTES!

Ovrhaul works on the mineral plating principle—No special tools needed. No car tie-up. No danger of ruining motor by grinding cylinder walls—works in while you drive, saves you time and money. Gives you months of extra car use. A single application lasts up to 10,000 miles.

SAMPLE FREE!

If your car is wasting oil and gas, before you spend up to \$151.37 for new rings and rebore—send your name and address on the coupon below for a free sample of this amazing mineral and full details of a real money-making opportunity. Air mail reaches us overnight.



PHONE, WRITE OR WIRE TODAY!

Let us send you free sample which every salesman is furnished for demonstration. Let us show you, with their permission, ACTUAL earnings of our distributors. Let us show you how you can start in this business NOW—before all territories are assigned. The market is there—we have the product—are you the man? Let's find out. Write, phone or wire today.—B. L. Mellinger, Pres.

OVRHAUL CO.,
J-984, Los Angeles, Calif.

Free SAMPLE COUPON

B. L. Mellinger, Pres.

Ovrhaul Co., J-984, Los Angeles, Calif.

Without cost or obligation, send me at once a FREE SAMPLE. Also show me your big money-making plan.

Name

Address

City

State

Make and Year of Car

Paste on postcard and mail—air mail reaches us overnight



Grace Moore
in Magnolia Gardens
.... *Chesterfield time is*
pleasure time everywhere

They Satisfy